


# SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1906, by Munn & Co.]


Vol. XCIV.—No. 9.  
ESTABLISHED 1845.

NEW YORK, MARCH 3, 1906.


10 CENTS A COPY.  
\$3.00 A YEAR.




A TYPICAL HIGH-POWER MOTOR BOAT UNDER WAY.



TRIPLE-SCREW MOTOR TORPEDO BOAT BUILT BY YARROW. SPEED,  $25\frac{1}{2}$  KNOTS.



THE "ARGO," WHICH MADE A RECORD OF 31.7 MILES PER HOUR ON JULY 4, 1905, IN A SPEED TRIAL ON THE HUDSON RIVER.



A SCENE AT THE SPORTSMEN'S SHOW HELD IN MADISON SQUARE GARDEN, NEW YORK CITY.

## SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN &amp; CO., - - Editors and Proprietors

Published Weekly at  
No. 361 Broadway, New York

## TERMS TO SUBSCRIBERS

One copy, one year for the United States, Canada, or Mexico.....\$3.00  
One copy, one year, to any foreign country, postage prepaid. \$0 10s. 5d. 4.00

## THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845).....\$3.00 a year  
Scientific American Supplement (Established 1876).....5.00  
American Homes and Gardens.....3.00  
Scientific American Export Edition (Established 1878).....3.00  
The combined subscription rates and rates to foreign countries will be furnished upon application.  
Remit by postal or express money order, or by bank draft or check.  
MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, MARCH 3, 1906.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

## FOR A HIGH-LEVEL LOCK CANAL.

The letter of President Roosevelt, transmitting to Congress the report of the Board of Consulting Engineers on the Panama Canal, together with the report of the Isthmian Canal Commission and letters from Secretary Taft and Chief Engineer Stevens, marks an important step in the settlement of the vexed question of the type of canal which is the best suited to the conditions at the Isthmus of Panama. The letter of the President leaves no doubt whatever that he is strongly in favor of a high-level lock canal. Furthermore, an analysis of the vote taken both by the Board of Consulting Engineers and by the Isthmian Canal Commission, to say nothing of the individual opinion of the Secretary of War, and the present Chief Engineer of the Canal, establishes the fact that the judgment of the majority of American engineers is in favor of a lock canal.

On the other hand, we must not lose sight of the fact that, if we take toll of the strictly engineering opinion of the many able minds that have been requested or appointed by the President to give their ripe judgment on this question, we find that a majority have given their vote in favor of a canal at sea level.

Thus, of the thirteen members of the International Board of Consulting Engineers, eight report in favor of a sea-level and five in favor of a lock canal; while of the six members of the Canal Commission, five are in favor of a lock canal, and one in favor of a sea-level canal. This, on the face of it, would show a balance of nine for and ten against a canal at sea level; but of the five members of the Canal Commission that voted against the sea-level canal, two, namely, the chairman, T. P. Shonts, and the governor of the canal zone, Charles E. Magoon, are not engineers. Therefore, the strictly engineering vote will stand nine in favor of a sea-level canal, and eight against it; and of these nine three are American engineers. Among the American engineers the opinion stands three in favor of the sea-level canal and eight in favor of a high-level canal with locks.

The majority report of the Board of Consulting Engineers recommends a canal at sea level with one tidal lock, having a bottom width of 150 feet, enlarged to a bottom width of 200 feet where the slopes are nearly vertical, and with a depth of 40 feet. The estimated cost is \$247,000,000, and the estimated time of construction twelve to thirteen years. The minority report, which is indorsed by the Canal Commission and by President Roosevelt, calls for the construction of a lock-and-lake canal, embodying many of the features of the Lindon W. Bates plan as published in the SCIENTIFIC AMERICAN, February 3, 1906. It contemplates the erection of an enormous dam at Gatun, 7,700 feet in length, 135 feet in height, and to contain 21,200,000 cubic yards of material. There will be a 500-foot wide channel at sea level from the Atlantic to this dam, where there will be built a double flight of three locks, by which vessels will be lifted into the huge artificial lake, 85 feet above sea level, formed by the dam. The waters of the lake will spread over a vast area, and will back up through the valley of the Chagres, affording unrestricted navigation (that is, navigation independent of the channel) for a considerable part of its length. Its waters will extend through the Culebra divide, in a cut 200 feet wide, to Pedro Miguel, where descent will be made by a lock with a 30-foot lift to another lake formed by the creation of a dam in the valley of the Rio Grande. From this lake, which will be at level 55, descent will be made by a double flight of two locks to Panama Bay. The canal will have a minimum depth of 45 feet, and it is estimated that it can be built in nine years at a cost of \$140,000,000.

The majority of the board of Consulting Engineers in their report say: "First and foremost, it is essential

that the Panama Canal shall present not merely a means of inter-oceanic navigation, but a means for safe and uninterrupted navigation. It is therefore evident that the canal ought to be formed in such a manner that the course thereof shall be free from all unnecessary obstructions, and that no obstacles shall be interposed in that course, whether temporary or permanent, which would by their nature be an occasion of peril and of detention to passing vessels, and more particularly to vessels of the great size which the Panama Canal is (in accordance with the provisions of the law of Congress) designed to accommodate." It is because the majority of the Board consider that locks and locking operations present risks and delays, that they favor, in spite of its greater cost and longer time of construction, the sea-level canal. The minority of the Board favor a lock canal, because they believe it would have a greater capacity for traffic; would offer greater safety and speed for ships because of the deep-water navigation in the lakes; and would involve less time and lower cost of construction.

There is no denying that the economy and quickness of construction of the lake-and-lock canal, and the fact that much of the navigation would be in deep water, render the lock project decidedly attractive. But—and we wish to draw the attention of everyone that shall discuss or vote upon this all-important subject during the next few months, to the serious nature of the doubt—is any one able to state with certainty that an earth dam, 7,700 feet long and with a head of 85 feet of water back of it, can be built to stand on the treacherous foundation of the alluvial substratum of the Chagres valley at Gatun? We have just completed the reading of the late Chief Engineer Wallace's examination before the Senate Committee of Investigation, in which he gives it as his opinion, based upon the elaborate borings, that the conditions for dam foundations at this point are unsuitable, the substratum being an alluvial deposit, in places pervious to water, and extending down 256 feet before firm bottom is reached. Before any final appropriations are made by Congress for a canal whose existence will depend absolutely upon the integrity of this colossal dam, it must be proved beyond a shadow of a doubt that so unsuitable a foundation can carry such a stupendous structure under the great head of water proposed, and do so, not merely for the present generation, or the next, but for all time to come.

## THE TRENCH METHOD OF TUNNEL CONSTRUCTION.

It is not unlikely that the well-known method of excavating subaqueous tunnels by means of the Great-head shield will, under certain conditions, be abandoned in favor of a new method which offers very material advantages both from the constructive and the operative point of view. We refer to what is known as the trench system of construction, which was first adopted in a modified form by Mr. McBean, the contractor for the Harlem River tunnel on the easterly branch of the New York Rapid Transit Subway. By reference to the illustrated article published in the SCIENTIFIC AMERICAN of October 31, 1901, it will be seen that the tunnel was built by dredging a trench in the river bottom and building within it a water-tight chamber, from which the mud was removed by the usual pneumatic method, the concrete tunnel being built within the rectangular prism thus provided.

We now learn that an improved application of the trench method is likely to be employed on the important two-track tunnel, which is to carry the main line of the Michigan Central Railroad beneath the Detroit River. The work will be of a magnitude and importance that will rank with that of the tunnels which are now being built by the Pennsylvania Railroad beneath the North River. The new method of construction, however, which has been proposed by Mr. W. J. Wilgus, the vice-president of the New York Central Railroad, differs from that of the North River tunnel in the fact that while the former is being driven by the Greathead shield, the Detroit River tunnel will be constructed entirely in a dredged trench. Moreover, the plan that is proposed will be a marked advance upon the one used for the Harlem River tunnel, inasmuch as the twin concrete tunnel will be built immediately in the trench, without the use of any form of cofferdam or the driving of a single foundation pile. The extreme simplicity, security, and low cost of the system, coupled with the fact that it is proposed to apply it on a work of such magnitude, will constitute this one of the most interesting pieces of subaqueous tunnel work ever attempted.

In the specifications upon which bids will be asked, there are four alternative designs presented, three of which are modifications of the trench method, while the fourth is the usual shield system. The profile of the crossing shows that for nearly 3,000 feet the twin tunnel will extend below the Detroit River, with approaches on easy grades at either end, which together will aggregate a length of about 10,000 feet. The trench method of construction will be adopted upon the stretch of tunnel lying immediately below the river. Briefly stated, it will consist in dredging a huge

trench through the mud and clay of the river bottom, and filling it with a monolithic mass of concrete, the tunnels being formed in the mass by means of temporary timber tubes, which are knocked down and removed after the concrete mass has set. In more detail the proposed method is as follows: The bottom of the trench will first be covered with an 18-inch layer of large stones and rock. Upon this will be deposited, from the temporary working platforms, a two-foot bed of concrete which supports, in turn, two lines of saddles, one on the axis of each tube. On the saddles are placed, end to end, large timber cylindrical forms 22 feet in diameter and from 50 to 500 feet in length. These forms are closed at their ends, and when they are placed in line upon the saddles, a space of about four feet is left between each section, for the purpose of dividing the tunnels into separate chambers. When the two lines of forms have been completed for a specified distance, concrete will be deposited in the trench and around the tubular forms until it has been brought up to a level corresponding to a depth of 41 feet below mean water level. The wooden forms will be surrounded with a waterproof covering, either of  $\frac{3}{4}$ -inch sheet steel, or of some of the well-known types of waterproofing. After the concrete has had time to thoroughly set, the end chambers will be entered and the forms knocked down and removed, leaving two circular tunnels 22 feet in diameter, whose length will be determined by the position of the first of the diaphragms or division walls of concrete, by which the tube is divided into working chambers. The inner concrete tubes of the tunnel proper, about two feet in thickness, will be then built in place, these walls being formed with steel reinforcement in the usual well-known manner. When these inner linings or tubes have been completed to the first bulkhead, the latter will be broken through and the work of lining carried into the next section, this being repeated until the whole distance below the river has been traversed.

The advantages of the proposed method of tunnel construction are very material, and affect practically every side of the question. There is, in the first place, a large saving in the time of construction and in the first cost of the work. The risks incidental to all tunnel construction are also reduced to a minimum. Finally, from the standpoint of subsequent operation, there is the great advantage that the tunnel can be built very much nearer to the surface of the river bed, and, therefore, the traffic does not have to be lifted from so great a depth, as the trains are hauled up to surface grade. If the great Detroit River tunnel be successfully carried through on the lines indicated, we shall look to see a very extended application of the trench method. Indeed, it seems to us that, as an alternative method of constructing tunnels beneath the North River, it will become, if it is not already, a subject for careful consideration.

## DISTILLATION OF GOLD.

Gold has long been considered one of the most difficult metals to vaporize; in fact, the only known means of accomplishing this is the use of the electric spark.

Prof. Henri Moissan, however, showed as early as 1893 that gold is rapidly set boiling in the electric furnace, as much as 40 grains of the metal being distilled in the time of a few minutes. He recently resumed his experiments in this direction, and an account of these is found in a communication to the French Academy of Sciences. The metal is shown to boil readily in the furnace at a temperature of 2,400 deg. C., 100 to 150 grains being converted to the gaseous condition within two or three minutes. By condensing the vapor on a cold body, either filiform gold or small cubes of crystallized gold are obtained. Like copper, gold at its boiling temperature is found to dissolve a small amount of carbon, which is freed again in the shape of graphite at the moment of solidification.

Gold is, however, less volatile than copper. In fact, when heating both metals under the same conditions, the latter is found to boil in a much shorter time than gold. The chemical properties of distilled gold are identical with those of hammered gold or of melted metal reduced to a fine powder. There is thus no indication of the existence of an allotropic modification of this metal.

Moissan also investigates alloys of gold and copper. There being no definite compounds of these, the copper is found to distill before the gold, and the same is true of gold-tin alloys, which were next studied. When collecting a large amount of the vapors given off from a boiling gold-tin alloy, the tin is found to burn at contact with the atmospheric oxygen, yielding tin oxide of a purple color, due to the fine gold dust condensed at its surface. This is nothing else than powder of Cassius. The same method can be used to obtain purples with different oxides, such as silica, zirconium, or magnesium oxide, lime, and alumina. The boiling point of gold, while higher than that of copper, is found to be lower than the boiling point of lime.



# THE HEAVENS IN MARCH.

BY HENRY NORRIS RUSSELL, PH.D.

The very clear evenings which sometimes occur at this season of the year give us our best chance to see what is really the largest, though one of the least known, parts of the solar system—the zodiacal light. Anyone who looks westward on a clear, moonless evening, as soon as it has become really dark, and the twilight has faded from the west, will see that the background of the sky is brighter in some places than in others. By glancing rapidly across from southwest to northwest, he can easily satisfy himself that this brighter region has the shape of a slowly tapering cone, with its base on the western horizon, above the sunken sun, and its apex lost in the Milky Way, beyond the Pleiades. This light is fully as bright, in its lower portions, as the Milky Way itself, but differs from it in character, being quite soft and uniform, while the Milky Way, even to the naked eye, is patchy and full of faint specks of light.

That this light has its origin in our own system, and not among the stars, is fully proved by its characteristics. In the first place, it lies along the plane of the earth's orbit (which nearly coincides with those of the other planets), and this alone would lead us to suspect a solar origin. But the conclusive proof is that it moves with the sun, appearing always in those constellations that lie near the horizon after sunset. Since it lies in the plane of the ecliptic, these constellations are always members of the signs of the zodiac—whence its name.

In the tropics, the zodiacal light is visible at all seasons of the year, after sunset and before sunrise. But in our latitude it is only well visible when its central line rises most steeply from the horizon, and this happens in spring for the evening light, and in autumn for the morning.

In very clear skies, it is possible to see that the cone of light does not run out to a point at all, but extends quite across the sky as a faint, narrow band, which connects the brighter portions visible in the evening and the morning.

A very satisfactory explanation of these facts is given by the hypothesis that the sun is surrounded by a great swarm of meteorites, shaped something like a convex lens, which lies about in the plane of the earth's orbit, and whose thin edge extends somewhat beyond the earth. It is the light reflected by these meteorites that we see.

This accounts for everything. The light grows wider and brighter toward the sun, because there are more meteors there, and we look through a greater thickness of the swarm. The thin edge, projecting beyond the earth's orbit, gives us the faint zodiacal band which connects the brighter portions of the light, and the whole affair must obviously follow the sun in its apparent motion through the heavens. A further confirmation of this theory has recently been provided by Prof. Newcomb, who, observing from a high mountain in Switzerland, has seen the zodiacal light at midnight in the north, and so determined that the widest part of the region of meteorites extends about 30 deg. from the sun.

How big these meteorites are we cannot say. They cannot be large bodies, astronomically speaking, for if they were more than a few miles in diameter, they would be visible separately in our telescopes.

But beyond this we cannot go. It is probable that, like the meteorites which strike the earth from time to time, they are of all sizes, from many tons weight to grains of sand.

## THE HEAVENS.

The evening skies in March are very fine. Starting in the west, we see Taurus, still at a good altitude, which, besides Aldebaran and the Pleiades, now contains Jupiter, the brightest object in the sky. To the left of it is the splendid Orion, and farther on, in the southwest, is Canis Major, marked by the superb Sirius, and an irregular cross of bright stars further south. Higher up is the isolated bright star Procyon, in Canis Minor, and above this is Gemini, with the two bright stars Castor and Pollux, from each of which a row of fainter ones extends toward Orion.

North of Gemini, in the Milky Way, is Auriga, with the very bright yellow star Capella. Below this, still in the Milky Way, is the bright group of Perseus, and the zig-zag line of Cassiopeia.

Returning to the south, we see below Sirius, and to the left of it, a part of the great southern constellation Argo. The sky to the east of the meridian is less brilliant. The most prominent group in the east is Leo, marked by the "Sickle"—which cannot be mistaken, even by a novice—and by a triangle of bright stars below. Between Leo and Gemini is Cancer, notable only for the star cluster Praesepe—a fuzzy patch to the naked eye, but a group of small stars to a field glass. Below this is a small but rather conspicuous group which marks the head of Hydra—a huge constellation which extends southeastward to the horizon, but contains only one bright star.

In the east the larger part of Virgo has risen. North of this is Boötes, with the bright red star Arcturus.

Ursa Major is admirably displayed high in the northern sky. The Bear's head and fore-paws have almost reached the meridian, while the end of her tail is still on a level with the Pole star. Ursa Minor and Draco, which lie below, complete the list of the conspicuous constellations.

## THE PLANETS.

Mercury is evening star in Pisces. On the 18th he is farthest from the sun, and about this date he can be best seen. This is an unusually favorable occasion for seeing him, as he is north of the sun, very bright, and does not set till about 7:30 P. M. Toward the end of the month he gets too near the sun to be well seen. On the 27th he is in conjunction with Venus, but both planets are too near the sun to be well seen.

Venus is also nominally an evening star, but she is so near the sun that, except at the end of the month, she is practically invisible.

Mars is evening star in Pisces and Aries, setting at about 8:30 P. M. in the middle of the month. Jupiter is likewise an evening star, being in Taurus, between the Pleiades and Aldebaran, and remaining in view till near midnight.

Saturn is morning star, but is too near the sun to be well seen. Uranus is in Sagittarius, and rises about 2 A. M. on the 15th. On the 29th he is in quadrature with the sun, and comes to the meridian at 6 A. M. Neptune is in Gemini. He is also in quadrature, on the 28th, and comes to the meridian at 6 P. M.

## THE MOON.

First quarter occurs at 4:20 A. M. on the 3d, full moon at 3:09 P. M. on the 10th, last quarter at 6:49 A. M. on the 17th, and new moon at 6:44 P. M. on the 24th. The moon is nearest us on the 12th, and farthest away on the 28th. She is in conjunction with Jupiter on the 2d, Neptune on the 5th, Uranus on the 18th, Saturn on the 22d, Mercury and Venus on the 25th, Mars on the 27th, and Jupiter again on the 29th.

On the evening of March 2 the moon passes between us and the bright star Aldebaran, occulting it for about an hour. As seen from Washington, the star disappears behind the moon's dark limb at 10:30 P. M., and reappears at the other side of the moon at 11:30. The times will be different at other places of observation, but not greatly so for places in the Eastern States.

At 8 A. M. on the morning of March 21, the sun crosses the celestial equator, and enters the sign of Aries, and, in the phrase of the almanacs, "spring commences."

Princeton, February 19, 1906.

## SIXTY MILES AN HOUR ON THE WATER.

BY ERNEST ARCHDEACON.

Builders of motor boats have realized for a long time the tremendous difficulties met with when they attempt to increase the speed of their craft even slightly, in view of the fact that the resistance of the water and, consequently, the power necessary to propel the boat increases with the usual type of hull as the cube of the speed.

During the last few years it has become possible to attain an increased speed with a motor of a given power by so shaping the hulls that their speed of translation tends to lift them partly out of the water, so that when the speed increases the resistance of the water increases much less than heretofore on account of this lifting of the hull, which, according to some constructors, reaches about thirty-three per cent of the total displacement of the boat. This is quite the *dernier cri* of motor-boat construction.

Over two years ago one of my countrymen, M. le Comte de Lambert, succeeded in constructing a boat which, in place of causing the emersion of about one-third of its hull from the water, succeeded in bringing the entire hull upon the surface. At this moment the resistance to the boat's advance became sensibly null. This boat is not a Utopia; it was built and operated over two years ago. The principles which its constructor followed were discovered a number of years ago by a Swiss scientist, M. Raoul Pictet, who carried on dynamometric experiments of the highest interest. These experiments were carried out on Lake Geneva with hulls of boats furnished with inclined planes; and they demonstrated accurately the phenomena of gliding and also the invariability of the effort of traction, at all speeds, as soon as the gliding was obtained.

Let us now return to the De Lambert hydroplane boat. (This boat was illustrated in the SCIENTIFIC AMERICAN of October 7, 1905.) The boat is constructed in a very rudimentary fashion. It is, according to its builder, too heavy and full of defects, as is generally the case with a first experimental apparatus. Nevertheless, with a 13-horse-power motor, it attained a speed of 35 kilometers (21¾ miles) an hour—a speed which was several times taken by official chronometers. It was two years ago that this boat was experimented with without any mishap or serious drawback; and the results of the experiments were given to the world.

It is hard to believe that in view of these results motor-boat builders have done nothing as yet toward

the construction of a boat built on these principles—a boat which seemed destined to create a revolution in the line of speed craft.

On the contrary, however, they have been too much preoccupied with increasing indefinitely the number of horse-power possible to place in their hulls. We have actually reached the point of placing 300 horse-power in a walnut hull in order to attain a speed of 31 miles an hour at the most. We are now awaiting the 500 horse-power motor-boat engine.

How blind these builders are not to see that with 20 horse-power and a hydroplane they will attain the same speed as is possible with 100 horse-power in the regular hull; and that with 300 horse-power—I do not dare to predict the speed!

To continue the discussion in a simple manner I will say that a well-constructed hydroplane can be made to attain sensibly the same efficiency as an automobile. But, in the actual state of the science, a 100-horse-power automobile will travel 90 miles an hour! Notwithstanding the lack of energy of boatbuilders in adopting a new idea, I am willing to bet, and I am ready to stick to it, that before September 1, 1907, 55 miles an hour will be made on the water. And I am surely below the truth.

The theory of the hydroplane, which is, moreover, identical with that of the aeroplane, is the following:

Any inclined plane moving in a fluid, air or water, and which has a horizontal movement of translation, undergoes an ascending or descending reaction according as the inclination of the plane is ascendent or descendent with respect to the direction of travel.

But, the hydroplane is nothing more than a boat to which has been added a suitable series of inclined planes. Before starting, the water which the apparatus draws, as well as its displacement, will be maximum. As soon as it is under way it will commence its movement of ascension, which will only cease when it attains such a position that the draft of water becomes zero, and the displacement also.

With Count de Lambert's boat, the inventor estimates that as soon as the speed reaches 15 kilometers (9.31 miles) an hour, the emersion is already complete. Moreover, he states that as soon as this emersion is obtained, the effort of traction no longer varies whatever may be the speed. From this we reach the conclusion that the force necessary for the propulsion of an emerged hydroplane increases exactly as the speed. At very high speeds this theorem will no longer be quite exact, since the resistance of the air will not then be negligible; but with speeds up to 20 miles an hour we are altogether free to neglect this.

Let us now calculate from these figures what power Count de Lambert's hydroplane requires in order to emerge completely. We have, evidently,

$$\begin{array}{rcl} x \text{ (power sought for)} & & 15 \text{ k} \\ \hline 13 \text{ horse-power (total power of motor)} & & 35 \text{ k} \\ \text{whence} & & \\ 13 \times 15 & & \\ x = \frac{\quad}{35} = 5.5 \text{ h. p.} \end{array}$$

Therefore, the boat used 5½ horse-power in order to rise from the water at a speed of 9.3 miles an hour, after which the increase of speed obtained was exactly proportionate to the increase in horse-power, i. e., in the proportion of 5.5 horse-power to 13.

It will be easy to construct a boat not weighing as much as that of Count de Lambert's (which weighed 800 kilogrammes, or 1,763 pounds), when fitted with a motor of 50 horse-power. Making the calculation in the manner as above, we have

$$\begin{array}{rcl} 5.5 & 15 & \\ \hline 50 & x & \\ 15 \times 50 & & \\ \text{whence } x = \frac{\quad}{5.5} = 136 \text{ kilometers (84.45 miles)} \end{array}$$

an hour.

I should add immediately that at these speeds the resistance of the air becomes quite important, and, as the calculation no longer holds exactly, the figure given above must be diminished considerably, although it would still remain quite high.

I believe that I have shown in a satisfactory manner the immense interest to be had in building and experimenting with well-constructed hydroplanes, and I repeat that I do not understand the apathy of the boat builders.

I know that the criticism will be made that the hydroplane will not work in turbulent water since the planes would strike the waves and not glide over them. This opinion is not altogether true, as I have found from my own experiments with the hydroplane that it is not stopped by the waves any more than is an ordinary boat.—Translated for the SCIENTIFIC AMERICAN from La Vie Automobile.

Casein Cement for Porcelain.—Mix 10 parts of recently prepared casein with 30 parts of soluble silicate of soda and 20 parts of similar silicate of potash.—Nouvelles Scientifiques.

### HYDROPLANE BOATS: LATEST TYPE OF HIGH-SPEED CRAFT.

BY WILLIAM M. MEACHAM.

Under normal conditions the resistance which a boat encounters is, in round numbers, proportional to the cube of the speed and may be divided into three classes:

(1) Skin or frictional resistance. (2) Eddy-making resistance. (3) Wave-making resistance.

The power expended in driving a boat is used largely in overcoming these resistances and is found to vary as the cube of the speed.

The only conceivable method of avoiding this condition is to lift the boat from the water by a means having less resistance than that of the boat when supported by displacement. The hydroplane offers this solution, and the following proposition aims to set forth its scientific basis, and to show that the power required to drive a boat on this principle varies in a much smaller ratio than the accepted formula above recited:

Given a flat plate, having weight which is constant under all conditions, deeply submerged in water, drawn edgewise, horizontally through the water, with front edge in direction of motion, raised at a small angle to the horizontal.

The power applied to the plate is divided into two components, one of which furnishes the supporting force, and the other of which overcomes frictional resistance.

I have found that the component of supporting force varies as the square of the speed. The component of frictional resistance also varies as the square of the speed, as demonstrated by experiments of Toëssel and Froude.

It then follows that if the supporting force is kept constant by reducing the width of the plate, across the line of motion, as speed increases, the frictional resistance of the plate, taken as a whole (not as per unit of area), remains constant.

Or, in other words, if the area of the plate is varied (in width across the line of motion) inversely as the square of the speed, the resistance due to skin friction and that due to the inclination of the plate will remain constant, and the supporting force will also remain constant. Since the resistance is constant and the distance through which the force acts varies directly as the speed, the power required will vary directly as the speed instead of as the cube of the speed, as would be the case if weight was supported by displacement.

Such would be the result under ideal conditions only. Count de Lambert, and others, with apparatus similar to that herein pictured, succeeded in raising the boat out of the water at high speed, the hydroplanes becoming partially emerged and gliding upon the surface. Such an arrangement, however, of large supporting plates at the surface, serves to produce, in considerable degree, the very resistances to be eliminated and thus, to such extent, to defeat the very purpose for which it has been designed.

With the object of substantiating the principle of the hydroplane, the writer has experimented with submerged plates.

The apparatus used was crude, but it will be seen from the photograph that even at the moderate speeds attained, not over 15 miles per hour, the submerged hydroplanes operated successfully to raise the hull of the boat entirely out of the water.

In the experiment pictured there were but two hydroplanes used, one at the front and one at the stern, in size 15 by 30 inches and 18 by 36 inches respectively. The balance was preserved by a small outrigger on either side. At another time the same apparatus (identically) was tested with a load of two men instead of

one with the same result as shown. In the latter instance the total weight, made up of the boat and two men, was exactly 550 pounds. By computation it will be seen that the total supporting hydroplane area was  $7\frac{1}{4}$  square feet. By careful measurement it was ascertained that the water displacement of all submerged parts was less than three per cent of the total weight.

Special attention is directed to the fact that the

ing of an apparatus designed to reveal this principle

The body of the boat, *A*, when at rest, is supported by displacement at the water-line, *J*. When the boat is put in motion, by the propeller, *H*, the regulating plates, *C C'*, which have hung submerged, are caused by their angle to the line of motion through the water, to rise and remain at the surface.

This lifting of the regulating plate, *C*, at the front end of the boat, causes arm, *P*, to turn on pivot, *d*, which operates the connecting pieces, *K*, *L*, and *M*, and raises the front edge of supporting plate, *B*, which is pivoted at *Q*, causing the angle of plate, *B*, to increase in relation to the horizontal.

The position of plate, *B*, when boat is at rest, and until its position is changed by the regulating effect of plate, *C*, is nearly horizontal, being curved slightly downward from front to back; but as soon as its front edge is raised, by the operation of the regulating plate, *C*, as above explained, a lifting force is produced which, when the speed is sufficient, causes the boat to rise. A like result is simultaneously accomplished by the supporting plates, *B' B'*, at the rear end of boat, which are regulated by the plates, *C' C'*, in a similar manner.

The boat is balanced at all times by the automatic and immediate adjustment of this rear mechanism. The level of the boat from front to back is likewise automatically maintained.

When the boat is put in motion, it steadily rises until it has attained the maximum speed, at which time the body of the boat is raised entirely above the surface of the water, and there maintained by the automatic adjustment of supporting plates, *B B'*, which is accomplished by their respective regulating plates, *C C'*, which, still held at the surface of the water, have gradually become lower, relatively to the boat, as the boat has risen in and above the water, with a corresponding lessening of the angle of the supporting plates *B B'*, which have, finally, at maximum speed, come to their position of highest efficiency.


As the speed may thereafter vary, any tendency to sink, because of lessened speed, is immediately overcome by the lifting effect of the automatically increased angle of the supporting plates, *B B'*, the said angle being immediately diminished as the speed is again increased.

This process, repeated, provides for indefinite duration, and when, finally, the speed is slackened, the gradual sinking of the boat is accomplished, automatically, by the reverse operation of the regulating plates, *C C'*, and the supporting plates, *B B'*, by which it is brought to a position of rest, when it is again supported, as at first, by water displacement at water-line, *J*.


The water-line, *I-I*, indicates the relative positions of various parts when the boat is at full speed and maximum height. Letters *D D'* show the hollow, elliptical, supporting frames to which the supporting plates, *B B'*, are attached, and in which the connecting rods, *M M'*, operate. Letters *S S* show the pivotal connections between said rods, *M M'*, and the rear regulating arms, *P' P'*. Letters *R R* show the rudders, which, attached behind the rear supporting frames *D' D'*, are operated by the lever, *G*, and cross-pieces, *O O*, by means of a chain. Letter *F* indicates the necessary wood or metal framework for rigidly connecting and supporting the rear portion of mechanism.

The supporting frame, *D*, at the front end, contains, in addition to the rod, *M*, the necessary shaft, gearings, etc., for the operation of propeller, *H*.

The supporting plates, *B B'*, it should be noted, are connected at pivots, *Q Q'*, at a point in front of the center, so that the upward pressure on these plates while the boat is in motion, tends to press them to a more nearly horizontal position and thereby operates as an unyielding spring against the pressure exerted



Longitudinal Section of a Proposed Motor Boat Fitted with Automatically-Adjusted Submerged Hydroplanes.



Experimental Test of Submerged Hydroplanes.

The boat, which is being towed at a comparatively low speed, is shown lifted clear of the water by submerged Hydroplanes at the bow and the stern. This type of Hydroplane is said to be more efficient than the surface type shown below.





Diagram Showing Positions Assumed at Rest and in Motion by Motor Boat Fitted with Surface Hydroplanes.



Motor Boat Fitted with Three Surface Hydroplanes of the Type Proposed by Archdeacon.

### HYDROPLANE BOATS FOR TRAVELING AT HIGH SPEED ON THE WATER.

surface of the water was scarcely ruffled, except from the regulating plate projected at the front, by means of a rigid bar, for the purpose of regulating or varying the angles of the supporting plates. The plates used in these experiments were excessively large on account of the necessity of working at low speeds with little power.

The outline drawings will convey a fair understand-



by the regulating plates, *C C'*. It will be understood that in this construction no attempt is made to adjust the plates in width as speed increases; but the advantage of the application of this principle is secured by designing the plates for each particular boat for one speed only (which is its maximum speed), and the lifting force required at other speeds (between starting and maximum) is obtained by the automatic regulating device which gives the plates at all times such an angle as is necessary.

Strange as it may seem, the chief obstacle encountered in early experiments was not to make the hydroplanes rise, but to prevent them from rising too far, and it was as a means to this end that the surface follower, as a regulating device, was adopted. By its use the boat becomes practically a soaring machine and bears the same relation to an ordinary boat, in the water, as does a soaring bird to a balloon, in the air; and this relation holds, also, in respect to their skin friction areas. It also possesses the following advantages over a soaring machine in the air, i. e., it soars in, and its propelling force is exerted upon water, which is seven hundred times as dense as air, while the displacement of the hull, with its necessarily large frictional surface, is all carried in the rarer medium, air, and above the water, the surface of which can be used to effect the regulation of the inclination of the supporting hydroplanes.

Another special advantage of a submerged hydroplane construction is that it will operate without hindrance in water sufficiently rough to totally unfit a gliding boat.

The strength of development and success will depend, not upon disproving or defying any established law, but upon strict application of rational laws and careful attention to details.

#### A MOTOR PADDLE WHEEL FOR SMALL BOATS.

In the accompanying engravings we give a side elevation and plan view of a detachable stern paddle wheel designed for the propulsion of small boats, and perspective views of the apparatus mounted upon a boat.


On examining the diagrams from left to right, we observe, at *A*, a two-cylinder de Dion-Bouton motor of 16 effective horse-power; at *B*, a clutch; at *C*, a speed reducer; at *D*, a reversing gear; and at *E* and *E'* sprocket chains connected with the paddle wheel *R*. This wheel consists of paddles inclined at an angle of 50 deg., small spaces being left, so that the stress is exerted upon a wider surface than if the paddle consisted of a single bow, as is usually the case. As the water is easily discharged, it creates no passive resistance, and thus a high efficiency is obtained. As this propeller is designed for Oceanica and has to be actuated by kerosene, the only fuel practical in that country, a special carbureter has been applied.

With this paddle wheel it is possible to carry from 18 to 20 tons of merchandise at a commercial speed of from 5 to 6 miles an hour with an output of fuel not exceeding 40 ounces per horse hour.—Translated from *L'Automobile* for SCIENTIFIC AMERICAN.

#### THE "MOTOGODILLE," A MOTOR DEVICE FOR PROPELLING SMALL BOATS.

BY THE PARIS CORRESPONDENT OF THE SCIENTIFIC AMERICAN.

An interesting device in the way of applying a motor to small craft has been brought out in France. The apparatus has been designed to afford a very simple as well as inexpensive method of applying a small gasoline motor to boats. It is nothing more or less than a power oar and consists of a motor-driven propeller which is adapted to be placed on the boat; but contrary to other apparatus and motors which require to be specially built and installed in



THE MOTOGODILLE, OR MOTOR SCULL, APPLIED TO A SMALL BOAT.

the boat so as to form part of the latter, it forms an entirely separate mechanism which is fitted to the stern of the craft in a few minutes, and which permits the immediate conversion of any ordinary boat into a motor-driven craft without any change whatever in the boat itself. By applying a simple socket-piece to the stern with four screws or bolts, the propelling apparatus, which fits in the socket by means of a pin in about the same way as a steering oar, can be immediately installed. The new propeller

in case of a calm, and it can easily be stowed in the hold. As will be noticed the motor is mounted upright just over the main pivot which works in the boat. Back of the motor and fixed on the steering bar is a box with sliding cover for the battery and spark coil. Above it is a cylindrical gasoline tank.

#### The Destruction of Flies.


The fly is doomed; the flat has gone forth, and its days are numbered. Doctors have recognized the fact that the house fly is not only a nuisance, but also a real danger, because it is the bearer of microbes and nastiness of all kinds. Fired with the spirit of enterprise, and wishing to do good to humanity at large, the *Matin*, of Paris, recently offered a prize to the discoverer of the most practical and efficacious means of destroying these insect pests, and thus eliminating one great source of the spread of epidemics.

A pamphlet entitled "*Delenda Musca*" has carried off the prize.

According to the writer of this essay, very few people are aware that the domestic fly lays its eggs in cesspools, drains, liquid manure, and dung heaps of all kinds. In these delectable media the *Musca domestica* deposits its oblong eggs, which are opened by the detachment of a narrow longitudinal band or strip—much in the same way as the blade of a knife is opened. The larvæ grow with surprising rapidity, attaining their full size, in summer, in eight days' time. One fly may

give birth to millions of others, as it breeds continuously for several consecutive months (usually from May to October). Assuming that one specimen lays 200 eggs (containing an equal number of males and females) then, as will be seen from an easy calculation, in six months' time one hundred thousand million flies will be brought into the world to tease bald-



headed men and the helpless in general. After showing that it is useless to attack the full-grown insect, the author seeks some means of destroying it while it is in the period covered by the laying of the egg to the formation of the pupa—just when the insect is most vulnerable, and is found collected together in more or less considerable quantities. The greatest points of attention to this end are cesspools, muck heaps, drains, manure heaps, and the like. Arsenic and arsenical compounds should not be used for the destruction of flies' eggs and larvæ in open cesspools in country districts, where—too often, unfortunately—they are in underground or other communication with wells, watercourses, and springs, which might thus get poisoned. Recourse should be taken to some substance which not only dissolves in the liquid contained in the drain, but which will penetrate right into the heart of solid matter. This substance must be of a nature to withstand fermentations and all transformations experienced by the solids contained



ELEVATION AND PLAN OF THE BUCHET MOTOR PADDLE WHEEL.

device, which is known as the "Motogodille," is of extra light, simple, and strong construction, and forms a single rigid piece having but a single contact with the boat. It serves to propel and steer the craft at the same time and also to change the speed. The socket and the support of the apparatus form a kind of universal joint which allows the pilot to raise the propeller

THE BUCHET MOTOR PADDLE WHEEL SEEN FROM THE REAR.



SMALL BOAT ACTUATED BY THE BUCHET MOTOR PADDLE WHEEL.



in the cesspool, as they are always, in such media, of ammoniacal and reductive nature. These reactions show that it is useless to employ sulphate of iron, sulphate of copper, etc., for although in the beginning these metallic salts might have some effect, they would subsequently become changed by fermentative influences and lose their efficacy. The first trials made showed that ordinary soda, mixed with ordinary chloride of zinc (in the proportion of 5 kilogrammes of each to every cubic meter of matter), was quite sufficient to kill the larvæ and prevent the hatching of further eggs laid in the same place during the season. This process could, if necessary, be used for stationary, hermetically closed cesspools, but it would not do for movable closets, sewage tanks, or open drains. Petroleum was then tried by the author of the pamphlet in question, in the proportion of one liter to every superficial meter; but in a short space of time—due probably to the slight rise in temperature caused by fermentative processes—the petroleum disappeared. This was verified by putting a stick into the cesspool; if petroleum had still been present, it would have left traces thereon. Coal tar was then tried with much better results, although they were still not all that could be desired. The most satisfactory results were secured with raw petroleum or raw schist oil (residue of distillation). Two liters per superficial meter were mixed with water, the whole being well stirred up with a piece of wood. This, on being poured into a drain or closet, will form a stratum of oil which will destroy all the larvæ, while, even should flies not be prevented from entering the drain, at least all the eggs they may deposit will be prevented from hatching. This oil is sufficiently consistent and tenacious to adhere to the walls of drains, to form a coating over solids, and remain attached thereto for a long time. This protective layer of oil also facilitates the development of anaerobic bacteria which cause the rapid liquefaction of solids, thus rendering them quite unsuitable as a breeding ground for Diptera. In the case of manure heaps this oil may be mixed with earth, lime, and fossil phosphates, in which state it is sprinkled (preferably in the spring) over all sources likely to tempt young couples of the Diptera family to start housekeeping and the rearing of a family.

#### Electric Trains for the Simplon.

It was at first proposed to use steam trains in the Simplon tunnel, but afterward the electric system was decided upon on account of the high heat of the tunnel coming from the hot springs and again because it was difficult to ventilate the tunnel and carry off the smoke. The administration of the Swiss railroads has lately accepted the project of the Brown-Boveri electric firm for installing the system of dynamos and rolling stock. The traction will be carried out according to the system which is now in use on the Valtelline road in Italy. The hydraulic power of the Videria and the Rhone which already served for putting through the tunnel, will operate a turbine station and the latter will supply current to a number of sub-stations situated some 30 miles off. In these the high-tension alternating current will be converted to 2,300-volt current for the different circuits. A dam is now building which will be nearly 500 feet long. The head of water is some 30 feet. The main station contains two halls for the turbines, 120 feet long, and the dynamo hall lies between the two. Each of the turbine halls contains four pairs of horizontal turbines. Each unit is laid out for 3,000 horse-power at a speed of 200 revolutions per minute. The turbine shafts pass through the wall and in the dynamo room they have the alternators mounted on them. These dynamos have a capacity of 1,500 kilowatts and generate three-phase current at 25 cycles. Lombard governors keep the speed constant. The three-phase current passes to the transformer hall, where a bank of oil transformers raise the tension to 33,000 volts. For the traffic in the Simplon tunnel it is intended to use five electric locomotives at first, and the electric system is to be extended to all the sections of the Simplon road which are operated by the Swiss railroads, or a total length of 25 miles. The total cost of the electric equipment of the tunnel is estimated at \$200,000. It is expected to open the new line about the 1st of May.

#### The Current Supplement.

The current SUPPLEMENT, No. 1574, opens with a summary of the granite industry of New England. Of interest to mining engineers are Dr. Kunz's statistics on the precious stone industry in 1904, and some data on the coal mines of Japan. G. T. Beilby contributes a very interesting paper on gold molecules in the solid state, giving valuable results of most interesting experiments. Some analogies are drawn between light and electric waves, in an article by Prof. B. Dessau. The American Society of Heating and Ventilating Engineers by a strange coincidence happened to hold its annual meeting on January 17, 1906. Two hundred years ago on this very date Benjamin Franklin was born. For that reason the interesting paper which was read before the Society on "Benjamin Franklin, the First American Heating and Ventilating Engi-


neer," should prove valuable. The paper is published in full. At the opening meeting of the Society of Mechanical Engineers, President J. R. Freeman read a paper on the safeguarding of life in theaters. The paper, which is abstracted, is the result of painstaking investigations on the author's part. A simple photographic and photo-micrographic apparatus is so clearly described and illustrated that any one can construct it. Dr. Alfred Gradenwitz writes on a modern testing plant for gasoline automobile motors. Some specifications of material used in high-speed automobile and motor-boat engines are published. A. L. Johnson contributes an excellent paper on steel for reinforced concrete.

#### SPEED AND ENERGY LOSS OF PROJECTILES IN WATER.

The singular explosive phenomena that are observed whenever rapidly-moving projectiles strike liquid masses have been investigated of late years by many experimenters, and it has been shown that neither the revolution of the projectile nor the heating it undergoes plays an important part. It has likewise been demonstrated that the phenomena are not due to the effect of hydraulic pressure, as the vessel does not explode until after the bullet has left it. In order further to study these interesting phenomena, Martin Gildemeister and Hans Strehl (see *Annalen der Physik*, Vol. 18) recently undertook tests to ascertain the magnitude of the forces concerned.

The kinetic energy imparted to the liquid is a maximum equivalent to that lost by the projectile as it passes through the liquid bulk, the amount immediately converted into heat being in all probability very small.

The arrangement used by the authors is represented in the accompanying illustration. After first breaking the wire *A*, the projectile causes the condenser *N* to be discharged through the resistance *W*, which is free from self-induction, the discharge ceasing as the second wire *B* is broken. The time elapsing between the two occurrences is calculated from the residual charge of the condenser, its capacity and initial charge



#### SPEED AND ENERGY LOSS OF PROJECTILES IN WATER.

being known. The following law is derived from the authors' experiments:

The loss in velocity of a projectile in water is proportional to the first power, and the loss in energy to the second power of the velocity of the projectile on entering the liquid.

#### A New British Range Finder.

The British Naval Department has adopted a new type of range finder, which is stated to be of great value. It is the invention of Lieut. Arthur Vyvyan, the details of the mechanism having been carried out by Mr. Newitt, R.N., an electrical engineer. The utility of this instrument is for automatically transmitting the range observations from the fighting control top to all the various gun positions on board the vessel simultaneously and automatically. There are a series of electric motors, one stationed in the fighting control top, and one at each gun position. These motors all run at a uniform speed, and when there is any movement in the one at the fighting top, the others are similarly affected automatically. For instance, when the officer in the fighting top describes a vessel or object to be brought under fire, he estimates the range, and instructs the officer in charge of the motor appliance. A trial shot is then fired some distance short of the estimated distance, say 400 yards. The instrument is set running for this distance, and by means of an indicator and pointer the range is transmitted immediately to the various gun positions, the instruments at which record simultaneously upon their indicators. Should the range prove too short, another shot is fired, the distance being increased by say one-half the underestimate, viz., 200 yards. The result of this second shot will bring the instrument's pointer to about the correct range. If not, then another shot is fired, the range being again proportionately increased. These trial shots only occupy a few minutes, and directly the correct range has been obtained by the recording officer in the fighting top, all the various gun positions have it as well, and firing can be continued without any delays. The instrument provides automatically for the deflection of the range and the speed of the ship. The transmitter has proved completely satisfactory under test, the correct range being invariably obtained by the second trial shot. It has been perfected during the past year, and is now in operation at the gunnery school at Whale Island and on board a war vessel, and its utilization is to be extended throughout the service.

#### A TRIPLE-SCREW MOTOR TORPEDO BOAT.

The torpedo boat shown under way in our illustrations is one of the latest productions of the English firm of Yarrow & Co. It is an exceedingly speedy craft, having excellent sea-going qualities and being intended to take the place of the usual steam-propelled second-class torpedo boat. The boat is 60 feet in length by 9 feet beam, and is fitted with triple screws and three four-cylinder Napier gasoline engines—two of 120 horse-power for the outer propellers and a 60-horse-power engine for the center propeller. The last-named propeller is reversible, and it is thought that a single reversing propeller is all that is necessary for this type of craft.

In a series of speed trials made recently this boat developed a speed of 25½ knots when running light. This is an advance of 5½ knots over what could be obtained under the same conditions with a boat having a steam power plant. The reasons for this increased speed are the much lighter weight of the machinery (there is probably a saving of some 50 per cent), and the form of hull, which, at these high speeds, for the displacement of a boat of this type, seems to enable it to skim or glide over the surface of the water—a fact made evident by the small surface disturbance. The power which is usually absorbed in making waves is therefore utilized for propulsion.

A motor boat of this type, if fitted with a revolving torpedo tube, could be readily used as a second-class torpedo boat, or as a gunboat for coast-guard service. On account of its light weight, which does not exceed 8 tons, it is quite easy to transport such a boat on a larger vessel to any part of the world. Regarding the cost of such a boat the statement is made that fifteen of them could be built at the cost of a modern destroyer. For the purpose of defending a port from an attacking or blockading fleet, there is scarcely any doubt that fifteen small, high-speed motor boats of this type would offer a considerably greater means of defense than one destroyer of large size upon which the fire of a number of guns could be concentrated.

In line with the construction of this first motor torpedo boat for the British navy mention should be made of the fact that Mr. Lewis Nixon, who built the motor boat "Gregory," that crossed the Atlantic a year ago and was subsequently sold to Russia, has designed and built for the Russian navy no less than ten of these small, high-speed craft. These are said to have a length of 90¼ feet and a displacement of 35 tons. They are driven by twin screws, each of which is driven directly by a reversible marine gasoline engine of 300 horse-power. A speed of 20 knots is obtained at 400 R. P. M. of the engines.

This is a second example which has occurred within the last five years of how backward our government is in seizing new and worthy inventions as soon as they are brought out. The other case in point is the Lake submarine torpedo boat, which, although tested and found far superior to any other boat of the kind either here or abroad, was abandoned and its inventor allowed to sell it to foreign powers, one of the largest purchasers among these being Russia.

#### The Color of Water.

L'Illustration (Paris) gives the following results of recent experiments on this subject:

"After long hesitation, scientific men agree to-day in admitting that water *physically* pure, seen in mass, is sky blue. This color is that taken by the white light of the sun when absorbed by the water, in consequence of a phenomenon the explanation of which would be a little long. It is not due to the *chemical* purity of the water, since the sea (which is the bluest water) is also that which contains the most salt. Nevertheless, according to Forel's experiments, the matter in solution should be the predominant cause of the modification of color; upon which act besides the matter in suspension, the color of the bottom, and the reflection of the sky and of the banks. Consequently blue water is pretty rare in nature; a good many seas and lakes that give us the impression of this tint are green. The water at present acknowledged to be the bluest is that of the Sargasso Sea, between the Cape Verde islands and the Antilles. The water of the Mediterranean off the French coast and around Capri is bluer than that of Lake Lemane, much less blue itself than that of the lakes of Kandersteg and Arolla, in Switzerland.

"Hitherto they have not exactly determined the relation between the color of water and its degree of purity. The Belgian, Prof. Spring, who has been a long time studying this delicate question, has just communicated to the Academy of Sciences at Brussels some interesting figures. Pure water containing a millionth of ferric hydrate appears brown under a thickness of 6 meters; a ten-millionth is sufficient for it to be green; and, in order that it may remain blue, is needed less than a twenty-millionth. As to humic matter, it causes the blue coloring to disappear in a quantity less than a forty-millionth. The calcic compounds should have a great influence upon clarification, as they eliminate, up to a certain state of equilibrium, the ferric and humic compounds."



## Correspondence.

## Impracticability of Cement Tiles.

To the Editor of the SCIENTIFIC AMERICAN:

In your issue of the 10th instant of the SCIENTIFIC AMERICAN is an inquiry for cement tile, by John R. Spears. He seems to have overlooked the fact that the farm drainage tile is porous, water going through its sides the same as through the earth. Cement tile might be used for glazed tile, for watertight or sewage purposes.

Yours truly,

Wayne, Neb., February 12, 1906. C. E. BARTLETT.

## A Centigrade Photometer.

To the Editor of the SCIENTIFIC AMERICAN:

I was much interested in the article by Mr. Butzing, "A Unit for Light Measurements and a Centigrade Photometer," in SCIENTIFIC AMERICAN of January 27, p. 91. His suggestions are very good. I would suggest to use a selenium cell in connection with a galvanometer, to indicate the intensity of light on a graduated scale, the same as we read the steam pressure on a steam gage. This photometer might be either permanent, intermittent, self-recording, or not. To save current it might be so made that it could be turned on or off at will. Of course, this photometer would hardly be as accurate as the ones now in use, but for ordinary purposes it would certainly be sufficient, and above all it would be handy. But I would suggest that zero should be absolute darkness, so as to avoid the nuisance of above and below zero. But make it Centigrade by all means.

Is there any chemical that would make paper permanently a fairly good conductor of electricity, so that electricity would pass through it? If paper would not do, I could use cloth.

REV. JAMES WALCHER.

Tintah, Minn., January 29, 1906.

[Acetate of lead, sodium chloride, or carbonate, and many other salts dissolved in water and absorbed in paper, will render the paper a fairly good conductor of electricity. If, however, the paper must be dry, these will not answer. Plumbago incorporated in or surfaced upon the paper would perhaps answer the purpose. The question conveys nothing of the use intended, and we are at a loss for an answer.—Ed.]

## Refractory Lining for Gas-Engine Cylinders.

To the Editor of the SCIENTIFIC AMERICAN:

I have read with a good deal of interest Mr. Howell's interesting article on "A Rational Method of Cooling Gas-Engine Cylinders." It might be interesting to him to know that Mr. C. C. Bramwell, of Hyde Park, Mass., tried this system of piston and cylinder construction on an air-cooled motor for automobile work on ordinary lines early in 1901. That part of the cylinder, where the packing rings were, was made of steel and was unjacketed; the upper part, where the explosion and expansion took place, was of copper.

He found that as far as lubrication, etc., went the motor gave him no trouble, but that it was necessary to water-jacket the head in order to prevent pre-ignition.

It seems to be a generally accepted belief that all the good that a water jacket does is to prevent pre-ignition and make possible the successful lubrication of the cylinder. I have reason to believe, however, that when an engine becomes overheated quite an amount of the loss of power may be caused by the expanding of the incoming charge due to its contact with the cylinder walls and the residual exhaust gases of the last explosion, thus preventing a full charge being taken into the cylinder. It can easily be seen that, if this is so, the higher the speed of the engine the less the loss from this cause would be. The same result could, of course, be secured by opening the inlet valve late in the stroke.

Of course, the first thought that comes to one's mind on hearing this argument for the first time is the matter of the Diesel engine. Now, as a matter of fact, the Diesel engine has not nearly as high a maximum temperature as the ordinary Otto cycle engine, and since an excess of air is always used in this engine it is evident that less heat units are developed from the combustion of the fuel and therefore there is proportionately less heat carried off by the water jacket or other cooling device; hence it is only reasonable to suppose that the mean temperature of the cylinder walls is lower, and therefore we would not be as likely to suffer from this result of overheating as with the ordinary Otto cycle. Furthermore, as in this Diesel cycle an excess of air is always used, this effect of expanding the incoming charge would probably do no harm anyway.

Mr. Howell, however, speaks about compounding. If this were done it would probably be advisable to use all the fuel that the oxygen of the air would unite with and perhaps to begin the admission of the fuel during the last of the compression stroke, thereby departing from the Diesel cycle in these two particulars. This would be necessary in order to get the highest possible terminal pressure so as to get the greatest advantage

from compounding. I feel, however, that Mr. Howell's estimate of the possible terminal pressure is somewhat high and that the advantage of compounding is somewhat doubtful.

HAROLD H. BROWN.

Boston, January 25, 1906.

## Time Signals from Electric Lights.

To the Editor of the SCIENTIFIC AMERICAN:

In modern life it is quite desirable that the people have a simple, inexpensive, and ready method of setting their clocks and watches to the correct time, at least once a day. In many cities and towns in the United States the correct time is distributed daily, by means of government time signals, telegraphed throughout the land at twelve o'clock noon. The Western Union Building, New York, and the Prudential Building, Buffalo, are provided with time balls. The ball drops at precisely twelve o'clock. Comparatively few of the inhabitants of those cities can make use of such signals. These can be seen only from certain positions and directions, and at short distances. Moreover, they can scarcely be seen, at any considerable distance, during rain and snow storms.

It recently occurred to the writer that time signals might be transmitted to nearly all the inhabitants of cities and towns which have central electric lighting stations. The proposed method, in its simplest form, may be described as it might be used in a town which has only one electric arc lighting circuit. At precisely nine o'clock each evening the attendant at the central electric lighting station would open the switch for a moment. All the arc lights on the circuit would blink at the instant of opening the switch. The speed of the electric current is about sixteen thousand miles a second, and the time required by the arc in blinking, or dying down to a red glow, is perhaps only about a quarter of a second after the opening of the switch.

In cities and towns where many electric arc lighting circuits radiate from one central station, the attendant at the electric lighting station might open the switch of circuit No. 1 at nine o'clock in the evening, the switch of circuit No. 2 at fifteen seconds past nine, and so on, until he had momentarily opened the switches of all the circuits radiating from his electric-lighting station. A printed card, in each house, might tell the inmates at exactly what time each arc-lighting circuit would momentarily be opened, and its lights in consequence caused to blink. Instead of printed cards, the local newspapers might contain this information once for all.

Time signals might also be transmitted in a similar manner on incandescent lighting circuits connected with central electric-lighting stations. Where the houses are fitted with incandescent lamps, on circuits connected with central stations, the convenience of incandescent electric lights as time signals would be even greater than that obtainable by arc lights.

In large stores and factories, it might even be advisable for the attendant at the dynamo to transmit a time signal throughout the establishment, at a certain hour each evening. All the employees would thus be enabled to secure the correct time while engaged in their regular vocations. The method might be used in order to distribute time signals on railway trains and ships. All the incandescent lamps might be caused to blink at a certain hour. Hence all the passengers might receive the correct time. The attendant at either a central station or a local plant might secure the correct time for transmission in one of several ways:

1. He might carry a well-regulated watch which could be compared with the government daily telegraphic time signal.
2. A telephonic time signal might be sent to him from some establishment in which a good regulator is already installed, and which is compared daily with the government telegraphic time signal.
3. An electric bell might be placed near the switches, and might be in a circuit connected with an establishment which contains a good regulator. A person in such an establishment might transmit a time signal to the attendant at the central station, shortly before nine o'clock each night.
4. A clock, synchronized hourly by one of the telegraph companies, might be set up near the switches, in the central electric lighting station.

If possible it would be well to have all the switches momentarily opened at nine o'clock, or other suitable time. But this would require an attendant at each switch; hence it would be impracticable. Perhaps inventors can devise a form of compound switch, supplementary to the ordinary switches, whereby one attendant might cause all the electric lights in all the circuits connected with one station to blink simultaneously.

The residents of a city using such time signals as I have herein proposed, would not only be enabled to secure the correct time daily, but also they would be enabled to regulate their clocks and watches with a high degree of accuracy and precision. The user of a watch, on leaving the city for a time, would be enabled to place more reliance upon his time-keeper.

In conclusion, it may be pointed out that one or more arc lamps can be seen from nearly every house

in a city, even during heavy rain and snow storms. Hence, nearly all the inhabitants might receive the correct time each evening, without leaving their houses; and, where electric lamps are used in the house, the inmates need not even look out of the window in order to receive the time signal. Moreover, the system, in its simple form, need not cause the outlay of a single dollar.

JAMES ASHER.

253 Hickory Street, Buffalo, N. Y., February 12, 1906.

## LIGHT POWER BOATS AT THE SPORTSMEN'S SHOW.

The most noteworthy development at the 1906 Sportsmen's Show, now being held in Madison Square Garden, is the application of the gasoline motor to all kinds of light craft for the purpose of propulsion. So far-reaching is this, that it extends even to St. Lawrence skiffs and to canoes. A portable apparatus that may be attached to any small boat in a few minutes, and which will be found illustrated on page 189, forms a further novel method of applying a motor to a light boat.

Among the various light launches exhibited, those built of steel are rather prominent on account of several unquestionable advantages—lightness, water-tightness, and the fact that they are non-sinkable—to be had from this form of construction. Two forms of small 16-foot launches of this type are shown on page 193. One of these is constructed of steel strips fastened together and to the framework by concealed galvanized steel rivets. As these rivets are not exposed to the weather, it is claimed that they can by no possibility rust and cause the boat to spring leaks. Another form is the smooth-skinned, pressed-steel boat, which is made of plates of steel pressed to the proper shape in powerful drop presses. The Michigan Steel Boat Company's craft is an example of the former, and the Mullins Company's boats of the latter construction.

The Michigan boat, as can readily be seen, is a very neat clinker-built launch 16 feet in length. It is fitted with an extremely simple, 1½-horse-power, two-cycle engine. This engine has a water-jacketed exhaust pipe, and a long spark-shifting lever with switch for cutting the current. This switch may readily be opened by pressing a button with the thumb as the hand grasps the lever. If the lever is moved to the other side of the center, and the switch released after the motor has been allowed to slow down, it will instantly reverse. An insulated, spring-pressed, brass block at the base of the lever presses against a fiber cam on the crankshaft, and when it rubs over a brass segment in the cam, the contact is made for the primary circuit, and sparks jump at the points of the spark plug in the top of the motor cylinder. The long, spark-shifting lever makes it possible to adjust the spark to a nicety, as a considerable movement of the top corresponds to a very slight advance or retardation of the time of contact. The crankshaft of the motor is made hollow, and the crank is lubricated by grease forced through from a grease cup at its forward end. Other grease cups lubricate the main bearings. The 2-horse-power motor has a 4¼-inch bore by 4½-inch stroke, and develops its power at about 500 R. P. M.

A considerable number of different types of boats are made by this concern. Among these are a small combination power, row, and sail boat; aluminium and steel canoes and ducking boats; a sectional steel boat made in two halves, one of which will fit inside the other; and a flat-bottom boat which may be folded and formed into a trunk.

In order to obtain a smooth-skinned steel boat, pressed steel plates, which have been galvanized and put through a special process that prevents scaling or cracking of the galvanized surface, are fitted snugly over the wooden framework of the hull. The joints of these plates are countersunk and riveted in a similar manner to the plates of an ocean steamer. They are afterward soldered and tested. The hull is consequently one piece of smooth steel, and is guaranteed against leakage at its joints. The keel is not bolted to the outside of the steel hull, but is inside the boat, being placed in a slot pressed into the steel shell for this purpose. It is thus protected, and adds great stiffness to the hull. The steel shell has a slight movement on the framework of the boat, and as the engine is mounted upon the framework, any vibration which the latter receives is not transmitted to the hull, and, consequently, does not tend to loosen its joints. The engine, which is placed in the center of the boat, has an exhaust pipe leading to a tube surrounding the propeller shaft and communicating with the water below the stern. The exhaust gases and cooling water pass through this tube into the water, thus doing away with all odor and noise. This under-water exhaust also has a tendency to keep the stern bearings lubricated.

In both these types of steel boats large air chambers are placed at the front and rear. These are sufficient to keep the boats afloat, even should they become filled with water. As they are built of steel, there is no danger of their destruction from fire. These qualities, together with their durability, make them ideal craft for pleasure or business purposes.

### A TYPICAL TWO-CYCLE MARINE MOTOR.

The cross-sectional cut shown herewith gives a very good idea of the interior construction of a Lozier marine two-cycle engine. This engine may be taken as a typical example of the two-cycle type. The piston, *X* (which is fitted with rings, *HHH*), is shown moving downward on the power stroke, being propelled by the burning gases in the cylinder, *D*. The movable electrode, *E*, of the igniter is shown separated from the insulated pin, *P*, which it touched and quickly snapped away from when the piston was at the top of the stroke. Upon the breaking of the circuit a spark was produced, and this exploded the gases. As soon as the piston uncovers the port, *F*, the burnt gases will blow out through the exhaust pipe (which is water-jacketed) by means of their own pressure. A moment later, when at the end of its downward stroke, the piston uncovers the inlet port, *C*, whereupon the compressed charge in the crankcase, *B*, will expand into the cylinder, *D*, being directed upward by the deflector plate, *G*. The piston will then move upward, and compress this fresh charge. At the same time it will produce suction in the pipe, *A*, and will raise the valve, *J*, thus allowing gasoline entering through the pipe, *K*, to flow past the needle valve (which terminates in the seat of valve, *J*), and be drawn through the intervening passages and pipe, *A*, into the crankcase, where it is compressed on the next downward stroke of the piston. An adjustable screw regulates the lift of the valve, *J*, and the needle valve can also be set for the proper amount of fuel. At the base of the rod, *O*, is a butterfly throttle valve used for throttling the mixture. The mechanism which operates the igniter is seen on the right of the motor cylinder. The pump, *L*, draws in water through the check valve, *S*, and circulates it through the water jackets, *M*. This pump is operated by an eccentric. The pipe, *T*, is used for introducing a certain amount of oil into the crankcase. This serves to lubricate the crank and wristpin by means of the splash. The main crankshaft bearings are lubricated by grease cups. The above description will give the novice some idea of the construction of the two-cycle motor.


### ELECTRIC LAUNCH WITH RECHARGING EQUIPMENT.

An improvement in electric launches, whereby they are made independent of an outside source of current for recharging the batteries, has been brought out by the Electric Launch Company on their 1906 pleasure craft. This consists of a horizontal double-opposed-cylinder motor placed just in front of the electric motor and adapted so as to be connected with it by a jaw clutch when, at the end of the run, it is desired to recharge the battery. The gasoline motor has a portable fuel tank, which may be filled, placed outside

motor provided gasoline is carried on board. It is always started by the electric motor, and no cranking is necessary. Jaw clutches are provided between the motors and between the electric motor and the propeller shaft. The arrangement is an ideal one, as it makes possible the use of the silent electric launch under all conditions; while, with the battery charged, there is never any doubt about starting and taking a sail when one wishes. Ladies or children can operate

pocket on one side for the exhaust valve, which is operated by a direct lift from the cam. The inlet valve is located directly over the exhaust, and is opened by a downward push, which is obtained by a reciprocating rod operated by the inlet cam. The rod passing up one side of the cylinder pushes on one end of a lever bracketed on top of the cylinder, the other end of which lever opens the valve. The relative position of the exhaust and inlet valves is advantageous, as

the cool, incoming gas is obliged to pass over the hot exhaust valve, thus helping to keep it cool and lengthening its life, by preventing the distortion and deterioration which so often take place from overheating this valve. The pistons and connecting rods of these engines are made as light as is consistent with good practice, thus permitting high piston speed with minimum vibration. All bearings are of ample size, to insure long service and an absence of excessive heating. The valves can be removed and reground with the removal of but a few simple parts. The problem of oil tightness has been satisfactorily solved, as the engine is practically oil tight. No leaky joints are to be found, as is so often the case where screw connections are used in the water pipes. The engines are also designed to be pleasing to the eye, with well-rounded cylinders, polished cast-bronze water pipes, inlet pipes, and inlet valve covers. The engines are not designed on the lines of an automobile engine, but according to safe mechanical construction, which would be acceptable in any stationary engine intended to run for long periods without stopping. The accessibility of all important parts of the engine—a feature so often overlooked in gas engine design—has also been carefully worked out. Throughout the best material is used, such as



CROSS-SECTION OF TYPICAL TWO-CYCLE MARINE MOTOR.

these boats as readily as can men. For recharging *in situ* gasoline motors of from 4 to 10 horse-power are fitted according to the size of the launch. These boats range in speed from 7 to 9 miles an hour under electric propulsion, and from 10 to 12 with the motors combined. They have a radius on a charge of 50, 65, or 90 miles according to the size of the battery installed. Forty 150 ampere-hour cells is the smallest battery used. The 8-horse-power electric motor develops normally about 5 horse-power and consumes 30 amperes of current for the 7-miles-an-hour speed.


### THE NEW "SPEEDWAY" MARINE ENGINE.

One of our illustrations represents a four-cylinder "Speedway" gasoline engine of 6-inch cylinder bore by 6-inch stroke, capable of developing 40 horse-power at 850 revolutions per minute.


These engines, of the type shown in cut, work on the four-cycle principle, and are designed with a reversing clutch for marine use. The engine shown is adapted for use in either pleasure cruisers or working

nickel-steel crankshafts and exhaust valves, phosphor-bronze bushings in the upper end on connecting rods, and in other places where bronze bearings are used. The engine parts are made to jigs as far as possible, thus making it easy to replace parts quickly and satisfactorily. Ball-bearing thrusts are used, and these are carefully protected from water. The larger sizes of these engines are designed to be started by compressed air. Several sizes of two-cycle "Speedway" motors are also built by this company, embodying all the up-to-date devices.

The reversing clutch used with four-cycle engines is of the planetary type. All cut spur gears are of steel of the finest material and used extensively. The friction clutch is of special design and of more than usual power. It is easily manipulated, and so constructed that the wear is very slight. Adjustment is simple and quickly made. For high-speed boats, where the utmost power possible is required to be developed by the engine, a clutch that is absolutely positive is used, friction not being depended upon to rotate the shaft.



GASOLINE MOTOR DIRECT-CONNECTED TO ELECTRIC MOTOR FOR RECHARGING THE BATTERIES OF AN ELECTRIC LAUNCH.



40 H. P. MARINE MOTOR WITH CLUTCH AND REVERSE DRUM. THE IGNITION DYNAMO IS PLACED ON END ABOVE THE FLYWHEEL.

the boat, and connected to the carburetor through a flexible pipe when it is desired to recharge the batteries. This can be accomplished in three or four hours. Both motors are placed at the rear of the boat under the floor, which is raised some inches above the main floor at this point. The batteries are placed in the bottom of the boat forward of the motors. In case of emergency, or if more speed is wanted, the gasoline motor can be run in conjunction with the electric

boats. A lighter stanchion engine is built for high-speed motor boats. The sizes of these four-cycle motors range from 8 to 150 horse-power, the number of cylinders being ordinarily four and six.

The cut represents the standard type, with cast-iron base and frame in two separate parts. The camshaft is on the outside of the frame, thus making it possible to take this shaft out easily without dismantling the engine. The cylinders are cast separately, with a


This arrangement embodies an entirely novel design brought out by this company during the fall of 1905, a patent for which has been applied for. It is so constructed that no matter how much power is applied, it cannot slip in any manner.

The manufacturers' special claims for these engines are: Up-to-date design, superior material and workmanship, and a resultant reliability, high efficiency, and durability.



### A SIXTEEN-CYLINDER MOTOR-BOAT ENGINE OF 180 HORSE-POWER.

The new 8-cylinder gasoline motor which has been brought out at Paris by M. Levavasseur, has a number of novel features. Our illustration shows two 90-horse-



**TWO 90-HORSE-POWER, 8-CYLINDER MOTORS CONNECTED IN TANDEM IN THE RACER "ANTOINETTE III."**


power motors as mounted in tandem on the launch "Antoinette," one of the prize winners of the season. By the use of eight cylinders great steadiness of power is secured as an impulse is obtained every one quarter of a revolution, and hence the flywheel can be dispensed with. Another great advantage lies in the fact that the motor can be run in either direction by the placing of special cams upon the cam shaft. By pulling a small handle located at the end of the cam shaft, the cams are shifted and the motor is reversed. The constructors claim that the new motor thus has the advantages of a steam engine.

The carburetion is produced by a small gasoline pump worked from the motor. It draws gasoline from the tank and sends it to eight small distributors placed at the top of each motor on the inlet. These regulate the supply of liquid, causing the spray action which is needed. The output of the pump is variable at will, but its automatic action is preserved, as it is run from the motor. Good carburetion is always secured in this way, and the method has an advantage in suppressing a large amount of piping.

The new "Antoinette" motor consists of eight cylinders mounted four on each side and at an angle of 45 degrees upon a crank case, as will be noticed. The eight cranks work on a single shaft. A cam shaft works the eight exhaust valves. What is to be remarked about the new motor is its great lightness in proportion to the power it will give. The 90 to 100 horse-power motor, having a 5.2-inch bore and stroke, weighs but 330 pounds, not including the reversing mechanism and ignition devices. With the latter, the weight is 370 pounds. It measures only 32 inches long and somewhat less in height. The great advantage of the motor when applied to a launch lies in the fact that it can be used to operate the propeller di-

rectly without needing a friction clutch or a reversing mechanism. It also starts up as soon as the ignition is set working, seeing that two of the cylinders are always in action. The new motor is claimed to be the lightest per horse-power that has yet been produced,

Before dipping into the precise details of the boat to be described, it may not be amiss to state that the question of the use of a duplicate plant in its entirety is one now receiving much attention from designers and users alike, and the trend of motor-boat construc-




**A NEW TWIN-SCREW SERVICE BOAT FITTED WITH TWO SEPARATE POWER PLANTS OF 30 HORSE-POWER EACH. THIS BOAT IS INTENDED FOR USE ON LAKES AND RIVERS**

this figure being 3.3 pounds per horse-power, and it is thus specially adapted for use upon airships. The smallest motor which has been constructed is a 40-horse-power size, while the largest size gives 400 horse-power. With the two 90-100 horse-power motors the launch "Antoinette III." made a remarkable performance lately at the Monaco races, where it took one of the prizes.

### A SERVICEABLE TWIN-SCREW MOTOR BOAT.

BY THOMAS J. FAY, E.E.

Twin-screw motor boats, if not altogether new, are quite rare, to say the least. This is not because the principle of twin-screw propulsion is in any way in question, but because motor-boat work did not grow up to the level of twin-screw products until very recently.



**A SIMPLE 1 1/2-HORSE-POWER, 2-CYCLE LAUNCH MOTOR.**

tion is toward more power, greater safety, and immunity from any serious inconvenience in the event of a mishap to any of the equipment.

At first it was thought the best way to obtain more power was to put two motors in "tandem." A few attempts at this arrangement put an end to it entirely, except in cases, like the "Dixie" and the "Challenger," involving the design and construction of eight-cylinder motors with integral bases and especially designed crankshafts, as well as an arrangement of accessories to match.


This, however, is altogether different from putting two motors in tandem and coupling their crankshafts together; for, as anyone can see, the crankshaft, barely large enough to sustain the power impulses of its own four cylinders, would be practically useless after sustaining the extra effort of four more cylinders for even a short while.

The best way, without any doubt, to realize the fullest benefit from the use of eight cylinders is to employ two motors in such a way as to afford two complete and independent power plants, even to the extent of employing two separate and distinct fuel tanks, and of course two screws, not to mention the attending accessories.

It is the purpose here within the brief space afforded to point out the most conspicuous features of one of the latest creations in the Simplex series. The main dimensions of this twin-screw boat are as follows:

**HULL DIMENSIONS.**—Extreme length, 45 feet; Load-water length, 44 feet; extreme beam, 6 feet 6 inches; water line beam, 6 feet; draft, 10 inches; propeller draft, 2 feet 5 inches; approximate speed, 20 miles per hour.

**MOTOR DIMENSIONS.**—Number of motors, 2; rated horse-power of each, 30; total rated horse-power, 60;



**LIGHT, CHEAP, AND SERVICEABLE STEEL LAUNCHES FITTED WITH AIR TANKS WHICH MAKE THEM UNSINKABLE.**

number of cylinders, 4 per motor; bore of cylinders, 4½ inches; stroke of piston, 5½ inches; type of motor four cycle; rated speed of crankshaft, 800 to 1,000 R. P. M.; fuel tank capacity, 60 gallons; fuel radius, 150 miles.

The first essential and important difference between this equipment and the conventional motor-boat installation, lies in the fact that the machinery equipment in its entirety is a separate self-contained unit, or, in this case, double unit in fact. The machinery complete is in no way dependent upon the hull for even its supports, for the entire equipment is first set up on its own independent girders in the shop, and upon its completion and test is lowered into the hull as a unit ready to run.

The old method of hanging the magneto to the skin on the starboard side and the carburetor to the ribs on the port side, or suspending the oil piping from the sheer-strake and hiding the battery in the fore peak where no one would be able to find it, is not adhered to in the least in this new system of construction. As just stated, the machinery in this case is absolutely separate and distinct from the hull in every way. It was found, in fact, that men accustomed to hull work were not efficient around machinery, and it has been the invariable custom with the present constructors to keep the respective classes of work separate, even to utilizing separate buildings remote from each other, the one for motors and the other for boats.

The appearance and general arrangement of the new twin-screw boat is made apparent from our illustration. As can be readily seen, the engines are very compactly placed in a cockpit at the center. The spark coils and control levers are on panels just back of the motors, where they are very accessible.

The sparking equipment consists of both a magneto and a storage battery, either one of which may be used at will. The timing of the spark is properly fixed by means of the Simplex jump spark timer.

The carburetion is taken care of by a governor-controlled Mercedes type of carburetor. There are important differences, however, between the Simplex carburetor and the Mercedes type it represents. As a matter of fact, the mixture provided to the motor through this carburetor is always rich enough to assure prompt starting, and is adjusted thereafter automatically to afford the right air dilution for all speeds.

The governor is of the "flyball" type on the camshaft, and is connected up by straight-line levers, while the oil pipes and other parts are neatly and securely fixed to the motor.

Among the novelties of construction may be noted an improved sea cock, by means of which the water for cooling is taken through the skin of the hull aided by a scoop, and screened before it reaches the gear circulating pump. This sea cock has a rubber ball which acts as a check valve and as a positive valve as well, and it is one of the nice fittings especially developed for motor-boat work, which differs in important details from the work done in hulls prior to the advent of motor boats of the higher order.


The gasoline tanks are protected by surrounding them with a copper jacket, and thus keeping them submerged in sea water. The fittings are so arranged as to afford entire immunity from accidents as a result of a leaky joint if, perchance, such a contingency should arise. At the same time, one may examine every joint in a moment at will, without even shutting down the plant. Moreover, leaks are highly improbable, because the scheme of piping is so thoroughly worked out as to eliminate such occurrences excepting as a rare contingency.

In the construction of the hull, Parsons manganese bronze castings are used, to the exclusion of composition or other cheaper brass products. The framing of the hull, while light, is of the finest white oak, while the planking is of Mexican mahogany and British Columbia cedar. Natural knees take the place of jointed members where knees are used, and copper fastenings are used throughout. The cutwater is of bronze finished to a knife edge, while the propellers of three blades each, as well as the rudder quadrant and other similar devices, are all of a special design of the same high-grade bronze.

This boat has a large seating capacity, possesses great stability, and is intended for family use on one of our inland lakes. The internal arrangements include every requisite for comfort, with ample storage under seats, while a canopy top will enable the owner to use the boat in fine and inclement weather alike. For the accommodation of ladies, the after end of the after pit may be curtained off; but all super work may be removed at will to accommodate a large fishing party on a fine day.


#### IMPROVEMENTS IN SPARK COIL CONSTRUCTION.

The spark coil depicted in the accompanying engravings embodies a number of interesting constructional features. The coils are made up in sets of two, three, or four, according to the number of cylinders of the engine, and are compactly stowed in a single case. The cover of the case is locked in place by means of




AN IMPROVED SPARK COIL.

the hooks which are shown in Figs. 1 and 2. These, it will be observed, are mounted eccentrically on the hubs of a pair of thumb levers, which may be operated to lift the hooks, as in Fig. 2, thus causing them to tighten their hold on the pins. When it is desired to remove a coil, only the primary terminal, P, need be unfastened, as the other connections are made by means



DETAILS OF THE SPARK COIL.

of contact plates at the bottom of the casing. The secondary terminal wire, which passes down inside of the coil, makes connection with a binding post at the bottom of the casing. This post differs from the ordinary type. Instead of binding the wire by screwing a setscrew against it, the setscrew is fed against a ball which bears against the wire, as shown in section in



DIRECT-CONNECTED ELECTRIC-CURRENT GENERATING SET FOR STATIONARY OR MARINE USE.

Fig. 3. This insures a good contact, and prevents injury to the wire. An important feature of the coil is the novel construction of the interrupter, which is clearly indicated in Fig. 4. The spring of the vibrator, V, is held between the block, D, and the heavy spring plate, S, which are clamped together by means of a screw, E, threaded into the plate, B. The thumbscrew A provides for the adjustment of the vibrator toward and from the core of the coil. The thumbscrew is threaded through the plate B, and is formed at its lower end with a groove adapted to engage a slot in the lower portion of the spring plate, S, which is secured to the coil head. Since the lower portion of the plate, S, is fixed, it follows that when the screw, A, is turned in one direction, it will move the block, D, down, carrying the vibrator toward the core, and when turned in the other direction it will positively lift the vibrator from the core, regardless of the spring tension of the plate, S. It is customary in other constructions to depend on a spring for the adjustment in one direction, but the spring is apt to become weakened in time, and for this reason the positive adjustment in both directions is provided in the present construction. The thumbscrew, A, passes through a split bearing in the block, D, and a setscrew is provided for tightening this bearing onto the body of the thumb-screw when the proper adjustment has been secured. By loosening the screw, E, the vibrator is released and may be withdrawn, as the vibrator spring is slotted to clear the body of this screw and that of the thumbscrew, A. The contact screw, C, is threaded into a split yoke-frame, which may be closed onto the screw to hold it at the desired adjustment.

#### Elastic Supports for Machines.

In a recent conference at the Sorbonne, M. Anthoni gave an account of the means which were used to do away with shocks, noise, and vibration, and showed the advantages and disadvantages of different kinds of compressible and non-compressible materials for this purpose. The first class, such as cork, carpet, felt, fur, etc., have the disadvantage of a lack of homogeneity and lack of constant properties, since they are resilient and work by the flexion of their particles, thus breaking down gradually. The second class, the incompressible materials, he divides into non-plastic matter such as sand and asphalt, and the plastic and elastic materials like rubber. To allow a machine to run without noise or shocks he devised a new elastic support which is portable. It is formed of two concentric cubes, the inner one being heavy and firmly fixed to the ground, and the outer one being hollow and attached to the machine. The two cubes are separated by six washers bearing on the cube faces, tending to compress the inner cube and press out the faces of the outer cube. The lower face of the large cube is formed of a steel disk. From it a bolt passes through the inner cube without touching it. The base which connects the inner cube to the ground passes between the steel disk and the vertical faces of the large cube which carry brace-pieces allowing the washers to be tightened. In this way he mounted two engine and dynamo groups of 125 and 60 horse-power with Willans engines running at 500 revolutions. No noise or other trouble was found in this case.

#### VIBRATIONLESS ELECTRIC LIGHT SETS FOR YACHTS.

One of the interesting exhibits at the National Motor Boat and Sportsmen's Show is a vibrationless direct-connected electric light set, which we illustrate herewith. These sets are made up with genuine imported De Dion engines direct-connected to generators especially built for the purpose. The engines are throttle governed and the whole equipment is thoroughly up-to-date. They are the most compact, light-weight sets on the market for their output, and are provided with a special vibrationless support which allows them to be used for launch and yacht work. By means of this special coiled spring suspension, every particle of vibration and a large part of the noise is eliminated, so that the sets are exhibited in operation, placed on a light box without being fastened down. The engines run at moderate speed, and are of an especially durable type, well known to the automobile public for their reliability, endurance, and steady running. These sets will produce perfectly steady light, there being no flickering whatsoever. A special type of ball throttle governor is used for controlling the speed, and the ignition is jump spark. These sets are wound for various voltages depending upon their use—for storage battery charging, house lighting, and launch and yacht lighting. They have proven very popular, quite a number having been installed up to the present. One of these sets is shown in operation in the basement of Madison Square Garden at the present show.



**ARTIFICIAL SEA BATHS.**

BY DR. ALFRED GRADENWITZ.

A decided novelty for inland summer resorts is provided by the artificial surf bath which is herewith illustrated. The scheme is the invention of Herr Hög-lauer, of Munich, Germany. With the assistance of Herr H. Recknagel, a plant was installed in the Starn-berg lake near Munich, last summer, and proved to be a great success, yielding very satisfactory financial re-sults. The project calls for a tank of water, or the inclosure of a portion of the lake or river in which it is installed, as shown in the photographs. At the outer end of the in-closure is the wave-forming machinery which com-prises either an oscillating partition or a plunger dropped periodically into the water. In this way the waves are formed and they travel the length of the tank. The tank is provided with a sloping bottom so that the reced-ing waters from one wave, meeting the succeeding wave, will cause the latter to curl and break in per-fect imitation of the ocean surf. If the device is in-stalled in a tank, it is pos-sible to exactly reproduce the conditions of ocean bathing by adding salt to the water and thus pre-serving the hygienic and therapeutic properties of the ocean bath. The power necessary to produce the waves is very small, as the motion is rhythmic. For example, in the case of waves measuring 2 meters (6.5 feet) from crest to crest, the best results are secured with a rate of 18 waves per minute, when the expenditure of energy will be 4 horse-power for a tank 1 meter (3.3 feet) in breadth. If steam power be used, the exhaust steam of the engine may be utilized for heating the water. Thus the temperature of a bath may be regulated to the desired degree and by the proper control of the engine the roughness of the waves may also be regulated so as to make the bath an ideal one. The inventor has also designed a small device for use in tubs, whereby the tub is rocked to produce the wave effect. The rock-ing of the tub may be effected either with an electric motor or by means of oars operated by the bather himself.

**COUNT VON ZEPPELIN'S DIRIGIBLE AIRSHIP.**

General Count von Zeppelin has repeated the Bo-densee experiments with his dirigible airship, which were concluded in 1900, and undertook an ascension on November 30. For several reasons, in no way involv-ing the principle of construction, it was necessary to desist from this attempt for the present.

For the sake of completeness, it is necessary briefly to recount the results of the experiments of 1900, which at the time were discussed in well-illustrated articles in the SCIENTIFIC AMERICAN. Three flights

were accomplished five years ago—on the 2d of July, the 17th and 21st of October. In July the craft demon-strated that it could be steered and propelled against a breeze moving at the rate of about 18 feet a second. At that time the full power of the engines was not utilized, as strong longitudinal oscillations had to be contended with, these being due to the fact that the rear retaining ropes of the airship were released too late. In addition, the crank of the adjustable sliding


The dirigibility was excellently demonstrated, this time in fact with two instead of four steering surfaces. Several great arcs were described to right and left. After a flight of 23 minutes a landing was made, again because of the lateness of the hour. As the financial resources of the constructing company were exhausted, further experiments were not possible.

The speed attained by the airship itself was found to be 24.5 feet per second, a rate, nearly 18 miles per hour, never before accom-plished. The determina-tion was made by three careful and independent surveyors, stationed at three different points on the shores of the Bodensee. The wind blew at the rate of about 11 feet per sec-ond. Taking into consid-eration the curves of the flight, Prof. Hergesell has calculated the independent speed to have been as high as 28 feet a second. This success was unquestion-able.


Following the experience gained in 1900, the motor airship was improved in almost all its details. The greatest advance lies in the increase of the motive power with practically no increase of weight. Each of the engines in the two carriages is now of 85 horse-power, so that to-day 170 horse-power is avail-able instead of 30 as for-merly. As this weighs only 11 pounds more than the earlier installation—880 pounds *in toto*—even the layman will recognize that the independent speed of the craft must be far greater. The length of the airship has been decreased by about two yards, the diameter being made some-what greater. With a length over all of nearly 410 feet, the diameter is a

trifle over 38 feet. Instead of seventeen gas compart-ments, the balloon now contains one less, with a total cubical content of hydrogen gas of about 367,120 feet, some 31,700 cubic feet less than in the former model. The total weight to be lifted is about 19,800 pounds, nearly 2,200 less than in 1900. The propellers have been made somewhat larger.

The two steersmen or guides, aeronautic and aero-static, were located in the forward car, where also were the wires, arranged visibly upon a board, which led to the valves of the gas chambers and the ballast bags. The latter, made of a waterproof material and filled with liquid, were equally distributed upon the skeleton; part of the ballast was also located upon the cars, and two of the bags are distinctly visible upon one of the accompanying photographs. Benzine, suf-ficient for a trip lasting 15 to 20 hours, was carried in special tanks in the two cars. In the possibility of long flight duration, the Zeppelin airship possesses a particular advantage which Lebaudy has not yet taken into consideration. This, too, is the reason why Count Zeppelin built his ship of such great size. If it is de-sired to transport large weights, it is necessary to con-



TRIAL TRIP OF ZEPPELIN'S IMPROVED AIRSHIP.





THE IMPROVED DIRIGIBLE AIRSHIP OF COUNT ZEPPELIN.

weight broke, so that it was possible to maintain a state of equilibrium only by running the engines alter-nately forward and backward. The landing upon the surface of the lake, announced beforehand by means of flag signals, was completely successful.

After a number of improvements, complicated through an unfortunate occurrence—the failure of cer-tain fastenings of the framework and the collapse of the middle part—the second trial trip took place. A position of equilibrium was attained successfully at a height of about 300 yards, but the steering-gear caught in the outer portion of the skeleton and was held to port, thus producing a swinging movement. This was counteracted by using the second rudder in opposition to the other; but this time also it was not possible to use full power, as the hour was late and a landing was imperative. This was accomplished sooner than was intended, as a valve in the balloon opened of its own accord, permitting the escape of the gas in a forward compartment. The ship had been in the air for 80 minutes.

Both defects were soon remedied, and four days later the imposing craft rose into the air for the third time.



AN APPARATUS FOR PRODUCING ARTIFICIAL SURF BY MEANS OF AN OSCILLATING PARTITION OR A PLUNGER DROPPED PERIODICALLY INTO A TANK OR INCLOSURE CONTAINING WATER.

struct large airships; this is dependent upon the carrying capacity of the gases. Fore and aft there are three vertical linen surfaces for horizontal steering. Between these and the car bodies are horizontal surfaces for vertical steering, the vanes being arranged one above the other as in an aeroplane. The aeronautic guide or steersman controls all rudders from his position.

In the test of November 30, it was noticed that the


The experiments will soon be renewed. It must be remarked that this trip was undertaken merely as a tentative trial. Count von Zeppelin never intended to immediately travel back and forth over the Bodensee for hours, but all the details were thoroughly to be tested, first in shorter and then in longer flights. Many people expect immediate and successful results from a structure as difficult to control as a dirigible airship, while this is not the case in other new ma-

great changes will appreciate what this means. This complete air compartment serves as a perfect protection against either heat or cold.


In ordinary weather only two pegs are necessary to stake it. When exposed to a strong wind, more pegs may be used.

#### HOW SNAKES FEED.


The manner in which snakes procure and consume




Approaching His Prey.




The Prey Captured.



Swallowing Well Under Way.



Only the Head and Forelegs Project.



The End.

#### HOW SNAKES FEED.

aeronautic steersman of 1900, Von Krogh, was located in the rear car and was replaced, forward, by the engineer of the airship. This change of the guidance in tests of such a difficult nature naturally caused some surprise among the experts, especially as the steersman was able to acquire but little experience in the few ascensions he had undertaken previously in a balloon of the ordinary type. Every aeronaut is familiar with the difficulty in the guidance of a large balloon of even the usual kind, and in a motor airship this difficulty is largely aggravated.

The filling of the gas-bag was accomplished on November 29 in six hours—the first attempt required fourteen, the second seven hours—and on the following day the craft was drawn out from the house, the wind at this time having a velocity of 19.5 feet per second. In the forward car were Count von Zeppelin, Engineer Dürr, and two machinists, and in the after car, Von Krogh, Eugen Wolf (the well-known African traveler, who also participated in the trials of 1900), and two machinists. According to the various newspaper accounts published by Eugen Wolf and the accounts of witnesses upon the balloon house, a steamer, etc., the trial occurred as follows: The running out of the craft from the house presented the first difficulty, for the lake was at a very low level, and the airship could not, as intended, be drawn out upon the lake while resting on a float, but had to be pulled forth directly by means of a tug. The turning against the wind, which blew toward the shore, was not intended to take place until a position farther out in the lake had been attained. But small causes give rise to great effects. The wind drove the airship ahead of the tug, so that it was necessary to drop the towrope. Because of a knot in the latter, it remained attached to the balloon, and this received so strong an impulse at the forward extremity, that the forward steering apparatus


chines. It is to be hoped that we shall soon hear something further about the airship of the energetic Count.

#### A NOVEL TENT.

BY EMILE GUARINI.

A most interesting tent has recently been constructed by Mr. Frank H. Gotsche, of San Francisco, Cal. The tent is remarkable for its portability. It is easy to pitch and fasten, and is not easily blown down. The shape is very convenient. For the amount of canvas used a remarkably large capacity is obtained.


The frame is made up of four wooden sections. These frame sections are held together by metal sleeves or couplings. When ready to pitch the tent, the frame is drawn into a semi-circle and the ends stuck into the ground four to six inches. The cover




Side View of the Tent.



Double Tent Half Open.



Ready for Transportation.



Entrance to Double Tent.

#### A NOVEL TENT.

entered the water while the after car was still suspended in the air. Furthermore, the forward motor obstinately refused to work. By means of the release of ballast and through the efforts of the second motor, the airship was again sent aloft; but as the forward steering gear had become useless, the trial was soon given up, and the airship returned to the house, where it arrived after the expiration of an hour and a half.

is then stretched out and drawn over the frame.

A peculiarly advantageous feature of this tent is the fact that a tent of one or two sizes larger can be set over another without touching the smaller tent at any point, thus leaving a complete compartment of air around the inner tent six to twelve inches deep. All who have had to live in permanent camps or in places where the temperature was subject to frequent and


their food is of ever-recurring interest to all of us, but as this detail of natural history is known to nearly everyone, the accompanying illustrations require little explanation. In the first of the engravings is depicted the rather dignified but nevertheless determined advance of the reptile upon its victim, in this case a good-sized frog, whose attitude denotes an indifference to be followed by dire results later. In the second photograph the frog is shown making desperate efforts to escape from the snake, which has seized the unfortunate by the hind leg, after the sudden dart in which the gradual approach culminated. The third photograph shows the act of swallowing the prey well under way, while in the next the frog has been so far consumed that only the head and fore-legs project from the mouth of the reptile. In this and in the last illustration, the remarkable distending powers of the elastic jaws of the snake are shown; and if we compare the head of the reptile in the first and last photographs, we find it difficult to believe that the creature is the same in both instances. That the swallowing of the frog was not a very difficult performance is demonstrated by the fact that from the positions of the snake in the last three pictures, it apparently was obliged to move only the fore part of its body while at the latter stages of the meal.

#### New Manufactory for Computing Scales.

A large factory for the manufacture of computing scales is about to be built near Asheville, N. C., by C. F. Christopher, who is the inventor of nine different kinds of these automatic weighing devices. The inventor comes from the western part of Pennsylvania, and while employed as a railroad brakeman, devised an improvement in the locks used on turntables. After he had perfected this invention he dis-

posed of it for \$3,500. He turned his attention to other inventions, and made several improvements of different kinds, but the computing scale was the most promising, so that he followed this up with a number of others, and surrounded himself with quite a large business. A local newspaper is authority for the statement that this invention realized \$57,000 for the inventor.





# WALTHAM WATCHES

Always On Time

*"The Perfected American Watch," an Illustrated book of interesting information about watches, free upon request.*

AMERICAN WALTHAM WATCH COMPANY  
WALTHAM, MASS.

**"Star" Lathe** Foot and Power  
Automatic Cross Feed  
FOR FINE, ACCURATE WORK  
Send for Catalogue B.  
SENECA FALLS MFG. CO.  
695 Water Street,  
Seneca Falls, N. Y., U. S. A.

**Engine and Foot Lathes**  
MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. BEST MATERIALS. BEST WORKMANSHIP. CATALOGUE FREE  
SEBASTIAN LATHE CO., 120 Culvert St., Cincinnati, O.

**THE CLIPPER CLIP**  
Its triangular shape prevents entangling and gives three times the capacity of any other clip for attaching papers together.  
Best & Cheapest. All Stationers.  
CLIPPER MFG. CO.,  
401 West 124th St., New York, U. S. A.  
For free samples and information write to us.

**THE BARKER MOTOR**  
has from the first shown itself to be of superior design. Mechanical ideas of proven worth, combined with the best materials and careful attention to details make it  
THE LEADER OF ITS CLASS.  
C. L. BARKER, NORWALK, CONN.

**ORIGINAL BARNES Upright Drills**  
Positive Feed  
10 to 50-inch Swing  
Send for Drill Catalogue.  
W. F. & JNO. BARNES CO.  
(Established 1872)  
1999 Ruby St., Rockford, Ill.

Andrew Carnegie, Thomas A. Edison and many other successful men began their careers at Telegraph Operating. Why don't you learn? For \$1.75 we will send you a complete N. D. outfit with book of instructions, by express (not prepaid). Send for catalog of electric apparatus, supplies and novelties.  
J. H. BUNNELL & CO., Inc., 20 Park Place, New York

**ROTARY PUMPS AND ENGINES.**  
Their Origin and Development.—An important series of papers giving a historical resume of the rotary pump and engine from 1568 and illustrated with clear drawings showing the construction of various forms of pumps and engines. 38 illustrations. Contained in SUPPLEMENTS 1109, 1110, 1111. Price 10 cents each. For sale by Munn & Co. and all newsdealers.

**The Genuine Armstrong's STOCKS and DIES**  
Acknowledged to be the best. Different sizes and capacities. Write for catalog.  
THE ARMSTRONG MFG. CO., Bridgeport, Conn.  
New York Office, 139 Centre Street

**Keystone Well Drills**  
for Artesian and Ordinary Water Wells; Mineral Prospecting and Placer T-sting for Dredgers; Deep Drilling for Oil and Gas; Contractor's Blast Hole Drilling, River and Harbor Exploration, etc. Our five catalogs are text-books in these lines.  
KEystone WELL WORKS  
Beaver Falls, Pa.

**Williams' Spark Coils**  
are reliable in every sense of the word; they are all thoroughly tested before leaving the factory, and are right in every respect. Let us tell you more about them.  
E. Q. WILLIAMS,  
538 S. Clinton St.,  
Syracuse, N. Y.

**Nickel Plate Road Again Selling Colonist Tickets to the Pacific Coast.**  
Extremely low rate tickets on sale daily until April 7 to Pacific Coast and other points in the Far West. Tickets good on any of our trains and in tourist sleepers. For particulars write A. W. ECCLESTONE, D. P. A., 385 Broadway, New York City.

**Mustard & Company**  
GENERAL IMPORTERS AND COMMISSION AGENTS  
Plumbing Supplies, Saws and Scales. The largest Hardware Machinery and Tool House in China  
9a NANKING ROAD - SHANGHAI, CHINA

**American Homes and Gardens**  
BOUND—VOLUME ONE  
Profusely Illustrated. Large Quarto. 426 Pages. Green Cloth Covers Produced in Several Colors. A Beautiful Book. Price \$3.50  
This volume, containing house plans, many suggestions for the decoration and furnishing of the home; also for the improvement of the grounds and the gardens, is indispensable to those requiring such information.  
MUNN & CO., Publishers of the Scientific American  
361 Broadway, New York

### RECENTLY PATENTED INVENTIONS.

#### Of Interest to Farmers.

**FENCE-POST.**—G. R. WYATT, Redwood City, Cal. One object of this case is to provide a metal fence-post well adapted for receiving and supporting fence-wire material, that may be either separate wires or material woven from wires. A further object is to provide novel means which co-operate with the posts for stretching and locking fence material upon a plurality of novel posts. Also braces for supporting the fence-posts and for maintaining the fence-wire material stretched taut; also protecting-casing for the base portion of the posts.

**STACKER FOR GRAIN OR THE LIKE.**—J. H. BULLOCK, Millerton, Kan. Mr. Bullock employs a stacker comprising a base-section of special construction, in connection with which is employed a crown or superposed section of special construction, imparting to the completed stock of grain, hay, or the like a contour or shape resulting in the effectual shedding off of rain or snow from the upper part of the stack and at such a distance from the base of the stack as to prevent material of the stack from being affected or injured thereby.

#### Of General Interest.

**CONFORMER-CORSET.**—C. MUNTER, New York, N. Y. One purpose of the invention is to so construct the health brace-corset that it will conform to and fit the body practically as smoothly as the natural skin, the shaping of the various parts being devoted to that end, especially at the armholes and shoulders, so that when the corset is tightened up upon the person it will gradually restore the bones and muscles at the chest, shoulders, and back to normal position, smooth the skin, and cause the lungs and bronchial tubes to be unobstructed, thus permitting regular easy breathing.

**STAIR STRUCTURE.**—M. PLOTKIN, New York, N. Y. This invention relates to improvements in the construction of sheet-metal stairs, the object being to provide a metal stairs with a means for securing rock-asphalt, concrete, or the like on the treads in such a manner as to prevent breaking or cracking thereof.

**FEED-BAG.**—J. A. SKINNER, Denver, Col. One purpose of the invention is to provide a bag for animals, particularly horses, which will be simple, durable, and economic and so constructed as to effectually prevent waste of feed and so that free and perfect ventilation is obtained. The bag is self-accommodating to different sizes of heads and permits an animal to have perfect freedom in raising and lowering the head.

**WATERPROOF EYEGLASS-CASE.**—MIRIAM DAVIDSON, New York, N. Y. The article is intended to be used especially by bathers, and while intended especially for carrying eyeglasses it is intended also as a receptacle for articles such as smelling-salts or a vial of brandy, which may be used in an emergency. The case is water-tight and attractive in appearance.

**CARRIER FOR PHOTOGRAPHIC PLATES.**—E. L. HALL, New York, N. Y. One purpose of the invention is the provision of a receptacle in which the plates may be placed and supported on end, it being adapted to contain liquid, so that the plates may be transported in a wet condition, enabling them to be subsequently thoroughly washed and preventing the possibility of the hypo drying on the plates and staining them during transportation.

**SHINGLE-PRESS.**—J. W. THURSTON, Maple Falls, Wash. Mr. Thurston's invention is an improvement in shingle-presses, and his object is to provide a novel construction by which to re-press or tighten-up bundles of shingles for shipping after they have come from the dry-kiln. The bundles may be pressed tightly together without injury to the shingles, and means are provided by which the short lap of the shingles at the middle of the bundles enables them to dry out much more rapidly than when a greater lap is made at the middle of the bundles.

**PIN-RETAINER.**—W. C. MAYNARD, Miami, Fla. This device is adapted for application to a scarf or hat pin for preventing its accidental or surreptitious detachment. To apply the retainer to a pin or remove it therefrom, the notched end is held disengaged from the pin and the end provided with an opening at one end of a curved spring is slid upon the pin, and when the retainer has been adjusted to desired position the notched end is placed in engagement with the pin, whereby the retainer as a whole is put under tension.

**OUTSIDE DRY-EARTH CLOSET.**—J. R. KOONS, Huntington Mills, Pa. The said invention has for its object to provide for supplying coal-ashes, earth, or suitable material to the excrement contained in the box or chamber of the closet or privy as an absorbent for such excrement, rendering the latter odorless and otherwise desirable from a sanitary point of view.

**LIQUID FORCING OR PUMPING DEVICE.**—L. J. C. LARSEN, New York, N. Y. More especially this invention has reference to devices for forcing or pumping temperature-reducing liquids—as alcohol, for instance—into and through the gas-service pipes for houses leading underground from the usual street-

**EBONITE PAINT-VARNISH**  
The only perfect composition for protecting metal and wood work from the ravages of rust, corrosion, and severe climatic changes. It is neither a paint nor a varnish, but a combination of the best qualities in both, developed, after extended tests and experiments, to meet the severest demands for a  
**Real Protective Coating**  
For structural iron work, stand pipes, exposed wood work, fences, in fact everything that needs protection or damp-proofing, Ebonite is superior to anything else for the purpose—and owing to our special process of manufacture is lower in price. It comes only in black.  
Interesting booklet, prices, etc., will be furnished by applying to  
**BUCHANAN-FOSTER COMPANY**  
452 Chestnut Street, Philadelphia, Pa.

**Send for this Book**  
This 128 page, beautifully illustrated volume tells the story of small craft from their earliest forms to the present efficient launches and pleasure boats. The development of each type described in breezy style by an enthusiast. Bound in cloth, pocket size. The book was originally intended to sell at \$1.00. Recognizing its interest and value, we purchased the entire edition and author's rights. To get in touch with lovers of boats, we will send "The Book of Boats," postpaid, together with our interesting quarterly, "The Launch," for one year for 50c. When you write for book enclose extra stamps for our attractive 80-p. catalog of Truscott Boats, the perfected product of 3 generations of boat-building experience.  
**Truscott Boat Mfg. Company**  
Dept. 183  
St. Joseph, Mich.

**NEW YORK SCHOOL OF AUTOMOBILE ENGINEERS**  
Incorporated  
147 West 56th Street, New York City  
Under the personal direction of  
PROF. CHAS. E. LUCKE, M. E., Ph. D.  
School of Engineers, Columbia University  
Departments include machine tool and forge shops, assembling and test shops, and every type of motor; also laboratories completely and specially equipped to teach all component parts of automobiles.  
**Day and Evening Classes.**  
**SPECIAL COURSES FOR OWNERS.**

**MARVELOUS**  
Wonderful, isn't it?  
how this rabbit is produced from the hat. You can do the same if I teach you how. Send for my new book, "An Evening of Sorcery and Magic Yielding Dollars."  
Explains how you can make quick easy money as an entertainer. I have made as high as \$600 a week. My course will make you a sleight of hand entertainer in five weeks. No toy tricks.  
Write before the second edition of this book is exhausted.  
Ansbach Correspondence School of Magic  
Dept. 19, Hillsdale, N. J.

**Medicated and Iron Clad Gloves**  
THE GREATEST GLOVES ON EARTH  
No more Sore Hands. No more Cracked Hands. No More Chapped Hands, but hands that are beautifully white, soft and smooth—such are the effects produced by wearing Medicated Gloves. Retail price 30 cents per pair.  
The Iron Clad Glove, the glove of the Working Man. It is not only Medicated and Water Proof, but also protected by a metallic surface which gives it great durability. Retail price 40 cents per pair.  
The best sellers on the market. Agents make from \$20 to \$30 per day. Write for particulars, if you want to make money. We want a good agent in every mill and factory. You can make more money at noon-time selling our gloves than you can during the day at your usual work.  
**THE COMMON SENSE MFG. CO.**  
Dept. 153, St. Louis, Mo.

**PORTABLE CONCRETE Block Machine**  
Ambitious young men can start fine business, immediately profitable, easily expanded.  
Blocks cost 6 cents to make, sell for 18 cents. One man can make 200 blocks per day. Whole outfit costs \$125.00.  
Sand, water and Portland cement only materials required.  
Sent on trial.  
**THE PETTYJOHN CO.**  
615 N. 6th St., Terre Haute, Ind.

main of the gas-distributing system for the purpose of relieving the passage through the service-pipe when the same has become choked or stopped up by the freezing or congelation of moisture therein.

**SAFETY-RAZOR.**—P. A. BENET, Boston, Mass. The object of the inventor is to provide a razor which can be conveniently carried in one's pocket and readily adapted for immediate use. A special object is to provide a device of such construction that it will have little tendency to wear the lining of a pocket and which will also occupy a small space.

#### Machines and Mechanical Devices.

**SIDE BRACE OR ANCHOR FOR DREDGERS.**—J. P. KARR, Monticello, Ind. By means of this attachment for dredging-machines, particularly such as are adapted for excavating canals, Mr. Karr provides a side anchor which not only prevents lateral movement of the screw, but also movement either forward or back, and also the anchoring attachment proper may be quickly and conveniently raised and locked whenever required, and also it may be instantly unlocked and turned again into working position.

**ROTARY FOR OIL-WELLS.**—H. D. BERNARD, Beaumont, Texas. The invention relates to pipe-rotaries such as used in sinking oil-wells. The object is to produce a rotary of this class which will enable the application of power in the screwing together or unscrewing of the pipe-sections which constitute the casing of the well.

**CUTTING AND MEASURING MACHINE.**—A. P. SWEENEY, Helena, Mont. The invention relates to apparatus for cutting and measuring fabrics and like sheet material, it being particularly adapted for trimming window-shade cloth and dividing it into definite lengths to furnish the shades. It will successively cut and measure lengths automatically and perform either of these operations separately.

**OIL-CLOTH-PRINTING MACHINE.**—W. H. WALDRON, New Brunswick, N. J. The improvement refers to machines for imprinting a design in various colors upon oil-cloth and other fabrics by the use of intermittently-reciprocating printing-blocks. The object is to provide a machine arranged to insure solid impressions with a comparatively small amount of color.

**BEAMING-MACHINE.**—F. A. BAER, Paterson, N. J. It is the essential object of the inventor to provide means for automatically cutting out the picks as the warp is beamed, leaving only short lengths in the warp, which may be readily removed by the weaver. In attaining this end Mr. Baer prefers to provide the machine with a number of automatically-operating knives, which run between the warp-threads and as the picks approach the knives serve to sever the same.

**MOLDING-MACHINE.**—H. C. STEELE, W. STENSON, and F. J. TROUT, Jacksonville, Fla. The principal objects of the invention are to provide means for smoothing the sides of the molded articles as they are removed from the mold, to provide for quickly and efficiently removing them from the molds, to provide for attaching two articles together by means of an insert placed in them in the act of molding, to provide for a convenient and efficient introduction of the molding material into the molds, and to provide for adjustments to accommodate one set of molds to articles of different lengths. It relates to improvements in machines and molds for molding plastic materials.

#### Railways and Their Accessories.

**AUTOMATIC AIR-COUPLING.**—E. V. SEXSMITH, Fond du Lac, Wis., and D. E. MOULTON, Belle Plaine, Iowa. The improvement pertains to a coupler for use upon either passenger or freight trains; and the principal objects thereof are to add to the efficiency without increasing the cost of these devices and to provide a construction which will operate effectively to conduct air from one car to another, as well as to provide for the automatic coupling of the parts and to secure means for allowing adjustment to suit various kinds of cars.

**SIGNAL.**—C. R. DOWLER, Lamar, Col. More definitely stated the invention refers to means indicating dangerous high-water level at a railroad or other bridge. The object had in view is to provide a signal involving new, improved, and simplified means for effecting the display of a visual or audible signal indicating dangerous high level of the water in a river at a bridge or other place.

#### Pertaining to Recreation.

**AMUSEMENT DEVICE.**—E. S. BENEDICT, New York, N. Y. The principal object in this case is to provide an artificial flow of water directly in line and falling over the track upon which the vehicle moves and for shutting off the flow as the vehicle enters it and then starting flow again when vehicle has passed. This is accomplished, first, by having the flow represent a waterfall, second, by having it represent a fountain. Either can be electrically lighted in any of the ordinary ways or can be provided with any features employed for beautifying artificial falls and fountains.

**FISHING-REEL.**—F. L. DICKSON, El Paso, Texas. This invention relates to fishing-reels such as are used by anglers for "playing" a fish after it has been struck. The object of the inventor is to produce a reel of simple con-



## SMALLEY

### MARINE GAS ENGINES



### "It Is Self Starting"

INDIAN RIVER, MICH., October 14, 1905.  
SMALLEY MOTOR CO., Bay City, Mich.

Gentlemen—You can refer anyone to me in regard to the Smalley motor; my motor runs perfectly. There is one thing about your motor that you do not mention—IT IS SELF STARTING. My motor starts just as sure as steam if it has not stood over ten hours; if it has I only have to turn the flywheel back one-quarter turn in the morning, but that is all for the day. Your rotary timer starts the engine every time. I don't think you mention this in your catalogue, but for a perfect motor it can't be beat. Yours truly, CAPT. WM. F. DAGWELL.

BAY CITY, MICH., June 10, 1905.  
SMALLEY MOTOR CO., Bay City, Mich.


Gentlemen—After using the 12 H. P. engine I am pleased to report to you that the engine has proved far beyond my expectations. In all my use of the engine I have never known it to miss an explosion. I have kept actual count of twenty-seven times I have started engine after having made stops at various points along the river and in twenty-six of these twenty-seven times I have never used either starting lever or turned a wheel simply starting engine by means of the commutator. IT IS SELF-STARTING. Yours very truly, CHAS. CORYELL.

Send 10 cents in stamps for complete illustrated catalogue. Address Dept. W.

SMALLEY MOTOR CO., LTD., Bay City, Mich., U. S. A.  
Member of the National Ass'n of Engine and Boat Mfrs.

## Regal

### Marine Engines



Four cycle—jump spark ignition—Automobile type. Have the **smallest number of working parts** consistent with a perfect operating motor. Our valves insure perfect mixture. Ignition system is like an automobile, and motor starts with one turn.

Regal Engines are fully guaranteed.

"They are Built to Run and Do It."

Our customers say we are the only manufacturers who put Good Work into a Small Engine. Made in 3 types, 1 1/2, 3 and 5 H. P.—single cylinder; 8 to 15 H. P. double cylinder; 30 H. P. 4-cylinder marine. Send for OUR NEW CATALOGUE No. 16—it shows all the latest designs—tells interesting things about gas engines. Mailed free.

Regal Gasoline Engine Co., Coldwater, Mich.

## THE MIETZ & WEISS

### OIL ENGINES



Sizes from 1 to 60 H. P.

Stationary 1 1/2 to 80 H. P.  
Marine 3 1/2 to 100 H. P.

Use KEROSENE and FUEL OILS. Direct connected Generators, Pumps, Air Compressors, Hoists, etc. Thousands in use in all parts of the world.

AUGUST MIETZ  
128-138 Mott St., New York, U.S.A.

**GAS ENGINE DETAILS.—A VALUABLE** and fully illustrated article on this subject is contained in Scientific American No. 1292. Price 10 cents. For sale by Munn & Co. and all newsdealers.

## KEROSENE

### OIL ENGINES



Marine Stationary Portable  
NO DANGER. Maximum Powers. Lightest Weight. Simple, Reliable, Economical. No Batteries. Self Ignition by Compression. Fully Guaranteed. Write for Catalogue P. M. No charge for packing.

International Oil Engine Co.  
253 Broadway, N. Y., U. S. A.

## The Fireless Cookstove

### AND POINTS ON PURCHASING

A most valuable and interesting book on Domestic Economy by Capt. HARRY H. SKINNER, showing how to make and use a Fireless Cookstove and save seven-eighths of the fuel ordinarily used in cooking and how to purchase and properly prepare food. Bound in cloth, illustrated.

This method has been adopted by the U. S. Government for use in army camps, and the book contains many recipes and valuable instruction from the most scientific and practical cook in this country, now in the employ of the Government. Sent prepaid to any address on receipt of 25 cents.

JAPAN PUBLISHING CO., Dept. B  
American Tract Society Building, New York, N. Y.

## SPARK COILS

### Their Construction Simply Explained

Scientific American Supplement 160 describes the making of a 1 1/2-inch spark coil and condenser.

Scientific American Supplement 1514 tells you how to make a coil for gas-engine ignition.

Scientific American Supplement 1522 explains fully the construction of a jump-spark coil and condenser for gas-engine ignition.

Scientific American Supplement 1124 describes the construction of a 6-inch spark coil.

Scientific American Supplement 1087 gives a full account of the making of an alternating current coil giving a 5-inch spark.

Scientific American Supplement 1527 describes a 4-inch spark coil and condenser.

Scientific American Supplement 1402 gives data for the construction of coils of a definite length of spark.

The above-mentioned set of seven papers will be supplied for 70 cents.

Any single copy will be mailed for 10 cts.  
MUNN & COMPANY, Publishers  
361 Broadway New York

struction which is provided with means for controlling at any instant the tension of the line in unwinding.

#### Pertaining to Vehicles.

**AUTOMOBILE.**—B. E. HERVEY, Spokane, Wash. The invention is an improvement in automobiles. By supporting the wheel-shaft upon either side of the wheel and by providing the oppositely-disposed crank-arms arranged upon either side of the longitudinal bar all cross strain is obviated, and as a consequence friction is reduced to a minimum. A better and more equal transmission of power is also effected by this arrangement, and a more stable support is provided for the wheels.

**TRUCK.**—J. D. SMITH, Cheraw, S. C. Mr. Smith's invention relates to trucks especially adapted for handling lumber in mills and elsewhere; and the purpose of the improvement is to provide a truck in which the frame is in one piece, and, further, in which the axles are of such construction as to act as braces and spreaders for the frame as well as axles.

**VEHICLE.**—J. H. HANSON and J. J. PETRABORG, Aitkin, Minn. The improvement has reference to vehicles, and more particularly to the running-gear thereof. Its principal object is to equalize the movement of said gear. Used in connection with automobiles it will relieve the engine and its associate parts to a great extent from ordinary wear and tear incurred. It will greatly reduce the liability of upsetting a vehicle or displacing its load.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

## Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. In every case it is necessary to give the number of the inquiry.

MUNN & CO.

Marine Iron Works. Chicago. Catalogue free.

**Inquiry No. 7913.**—Wanted, name and address of makers of a waterproof glue.

For mining engines. J. S. Mundy, Newark, N. J.

**Inquiry No. 7914.**—Wanted, makers of gear wheels or cog wheels, or sprocket wheels.

"U. S." Metal Polish. Indianapolis. Samples free.

**Inquiry No. 7915.**—Wanted, a manufacturer of a door check which is placed on the outer corner of the door, as an additional check besides the spring.

Handle & Spoke Mch. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

**Inquiry No. 7916.**—Wanted, wrought iron filings or borings; as fine as granulated sugar.

WANTED.—To secure a party to manufacture a patent Ratchet Drill. Address Drill, Box 773, New York.

**Inquiry No. 7917.**—Wanted, information concerning the manufacture of collar buttons, such as material, cost, etc.

I sell patents. To buy, or having one to sell, write Chas. A. Scott, 719 Mutual Life Building, Buffalo, N. Y.

**Inquiry No. 7918.**—Wanted, makers of rotary or turbine steam engines.

Well gotten up typewritten letters will increase your business. \$2 per 1,000.

Typewritten Letter Co., St. Louis.

**Inquiry No. 7919.**—Wanted, makers of drop forging machines, also small machines for crushing cottonseed.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Machine Company, Foot of East 138th Street, New York.

**Inquiry No. 7920.**—Wanted, name and address of parties who make a specialty of manufacturing cabinets on contract.

FOR SALE.—Self-swinging gate, great improvement. Sell or lease on royalty. Patented November 21, 1905. Claude Siebring, George, Iowa.

**Inquiry No. 7921.**—Wanted, the manufacturers of the railroad track-laying machine.

I have for sale the U. S. and all foreign rights of new patent improvements in Water Tube Types of Boilers. Great economizer. J. M. Colman, Everett, Wash.

**Inquiry No. 7922.**—For manufacturers of bicycle fittings or bicycles.

WANTED.—Practical storage battery man to join me in making small storage batteries. Must have some capital. I have building and power. Capital, Box 773, New York.

**Inquiry No. 7923.**—Wanted, address of makers of rotary pumps to lift water 15 to 20 feet, and put 75 to 80 pressure on pressure tank and maintain that pressure while 2-inch hose lines work from the pressure tank continuously.

Manufacturers of patent articles, dies, metal stamping, screw machine work, hardware specialties, machinery tools, and wood fiber products. Quadriga Manufacturing Company, 18 South Canal St., Chicago.

**Inquiry No. 7924.**—Wanted, makers of friction clutch pulleys.

WANTED.—Experienced foreman for erecting department "Four Cylinder Motors" with well-established automobile company. Must have had similar experience with good company. Address Foreman, Box 773, New York.

**Inquiry No. 7925.**—For manufacturers of tin boxes made to represent books.

PATENT FOR SALE.—Traction wheel or runner. A newly invented vehicle wheel or runner; a sled that will run freely and smoothly on snow or ground, and gives good satisfaction. Can be used anywhere in the north or south. Good bargain.

Andrew Sell, Bridge, Itasca County, Minn.

**Inquiry No. 7926.**—For manufacturers of dust protectors.

**Inquiry No. 7927.**—Wanted, manufacturers of adjustable scaffolds for use of bricklayers.

**Inquiry No. 7928.**—Wanted, a small milling machine.

**Inquiry No. 7929.**—Wanted, the name and address of the makers of the Norton Door Spring.

## JUST PUBLISHED

# Electrician's Handy Book

BY  
Prof. T. O'Connor Sloane, A. M., E. M., Ph. D.

Handsomely Bound in Red Leather,  
with Titles and Edges in Gold

Pocketbook Style Price \$3.50

A thoroughly practical up-to-date book of 768 pages, covering the entire field of electricity. Contains no useless theory. Everything in it is to the point and can be easily understood by the student, the practical worker, and the every-day working electrician. The advanced electrical engineer will also receive great benefit from its perusal and study.

Fifteenth Edition Revised, Enlarged and Reset

## Gas, Gasoline and Oil Engines

Including Gas Producer Plants

By GARDNER D. HISCOX, M. E.

Price \$2 50

The only complete American book on the subject for Gas Engine Owners, Gas Engineers, and intending purchasers of gas engines, treating fully on the construction, installation, operation and maintenance of gas, gasoline, kerosene, and crude petroleum engines.

The new rewritten, enlarged and revised 15th edition of this work has been prepared to meet the increasing demand for a thorough treatise on the subject. Its 450 pages give general information for everyone interested in this popular motive power, and its adaptation to the increasing demand for a cheap and easily managed motor requiring no licensed engineer. It is fully illustrated by 351 Engravings and Diagrams.

## MODERN MACHINE SHOP CONSTRUCTION

Equipment and Management

By OSCAR E. PERRIGO, M. E.

Nearly 400 Large Quarto Pages, Illustrated by over 200 Engravings Specially

Made by the Author

Price \$5.00

A work designed for the practical and every-day use of the Architect who designs, the Manufacturers who build, the Engineers who plan and equip, the Superintendents who organize and direct, and for the information of every Stockholder, Director, Officer, Accountant, Clerk, Superintendent, Foreman, and Workman of the Modern Machine Shop and Manufacturing Plant of Industrial America.

SEND FOR DESCRIPTIVE CIRCULAR

## Electric Wiring, Diagrams and Switchboards

By NEWTON HARRISON, E. E.

Instructor of Electrical Engineering in the Newark Technical School

PRICE \$1.50

A thoroughly practical treatise covering the subject of Electric Wiring in all its branches, including explanations and diagrams which are thoroughly explicit and greatly simplify the subject. Practical every-day problems in wiring are presented and the method of obtaining intelligent results clearly shown. Only arithmetic is used.

MUNN & CO., Publishers,  
361 BROADWAY NEW YORK.

## Notes and Queries.

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(9894) F. G. H. asks: Will the range (actual and theoretical) of a 30-caliber bullet (any other caliber probably would not matter) fired from a gun weighing ten pounds suspended by a wire, i. e.—free to recoil without friction—be the same as a bullet of the same caliber fired from a gun having an equal bore and similarly suspended, but having a weight or mass of 10,000 pounds? This has puzzled the writer and a number of his friends who are readers of your valuable paper. Any light you can throw on the subject, together with explanation of how you arrive at the correct solution will be greatly appreciated. A. Newton's Third Law of Motion is, "The mutual action of two bodies is equal and opposite in direction;" or, as it is usually expressed, "action and reaction are equal and opposite in direction." The action of the gases upon the gun and the ball are equal in quantity, and each has the same momentum, the ball forward, the gun in the opposite direction. No account need be taken of the weight of either unless the velocity of the two need be determined. The velocity of recoil of the guns will be in proportion to their weight.

(9895) J. K. asks: How cold is it when it is twice as cold as two degrees above zero? The above problem appeared in a publication recently, which caused considerable discussion. Some considered it as a joke, and others more serious. Following issues published different solutions. If I may be permitted to trespass upon your time, please favor by answering the above problem if possible. A. It is not twice as cold when it is one degree above zero, F. as it is at two deg. above zero. To get an absolute comparison of temperature we must measure from absolute zero. Temperatures above absolute zero correspond to the heat required to produce them. Two above absolute zero is twice as hot as one above. Absolute zero is 459 deg. Fahr. below its zero. The real temperature when the Fahr. thermometer shows 2 deg. above is 461 deg. absolute Fahr. Twice as cold, or as it should be expressed, half as hot as this, is 230.5 deg. absolute Fahr.

(9896) S. R. says: I have a maximum and minimum thermometer, the principle of which I find it difficult to understand, and so far have not been able to find any description in any books that I have. It is the bent tube thermometer, containing quicksilver, but with no bulb as a reservoir of the metal. It carries two glass rods with iron pins in them, which mark the maxima and minima, and which are drawn back to place by means of a small horseshoe magnet. A. The thermometer which you describe is a Six's thermometer. The liquid is usually the same on both sides of the mercury, and is usually alcohol. A space above the alcohol in the bulb has in it only vapor of alcohol. When the temperature rises, the expansion of the alcohol in A pushes the mercury and the iron wire above the mercury in B along to the highest point reached by the mercury. When the temperature falls, this wire is left at the highest point it has reached, the alcohol contracts in A and draws the mercury over to the side A. The iron wire is not pushed in front of the mercury in A to the lowest temperature reached by the contraction of the alcohol in A. The thread of mercury is the indicator; the change of volume of the alcohol measures the change of temperature.

(9897) W. A. W. asks: Can it be proved that light is not electrical energy generated by the sun, which energy in coming in contact with the resistance of the earth's atmosphere produces light by friction? Does the wireless telegraph operate through waves of ether or waves of air? A. Scientists believe that light is due to the same waves as electricity, and that these come through space, from any body which can produce them, to the earth. When these waves strike the earth, they are ultimately absorbed as heat waves. If they strike an eye, they are converted into light waves. Any object which is hot enough can emit such waves. Objects which can reflect these waves may send them to the eye, as flowers and other visible objects on the earth do send them. Friction is not involved in the action. Wireless telegraphy is performed by waves which are electro-magnetic in character, and which pass through air or ether on their way, supposedly with the speed of light.

(9898) W. O. D. asks: Should it be practicable to convert the alternating machine, described by N. Monroe Hopkins in SUPPLEMENT No. 1558, by making proper connections with regard to the field and using a separate commutator with the necessary connections in armature. Please advise me as to size of wire to use in both field and armature, together with any other information you have time to give me. A. No change in field or armature winding is necessary to convert the alternating-current dynamo of SUPPLEMENT No. 1558 into a direct-current machine. It is only necessary to replace the collecting rings by a commutator with as many segments as there are coils on the armature, and connect the end of one coil and the beginning of the next coil of the field to the bars of the commutator in regular order around the commutator. The machine will then give a direct current.

## INDEX OF INVENTIONS

For which Letters Patent of the  
United States were Issued

for the Week Ending

February 20, 1906.

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

Adding and recording machine, A. S. Dennis	813,361
Advertising device, P. Couette	813,200
Advertising device, E. C. Crow	813,354
Air and liquid cooling apparatus, G. T. Voorhees	813,066
Air brake coupling, H. H. Sartain	813,390
Air brake mechanism, A. L. Goodknight	813,090
Air purifying apparatus, J. H. Kinealy	813,217
Alarm, W. L. Monroe	813,164
Albumin from vegetable substances, extracting, F. W. Gaertner	813,373
Amusement device, T. C. Hurst	812,848
Anchor hook, guy clamp, and guy stretcher, combined, G. F. Swartfeger	813,182
Animal shears, S. Robinson	812,882
Animal trap, J. H. Tharp	813,333
Annealing box, J. J. Markey	812,943
Annunciator drop, C. E. Scribner	812,954
Anode, L. Levett	813,048
Automatic sprinkler, E. V. Smith	813,061
Automobile, W. T. Penrose	813,058
Automobile frame, Schaaf & Davis	813,175
Automobile steering gear, J. Warrington	813,186
Awning, J. Malinofsky	813,103
Bag fastener, J. S. Williamson	813,266
Baling press, T. & H. B. Abbot	813,270
Band cutter and feeder, L. N. Holm	813,000
Band cutter and feeder, R. E. Van Court	813,250
Barrel heading press, O. J. Wyman, et al.	812,911
Bed, folding, F. J. Hubbard	813,004
Bed spring, E. F. Linsley	812,939
Beers or malt liquors, manufacture of English, N. H. Claussen	813,199
Belt for supporting catamenial bandages, self-adjusting, B. Schick	813,176
Belt tightener, J. J. Thacher	812,899
Bin, H. M. Praed	813,059
Binding post, E. C. Henn	813,093
Bit. See Bridle bit.	
Block lifter, hollow, G. D. Rowell	813,060
Blower for explosion engines, engine driven, Frayer & Miller	813,204
Boat, life, R. A. Brown	812,815
Boiler, S. Hallander	812,844
Boiler, W. J. Sheetz	812,890
Boiler furnace, steam, W. H. Hampden	813,380
Book holder, J. N. Miller	813,227
Book strap, M. H. Karbo	813,216
Bookbinder's plow, J. Hinkley	812,998
Bottle cleaning machine, C. H. Loew	813,012
Bottle closure, A. & D. Celenza	813,198
Bottle, non-refillable, A. Bennett	812,804
Bottle, non-refillable, M. Conner	813,038
Bottle rinser, C. H. Loew	812,940
Bottle sterilizing and cleansing apparatus, T. C. Bates	812,974
Bottles, frangible cap for the closure of, S. M. Stevens	813,181
Brake. See Vehicle brake.	
Brake band, H. N. Covell	812,827
Brake hanger, adjustable, G. M. Brill	813,346
Brake mechanism, power, C. B. Goode	812,989
Brick clay crusher rolls, J. H. Bach	813,273
Brick cutting machine, Barr & Gandert	812,973
Bridging horizontal and vertical spaces, R. C. Sayer	812,952
Bridle bit and attaching means therefor, F. Weathers	813,337
Brooder, H. F. Rau	813,115
Buckle, Merrill & Howard	812,862
Building structures, stairs, corners, and the like, protecting rail for, M. Rupke	813,326
Burglar alarm, J. H. Snow	812,892
Burial casket, J. H. Mills	812,945
Calculator and recorder, mechanical, L. S. Crandall	813,281
Camera, cinematographic, M. Hansen	812,845
Can body forming and soldering apparatus, L. C. Sharp	812,955
Can heading and crimping machine, automatic round, A. Lotz	812,858
Can heading and crimping machine, automatic square, A. Lotz	812,857
Candy machine, A. Mosebach	813,315
Car, convertible, Stanley & Gilmore	813,249
Car coupling, G. A. Hermanson	812,927
Car coupling, W. McConway, Jr.	813,107
Car draft appliance, railway, J. F. O'Connor	812,868
Car friction draft rigging, railway, F. B. Townsend	812,902
Car grain door, J. Feucht	812,838
Car indicator, street, Evans & Patterson	813,144
Car lubricator, J. F. Joy	813,214
Car seat, reversible, H. Witte	813,267
Car wheels, producing self-lubricating, J. W. Fuller, Jr.	813,146
Cars, cable grip for, J. L. Davis	813,040
Cars, tandem spring draft rigging for railway, J. F. O'Connor	812,867
Card mounting, C. C. Harper	812,993
Carding machine feeding mechanism, P. L. McBride	812,863
Carrier. See Trace carrier.	
Carrier, D. G. Lyman	813,160
Cashiers, registers, and recorders, keyboard locking mechanism for mechanical, Dement & Hull	813,360
Cask or vessel for ignitable or explosive liquids or gases, W. Dreyer	813,365
Catamenial sack, W. M. Longstreth	813,221
Cattle guard, W. E. Dement	812,984
Cement block making machine, B. Poulson	813,112
Cement kiln, oscillating, B. E. Eldred	812,834
Centrifugal machine, E. H. Dutcher	813,282
Centrifugal machines, speed controlling mechanism for, E. H. Dutcher	813,283
Chain, detachable link, A. D. Morris	813,229
Chain hook, F. Kramer	813,386
Chain sling and trip, W. E. Cage	813,277
Charging machine, A. L. J. Queneau	813,022
Chuck, drill, T. James	813,151
Churn, butter, C. M. Runyan	813,325
Churn operating mechanism, H. L. Busch	812,819
Cigarette holder, W. Durand	813,366
Circuits, switch or circuit breaker for high potential, E. W. Rice, Jr.	812,880

## SPECIAL 60-DAY OFFER TO INTRODUCE OUR LATEST LARGE, POWERFUL ACHROMATIC TELESCOPE, WITH SOLAR EYE-PIECE

FACE TO FACE WITH THE SUN!



**NEEDED ON FARM, SEA OR RANCH.**  
POSITIVELY such a good telescope was never sold for this price before. These Telescopes are made by one of the largest manufacturers of Europe, measure closed 12 inches and open over 3 1/2 feet in 5 sections. They are BRASS BOUND, BRASS SAFETY CAP on each end to exclude dust, etc. with **POWERFUL LENSES**, scientifically ground and adjusted. **GUARANTEED BY THE MAKER.** Heretofore Telescopes of this size have been sold from \$5.00 to \$8.00. Every sojourner in the country or at seaside resorts should certainly secure one of these instruments; and no farmer should be without one. Objects miles away are brought to view with astonishing clearness. Sent by express for \$1 safely packed; if by mail, \$1.10. Our new catalogue of Watches, etc., sent with each order. This is a grand offer and you should not miss it. **WE WARRANT** each Telescope **JUST AS REPRESENTED** or money refunded. **WHAT A TOURIST SAYS:** New York, Nov. 4, 1905. Messrs. Kirtland Bros. & Co. Gentlemen: I had with me on my recent European trip, one of your Excelsior Solar Telescopes, with which I had the pleasure of observing an Eclipse of the Sun. At the Austrian Tyrol it was almost 80 per cent concealed. Your Solar eye-piece is a great thing. Its value to me on this occasion was many times greater than the entire outlay for the Telescope. Yours truly, L. S. HENRY.  
Send \$1.10 by Registered Letter, Post Office Money Order, Express Money Order, or Bank Draft payable to our order

KIRTLAND BROS. & CO., Dept. S. A., 90 Chambers Street, New York

### Valuable Patent For Sale

**Revolving Ball Bearing Flag Device**

Every public building in every hamlet, town and city in the world, a possible purchaser for this device. It is an absolute necessity to military and naval stations and public buildings. Where expensive flags are used, it saves initial cost first year from wear alone, besides allowing flag to fly free and with the wind. No entangling of flag, halyards and pole, but always as shown in cut. The U. S. Government will use thousands of them when brought to its notice. Easy to manufacture, and to a concern with facilities for turning out this device, a fortune can be made. Lack of capital, reason for selling. Will be glad to go into details with interested parties. Will offer for sale outright or on a royalty basis.

**J. EVELETH GRIFFITH, 368 Congress St., BOSTON, MASS.**


## I KNOW

Where to locate you on the

### LEHIGH VALLEY RAILROAD

if you want to establish a new industry  
or re-locate one already established.

**P. H. BURNETT, Industrial Agent**  
143 Liberty St., N. Y.



OUR factory buildings and equipment, materials and processes, are unapproached in the entire American automobile industry and in many essentials Columbia Gasolene Cars for 1906 are a full year in advance of all others. This is not mere assertion. Make the comparison yourself. In no other cars will you find crankshafts machined cold from a solid block of metal and chrome-nickel steel transmission shafts, jack-shafts, gears, etc., nor the I-beam front axle forged in one continuous piece. In no others will you find the same perfection of body designs, beauty of color schemes and painstaking details of finish. Mark XLVII, four cylinders, 40-45 h. p., double chain drive, price, \$4500 to \$5500, according to body, is the accepted ideal of the American high-powered car. Mark XLVI, four cylinders, 28 h. p., shaft drive, price \$3000, is unequalled among medium-powered four-cylinder cars. Mark XLIV-2, two opposed cylinders, 18 h. p., shaft drive, price \$1750, we offer as the highest grade two-cylinder car in the market.

Separate Catalogues of Columbia Gasolene Cars, Columbia Electric Carriages and Columbia Electric Commercial Vehicles will be mailed on request; also, special illustrated booklets; "Columbia Chrome-nickel Steel," "Fashioning a Crankshaft," "Consistent Differences in Columbia Cars," "Transmission," etc.

## ELECTRIC VEHICLE COMPANY

HARTFORD, CONN.

New York Branch: 134-136-138 West 39th Street. Chicago Branch: 1332-1334 Michigan Ave.  
Boston: Columbia Motor Vehicle Co., 74-76-78 Stanhope Street. Philadelphia: Pennsylvania Electric Vehicle Co., 250 North Broad St. Washington: E. V. Transportation Co., 15th St. and Ohio Ave.

Member Association Licensed Automobile Manufacturers

Clock, self-winding electric, M. Menkin	813,161
Cloth cutting machines, circular knife and retaining gear for, H. A. Meyer	813,313
Clothes drainer, F. P. Sager	812,884
Clutch, Ehle & Nice	813,369
Clutch mechanism, J. H. B. Bryan	812,817
Coffee, malt, etc., roasting apparatus for, M. Boof	813,274
Coffee pot attachment, Randall & Peirson	813,297
Collar foundation, D. Potts	812,876
Column, T. F. McCarthy	813,318
Concrete curbing, reinforced, A. Thomas	813,334
Concrete, reinforcing truss for, E. B. Jarvis	813,303
Conveyer, C. H. Anderson	813,134
Conveyer for coke retorts, H. A. Carpenter	812,977
Core forming machine, sand, C. C. Korns	812,852
Corn shocker, O. Boyer	812,809
Cotton picker, J. K. Piper	813,170
Cotton picking machine, J. Nisbet	812,865
Cotton scraper, J. D. Fairless	813,085
Cross tie and means for holding track rails thereon, E. A. Gillchrist	813,205
Cultivator attachment, W. H. Mitchell	812,946
Cushion spring, W. R. Smith	813,244
Damper, automatic, W. H. H. Morelock	813,228
Damper, pipe, H. Whitham	813,188
Davenport and bed, combined, A. M. Padmore	813,233
Dental handpieces, slip joint connection for, Smith & Jones	813,178
Dental tool for removing crown pins, G. T. Carpenter	812,976
Dentistry, grinding stone and disk employed in mechanical and operative, H. Sanford-Burton	813,348
Derrick, log, H. Combs	813,352
Die stock, H. W. Oster	812,870
Disintegrating machine, M. F. Williams	813,190
Disintegrating machine, J. W. Hyatt	813,300
Dispensing apparatus, E. Talbert	813,027
Display form, G. Gallau	812,986
Display tray, J. J. Hoffmann	812,999
Distilling wood and obtaining therefrom the different by-products, apparatus for, W. & T. L. James	813,302
Door check, Parker & Papenfoth	813,111
Door check and closer, N. W. Crandall	812,829
Door, combined storm and screen, J. Abrim	813,271
Door lock, grain, J. Feucht	812,839
Door wings, device for hanging revolving, J. Wendler	812,907
Dop, P. H. Farrell	812,836
Doubletree hitch, J. H. Cook	813,039
Draw knife, A. B. Jennings	813,152
Dredge, J. F. Loreman	813,222
Dredge, V. A. Strom	813,252
Dry meter for gas, air, and like fluid, D. Macfie	813,312
Drying apparatus, C. M. Davison	813,358
Drilling machine, J. P. Jacobs	813,211
Drilling machine, A. Walker	813,335
Drilling machine, F. W. Clough	813,351
Drum mill, R. Beneke	813,476
Dumping mechanism, P. J. Sleezer	812,957
Dye and making same, red azo, G. Kalischer	813,155
Dynamometer, H. Ruddick	813,324
Electric heater, A. A. Pratt	813,113
Electric meter, T. Duncan, reissue	12,453
Electrical heater, E. L. Vaughn	812,965
Electrical safety apparatus, Hosmer & Dietrich	813,297
Elevator. See Grain elevator.	
Embroidering machine, J. P. Lowenhaupt	812,859
Embroidering machines, fabric moving mechanism for, M. Trautmann	813,122
Engine controlling mechanism, blowing, J. V. Symons	813,064
Engine sparking igniter, explosive, Cornack & Zumdahl	813,081
Engine starting mechanism, explosive, H. J. Wiegand	813,068
Engines, automatic cut-off for explosive, M. Munzel	813,316
Evaporating pan, J. P. Golden	813,089
Excavating machine, T. H. Walker	813,393
Exhibiting apparatus, lace curtain, J. F. Mumford	813,165
Explosive, F. Sparre	812,958
Eyeglasses, J. C. Wells	813,030
Face plate, adjustable, F. A. Borst	812,916
Fare recorder, J. F. Ohmer	813,017
Fastening hook, C. D. Rice	812,879
Feed attachment, J. A. & J. C. Doran	812,833
Feed mechanism, J. J. Thacher	812,898
Feed water heater, H. G. Miller	812,944
Fence, wire, Elwell & Grimm	813,370
File cabinet, F. L. G. Straubel	812,962
Filing case, C. O. Hisecock	813,150
Filter, K. Kiefer	812,933
Filter, B. F. Schirmer	813,327
Filter, centrifugal, E. H. Dutcher	813,368
Filter press, S. Thurstensen	813,121
Filter press container, C. W. Merrill	813,014
Filter pulp packing machine, K. Kiefer, reissue	12,455
Filtering apparatus, K. Kiefer	812,931
Filtering element, K. Kiefer	812,932
Fire escape, Brown & Francis	813,139
Fire escape apparatus, G. B. Price	812,950
Fireproof column and column cap, J. J. Tresidder	813,183
Fish, apparatus for dry curing, V. Whitman	813,264
Fish, dry curing, V. Whitman	813,265
Fishing float, L. M. Johnson	813,153
Flashlight apparatus, automatic, Berens & Gatzert	813,077
Fluid pressure generator, A. Baudin	813,075
Flypaper, J. H. Bien	813,196
Folding box, E. G. Brown	813,347
Folding machines, paper slitting device for, La Sor & Smith, reissue	12,456
Footwear, anatomical, H. P. Cole	812,920
Forging and welding machine, C. Reinhart	813,174
Formaldehyde generator, A. E. Dieterich	813,363
Fumigating material and making same, J. H. Rivers	813,323
Furnace, J. C. Miller	813,226
Furnaces, air feeding device for, M. A. Lutzner	813,102
Galvanometer, P. H. Wynne	813,269
Game recording device, A. S. Nichols	812,864
Garden rake and cultivator, B. J. H. Guice	813,377
Garment rack, individual safety, H. J. Bouhal	813,917
Gas burner, S. Bernheim	812,975
Gas burner, inverted incandescent, H. Farnoff	813,042
Gas light switch, T. A. Davis	813,357
Gas meter, K. R. Howard	813,097
Gate, G. W. Thompson	812,964
Gearing, B. Tropp	812,903
Gearing, E. Wighton	813,189
Gearing, variable speed, W. T. Sears	812,886
Glass blowing machine, N. W. Hartman	813,289
Glass drawing apparatus, Speer & Harvey	813,248
Glass drawing machine, G. H. Harvey	813,290
Glass making apparatus, wire, J. Heidenkamp	812,994
Glass, manufacture of, Speer & Harvey	812,894
Glass, manufacturing, J. R. Speer	813,247
Glass ornaments, making, J. True	813,123
Glove, baseball, E. H. Decker	812,912
Governor, throttling, H. C. Clay	813,037
Grader, road, J. W. Langitt	813,010
Grader, road, C. Morsing	813,055
Grain drills, adjustable feed for, A. F. Mills	813,054
Grain elevator, pneumatic, W. C. Allen	813,073
Grinding apparatus, L. H. Olmsted	813,167
Gun carriage, S. N. McClean	813,106
Halter, M. M. Stokes	813,062
Hame, W. H. Hill	813,294
Hammer and spike puller, claw, C. F. Fifer	812,985
Hammer, pneumatic, R. A. Norling	813,109
Hanger. See Brake hanger.	
Harness, G. E. Bennett	812,913
Harvester platform adjusting means, seed, T. J. Campbell	813,349
Hat crown protector, M. Oldford	813,019
Hay press, A. Lorenz	813,013
Hay rake attachment, J. H. Sutherland	812,897
Header connection, J. P. Sneddon	813,245
Headlight cover, H. M. Davenport	812,982
Heat cartridge and protective apparatus, self-soldering, F. B. Cook	812,980
Heater, O'Hare & Weston	812,869




### Toquet Marine Motor

**STANDS FOR RELIABILITY**

Ask any owner of a "Toquet" Motor. Get his opinion.

If you don't know a "Toquet" owner write us, we'll gladly send names and addresses of a few.

Catalogue sent on receipt of three 2 cent stamps.



**THE TOQUET MOTOR CO.**  
Metropolitan Building, 31 East 23d Street, New York  
G. EDWARD SHAW, General Manager

### Big Faucet Water Motor

Connects to any faucet. On 80 pounds pressure develops 1-8 horse power. The average pressure of your faucet is from 40 to 80 pounds. Used for polishing, grinding, buffing. Furnishes power for sewing machines, small lathes, scroll saws, dental lathes, washing machines, etc., etc. A thousand and one uses. The Divine Faucet Water Motor is nearly twice as large as any other advertised motor. We guarantee it to give satisfaction or we will refund the money paid for it. You can be the judge.

**Regular \$5 Outfit for \$3.50**

Price will soon advance, so take advantage of this opportunity at once. Price includes complete outfit—emery wheel, buffing and polishing wheels, pulley wheel, leather belt, oil can and polishing composition. Sent upon receipt of money order for \$3.50. Write to-day for copy of Morton's Water Motor Book.

**MORTON MANUFACTURING CO.**  
Dept. C, 130 Fulton St., New York

### Good Cooking Means Good Health

Steam cookery retains all the nutrition and health-giving properties of food. In the

**Arnold Steam Cooker** both meat and vegetables are thoroughly cooked in separate patented compartments, entirely independent of one another, so that flavors are uncontaminated. Saves half your time and one third of everything cooked by any other means. Ask your dealer and write for full particulars to

**WILMOT CASTLE CO.**  
17 A Elm Street, Rochester, N. Y.

### Wizard Repeating LIQUID PISTOL

Will stop the most vicious dog (or man) without permanent injury. Perfectly safe to carry without danger of leakage. Fires and recharges by pulling the trigger. Loads from any liquid. No cartridges required. Over 60 shots in one loading. All dealers, or by mail, 50c. Club over-cooler, 50c. extra.

**Parker, Stearns & Co., 226 South St., Dept. G, New York**

### Wonder Electric Lighting Outfit

For the farm, shop, cottage, or private residence.

So simple anyone can operate them. This is the first outfit ever offered for sale at such a price that you cannot afford to be without one. Think of it; only one-tenth of a cent per hour for each 16 C. P. lamp. You can also use engine during the day for other purposes. Lighting outfit from \$110 up. Send for complete catalogue

**THE R. M. CORNWELL CO.**  
406 South Salina Street, Syracuse, N. Y.  
1132 Park Row Building, New York.

### THE Nulite Vapor Lamps

For Home, Store and Street

We also manufacture Table Lamps, Wall Lamps, Chandeliers, Street Lamps, Etc. 100 Candle Power seven hours ONE CENT. No Wicks. No Smoke. No Odor. Absolutely safe. **THEY SELL** Exclusive territory to good agents. **AT SIGHT.** Write for catalogue and prices.

**Chicago Solar Light Co., Dept. G, Chicago**

### Spend March IN THE West Indies

Leaving NEW YORK on **MARCH 8, 1906**

by the Superb Cruising Steamship **Prinzessin Victoria Luise**

Visiting St. Thomas, Martinique (St. Pierre, Fort de France); Barbados, Trinidad (Pitch Lake); Porto Rico (San Juan); Jamaica (Kingston); Cuba (Santiago, Havana) and Nassau.

**Duration of Trip, 25 Days**  
**Cost \$150 Upward**

Including stateroom, accommodation and meals. For further particulars apply

**HAMBURG-AMERICAN LINE**

OFFICES:  
New York, 35-37 Broadway.  
Chicago, 159 Randolph St.  
San Francisco, 201 California St.  
Boston, 92 State St.  
Philadelphia, 1229 Walnut St.  
St. Louis, 901 Olive St.

Heater and folding furniture, combined, W. C. James	813,383
Heating system, hot water, W. J. Sheetz	812,889
Heating system, low pressure, A. Harrison	812,926
Hinge butt recesses, tool for marking and incising, W. J. McIntyre	813,319
Hitching device, Hazlewood & Robinson	813,045
Hoisting and conveying mechanism, C. C. Dolan	813,364
Holder, King & Ploss	813,047
Hoof trimmer, L. J. Hronish	813,298
Hook eye, garment, T. J. Browning	813,140
Horseshoe calk, L. A. Weyburn	812,966
Horseshoe shaping machine, C. Arbutnot	813,135
Hose coupling, E. J. W. & F. I. De Forest	813,359
Hose supporter, H. W. Cahn	813,197
Household cleaner, J. Wolff	813,339
Hydraulic intensifier, steam, T. E. Holmes	813,209
Hydrocarbon motor, A. A. Low	812,860
Ice cream machine, J. J. Glauser	813,149
Ice crusher, O. Harsch	813,544
Inhaler, C. S. Birt	813,125
Inking mechanism for presses, C. Williams	813,353
Insulator, H. B. Crouse	813,250
Internal combustion engine, C. M. Steele	812,910
Invoicing machine, J. Q. Wimer	813,141
Iron bending machine, cast, B. S. Cowles	813,257
Ironing board, knockdown, E. E. Tarr	813,276
Jar closure, F. G. Burley	812,915
Journal lubricator, A. Berry	813,192
Kettle, plaster, S. W. Womack	813,009
Knife, R. Kny	813,142
Knife cleaning machine, C. H. J. Dilg	813,251
Knitting machine, H. Stoll, Jr.	813,240
Knitting machine stop-motion, G. W. Ruth	812,936
Labeling machine, D. W. Kneisly	813,172
Lamp burner, W. G. Rankin	812,872
Lamp burner, F. W. Dressel	812,961
Lamp, incandescent electric, H. O. Parker	813,148
Lamp, inverted incandescent gas, T. Steinicke	813,331
Lamp, magnesium flash, E. F. Harrison	813,236
Lamp, oil, T. S. Tarling	813,376
Lamps and lanterns, apparatus for supplying liquid fuel to burners of, T. C. Purdy	812,832
Latch, J. L. Greenwood	812,915
Lavatory fixture, A. P. Creque	813,078
Leaching apparatus, potash, E. F. Bernhardt	12,457
Leather stretching clamp, C. B. Rathbun, reissue	813,194
Leer, W. M. Anderson	813,069
Levee, F. V. Wright	813,234
Lifting device, K. Kiefer	812,846
Liquid indicator, H. A. House	813,032
Liquid weighing machine, C. J. Hedemans	813,193
Load binder, C. W. Baker	812,871
Loading device for dirt, manure, etc., G. H. Young	812,828
Lock and latch, P. Papenfoth	812,905
Lock and latch mechanism, N. W. Crandall	812,821
Lock and latch mechanism, H. G. Voight	813,119
Lock mechanism, Caley & Voight	813,379
Lock strike, electric, H. F. Smith	813,304
Locomotive, C. Hagans	813,307
Loom warp stop-motion, A. A. Johnson	813,308
Loom warp stop-motion, Kip & Armstrong	813,309
Loom warp stop-motion, Kip & Greenwood	812,970
Loom warp stop-motion, Kip & Smith	812,887
Loom warp stop-motion, Kip & Smith	12,454
Loom warp replenishing mechanism, H. Zwicky	813,056
Lubricating wheel, O. Q. Sellers	812,835
Lubricator, C. B. & F. W. Hodges, reissue	813,261
Machine tool, combination, J. W. Myers	812,861
Mail bag catcher, J. C. Elliff	812,922
Machines, producing folding, G. H. Vining	813,126
Meat hook, pendent or trolley carrier, G. W. Martin	813,129
Meat products, apparatus for smoking and curing, W. Eppinger	813,159
Mechanical movement, C. Williams	813,071
Mechanical movement, R. T. Wingo	812,856
Merry-go-round, F. Long	813,381
Metal cutting machine, J. Abbott	813,206
Metal object, wood veneer, L. Coburn	812,842
Metal upsetting, H. V. Loss	812,855
Metal working tools, adjustable support for, B. M. W. Hanson	813,212
Metals, treating, H. H. Goodsell	812,849
Milking apparatus, E. E. Good	813,328
Milking machine, F. Ljungstrom	813,253
Mill pick, R. Johnson	812,820
Mine shaft door, I. Whitney	812,979
Mixing machine, C. Jaquet	813,117
Moltening and warming rooms or apartments, apparatus for, A. Schmidt	813,340
Mold, J. H. Sullivan	812,179
Molding machine, C. J. Caley	812,997
Molding machine, A. Choiniere	812,891
Molding machine, C. M. Bunyan	813,203
Monkey wrench, quick acting, J. L. Smith	813,124
Mop wringer, P. B. Smith	813,162
Motor chair, J. A. Himburg	813,031
Motors, interconnected suspension means for gearless, R. Siegfried	813,168
Muffler, G. E. Franquist	813,242
Multicolor press, C. Williams	812,831
Nail and rivet delivering machine, J. A. Milliken	813,367
Nut lock, A. B. Allen	813,314
Nut lock, J. Peters	812,995
Nut lock, H. Seeger	813,246
Oil and feed water separator, G. R. Davidson	813,320
Oil extracting machines, lubricating device for centrifugal, E. H. Dutcher	812,805
Oil extractor, L. E. Moffatt	813,280
Organs and pianos, foot release valve for pneumatic actions for, O. Herrmann	813,208
Packing case, partitioned, A. R. Speer	813,207
Packing for the end faces of pairs of rollers, lateral, F. E. F. Neumann	813,128
Paddle wheel, J. Best	813,288
Paper bag machine, E. E. Claussen	813,086
Paper bag machines, conveying mechanism for, O. Hesser	813,108
Paper bag making machine, O. Hesser	813,049
Paper feeding mechanism, C. Williams	812,816
Paper fixture, H. J. Williams	812,263
Paper machines, felt regulating device for, T. Hancock	813,356
Paste pot, R. P. Dist	813,355
Pencil tip, F. McIntyre	813,131
Perforating machine, B. J. Lindgren	813,132
Photographic printing device, W. H. Brown	813,235
Piano action, E. Werner	813,256
Piano attachment, self-playing, J. W. Darley, Jr.	813,158
Piano, self-playing, J. W. Darley, Jr.	812,942
Pile fabric, woyen, J. Zimmerman	812,925
Pile gage, J. Zimmerman	812,983
Pipe coupling, steam, Pine & Hynes	812,978
Pipette, S. I. Takaki	813,118
Piston rod moving device, H. Linke	813,065
Plant support, C. Lund	813,362
Planter, W. S. Graham	813,338
Planter and fertilizer distributor, combined corn, J. D. Davis	813,020
Plaster, wall, J. W. Chase	812,949
Plow, L. N. Schultz	812,968
Plows, sod turner for disk, J. J. Travis	813,292
Pocket, safety, M. C. Dexter	812,914
Post, W. W. Wilcox	813,279
Pot. See Paste pot	812,901
Powder and making same, gun, F. I. Du Pont	812,923
Power generator, electromagnetic, J. L. Potter	813,241
Preserving can, vacuum sealing, H. B. Williams	812,818
Press operating device, J. L. Haverfield	813,051
Presses, bed lock for ink table distribution, J. C. Birmingham	812,883
Printing press attachment, C. R. Clare	
Printing press automatic sheet adjusting device, F. H. Tibbets	
Printing press delivery apparatus, S. G. Goss	
Printing press, power plate, H. J. Schoen	
Profiling machine driving mechanism, E. W. Bullard	
Propeller, boat, C. E. Barber	
Pump, P. H. Lynch	
Pump for atomizers, door operated air, W. H. Rose	

### THE IMPROVED Boston Garter

**WORN ALL OVER THE WORLD**

**REFUSE ALL SUBSTITUTES OFFERED YOU**

The Name is stamped on every loop—

**The Velvet Grip**

**CUSHION BUTTON CLASP**

Lies Flat to the Leg—Never Slips, Tears nor Unfastens

Sample pair, Silk 50c., Cotton 25c. Mailed on receipt of price.

**EVERY PAIR WARRANTED**

**GEO. FROST CO., Makers**  
Boston, Mass., U. S. A.

**ALWAYS EASY**

### THE COMING THING—THE Orient

FRUCTION DRIVE BUCKBOARD

A REMARKABLE MOTOR CAR FOR \$400

MADE BY THE WALTHAM MANUFACTURING CO. WALTHAM, MASS. U.S.A.

ACTIVE AGENTS DESIRED IN UNASSIGNED TERRITORY WRITE FOR PROPOSITION AND ILLUSTRATED CATALOG

The best Agency Proposition in America. Write for particulars and illustrated catalog.

### We Guarantee to Reduce Fuel Consumption

We guarantee that the Dean Boiler Tube Cleaner will reduce your fuel consumption. This Cleaner is used by over 6,000 power users.

We'll loan a cleaner to you to demonstrate its value. Send size of tubes and cleaner will go forward.

The book, "Boiler Room Economy," tells all about scale and the Dean Cleaner. Send for it TO-DAY.

**W. M. B. PIERCE CO.**  
819 Washington St., Buffalo, N. Y.

**BABBITT METALS—SIX IMPORTANT FORMULAS.** SCIENTIFIC AMERICAN SUPPLEMENT 1123. Price 10 cents. For sale by Munn & Co. and all news-dealers. Send for catalogue.

### INVESTIGATE THE POULTRY BUSINESS

Write for a free copy of my book describing **Profitable Combinations of Egg, Broiler and Roaster Farms**

It gives the prices paid for eggs and poultry week by week for the past three years. It tells how and when a hatch taken off each week in the year could be most profitably marketed. It shows how you can make \$2.00 on a large winter roaster. It tells what profits can be made with each of the popular breeds, and the costs of production. I have helped thousands to make money with poultry. My Model Incubators and Brooders are used on the money-making farms. It is my business to teach those who use them to do so profitably. Whether your needs are small or large, I will furnish without charge, estimates and plans for a complete equipment that will insure success without your spending a dollar uselessly. Send for my complete literature.

**CHAS. A. GYPHERS**  
3944 Henry St. Buffalo, N. Y.

Pumping apparatus, H. W. Kimes	813,008
Radiator, I. Brooke	813,275
Radiator air valve, F. W. Leuthesser	813,011
Rail bond, E. C. Thomas	812,900
Rail bonding tool, P. C. Arney	812,803
Rail, cast manganese steel, W. Brinton	812,810
Rail crossing, F. A. Lehmann	813,387
Rail joint, T. W. Mayo	813,224
Rail splicing device, T. W. B. Knight	813,157
Railway automatic switch, electric, Joksche & Petrik	813,154
Railway crossing, G. W. Lancaster	813,311
Railway frog turn-ins and turnouts, E. M. Rankin	812,877
Railway joint, G. M. McClure	813,057
Railway journal boxes, means for preventing theft of brasses from, E. J. Noblett	812,866
Railway rail, E. C. Geneux	812,988
Railway signal, W. Loos	812,941
Railway stock guard, L. Liesmann	813,220
Railway switch operating apparatus, C. J. Coleman	812,825
Railway tie, Booth & Bittle	812,807
Railway tie, S. N. Griffith	812,991
Railway tie, J. B. Johnson	813,006
Railway tie, C. E. Shannon	813,243
Railways, closed conduit for electric, Lohman & Pruis	813,101
Railways, ice cutter for surface, W. H. Perry	812,873
Raisins to remove cap stems, treating, F. C. Adams	812,971
Razor, J. W. Offutt	813,232
Reclining chair, L. Kipp	813,156
Recording instruments, paper pressing attachment for, C. Hult	813,005
Refrigerating means, J. Beck	813,195
Rein guard, Scott & McCall	813,329
Rein supporter, Stokesbury & Lawhead	812,896
Relay, A. & L. G. Vera	813,184
Retort benches, apparatus for charging, A. L. J. Queneau	813,023
Retorts, muffles, furnaces, and the like, charging, A. L. J. Queneau	813,021
Reversing mechanism, I. G. Yoders	813,341
Roads, etc., prevention and laying of dust in, W. M. Sandison	813,389
Rock drill, D. C. Demarest	813,041
Roofing material, sheet, H. R. Wardell	813,336
Roofing, ready-made, W. J. Moeller	813,163
Rotary engine, J. H. Kenner	813,024
Rotary engine, G. B. Eckler	813,284
Rotary engine and motor, M. S. Okun	813,018
Rule, garment designing curve, E. L. Phelps	812,874
Safes or vaults, making, W. Brinton	813,394
Sand drier, Wilson & Bronson	813,191
Sash adjuster, window, H. Bowers	812,808
Sash weights, mold for casting center hung, L. H. Knapp	812,935
Saw blades from sagging, device for preventing the shafts or arbors of, T. B. Rice, Jr.	813,238
Saw clamp, C. W. Cardwell	813,836
Saw drive, W. Lewis	812,853
Saw tooth, C. G. Fleming	813,371
Saws, gage for ivory nut, J. Hornby	813,002
Saws, resawing attachment for band, M. Garland	812,987
Sawing machine, numerator, F. L. Kreil	813,099
Sawmill carriage dog, M. S. Eby	813,143
Sawmill feed drive, H. C. Clay	812,823
Screw, temper, B. C. Hagan	813,378
Screws upon long rods, device for cutting, P. Preuss	813,114
Seal press, E. J. Brooks	813,079
Seal, self-locking, F. Laporte	813,219
Seaming machine, O. S. Beyer	813,034
Separating machine, H. Baldwin	812,972
Separating substances of different dielectric capacities, H. M. Sutton, et al.	813,063
Separator. See Oil and feet water separator	
Setting, G. W. Dover	813,084
Sewer cleaner, J. M. Thompson	813,028
Sewing machine needle-threader, S. Blumen-thal	813,138
Shaft gate, Brown & Taylor	812,814
Shafting and for like purposes, apparatus for ascertaining errors in the alignment of, A. E. Horsfall	813,003
Shaving stick holder, R. L. Warner	812,906
Shelves, apparatus for removing articles from, G. Ward	813,029
Shingle edging machine, C. Provost	812,951
Shoe, F. X. Brodeur	812,812
Shoe, J. G. Marchand	813,185
Shoe and slipper hanger, C. Ackroyd	813,072
Shoe nailing machines, nail supplying device for, W. Knecht	813,310
Shovel, J. E. Newton	813,166
Shutter fastener, A. D. Bartlett	813,343
Sign, illuminating, Gatzert & Berens	813,087
Silk fibroin peptone, making, J. Altschul	813,272
Skin stretching machine, A. A. Hellwig	813,293
Snow removing apparatus, H. Maine	813,050
Soda water bottling machine, W. C. Wood	813,340
Soldering iron, P. Gilbert	813,374
Sparkling device, H. A. Miller	813,104
Speed changing mechanism, P. Shannon	812,888
Speed controlling system, A. L. De Leeuw	813,201
Speed indicator, B. Volman	813,185
Spike puller, J. F. Loreman	813,223
Spinning frame tension device, R. G. Carle	812,919
Spray, J. M. Sweeney	813,254
Spring wheel, F. A. Born	813,035
Square, mechanic's, J. M. Realing	813,173
Stall floor rack, J. H. Murray	813,177
Stapling machine, C. A. Juengst	813,215
Starting device, automatic, H. A. Warden, et al	813,262
Stay bolt, J. B. Tate	813,120
Steam boiler, D. Wigert	812,908
Steam engine, F. S. Hyde	813,301
Steam generator, W. S. Johnson	813,068
Steam generator, C. F. Altmann	813,133
Steam trap, J. H. Taylor	813,332
Steel treating, manganese, W. Brinton	812,811
Stencil cutting attachment, G. L. Hilliker	813,004
Stereotyping apparatus, S. G. Goss	812,924
Stone dressing device, H. R. Hughes	813,210
Stone plates, production of artificial, C. Pohl	813,171
Stoves, heater attachment to, E. Bell	813,137
Suspender end, W. W. Hoopes	813,296
Swing, giant, T. G. Hill	812,996
Tachometer or speed indicator, V. Kobizek	812,937
Tag, shoe rack, C. H. Holt	813,001
Telephone exchanges, service meter for, McBERTY & Craft	813,230
Telephone memorandum attachment, F. B. Gilbert	812,841
Telephone system, R. Sherer	813,330
Therapeutic pad, P. B. Hardy	813,092
Thill, shifting, T. Grant	812,843
Ticket, transfer, W. C. Pope	813,321
Tile, mixing, G. R. Schimmel	812,953
Tile protector, drain, W. J. McHugh	813,016
Timepiece stem-winding mechanism, C. R. Stucky	812,963
Tinned sheets or surfaces, treating oxidized, S. K. Green	813,147
Tire, wheel, E. F. Sobers	812,893
Titanium with other metals, combining, F. E. Canda	813,278
Tongs, G. Kernin	812,922
Tool, combination, J. D. Barry	813,342
Tool, combination, R. A. Baggett, reissue	12,458
Tool of the hammer type, combination, H. E. E. Molkenhuth	812,947
Toothpicks from veneer strips, cutter for cutting, G. P. Stanley	812,895
Top roll saddle, G. L. Pierce	812,875
Toy, I. Kinman	813,306
Toy for baby or doll carriages, rotary, W. Saxon	813,391
Toy, mechanical and magnetic, H. Cottrell	813,082
Trace carrier, J. H. Wilson	812,909
Track or trolley wire, adjustable, W. Hills	813,295
Traction system, electric, J. P. Gorman, Jr.	813,087
Trammel, J. F. Hottman	813,085
Tramway switch, O. C. N. Gundersen	813,091
Trolley wheel, electric car, J. H. Kinter	812,851
Trolley wheel, J. Hensley	812,847
Trolley wires, hanger or ear for overhead electric, A. Richardson	812,881
Troposcope, S. W. Balch	813,136
Trousers rack, M. Rosenberg	813,239
Truck, locomotive, W. E. Symons	813,255
Trunk, C. C. Wington	812,967
Tub, P. Connolly	812,826

## "A Kalamazoo Direct to You"

You save from 20% to 40% by buying a Kalamazoo Stove or Range direct from the factory at lowest factory prices. Moreover, you get a stove or range not excelled by any in the world. We guarantee quality under a \$20,000 bank bond.

**- We Ship On 360 DAYS APPROVAL and We Pay the Freight.**

If you do not find the Kalamazoo exactly as represented, the trial does not cost you a cent. It will pay you to investigate.

**Send Postal for Catalog No. 346.**

All Kalamazoos are shipped promptly, by, blacked, polished and ready for use.

**Kalamazoo Stove Co., Mfrs., Kalamazoo, Mich.**

All our cook stoves and ranges are fitted with patent oven thermometer which makes baking easy.




## Stoddard-Dayton

(MODEL D)


A perfect power plant swung lightly but securely in a frame of hot-rolled, high carbon, pressed steel so re-enforced that tremendous weight will not deflect it. Roller bearings everywhere, running in a constant bath of oil.

**Control—absolute Comfort—princely**

The Stoddard-Dayton, Model D 5-passenger Touring Car has a special type of 4½ x 5 in. 4-cylinder motor; water-cooled; frame of hot-rolled, high carbon, pressed steel; sliding gear transmission; three speeds and reverse—selective type, can change from high to intermediate, or vice versa, at speed of 25 miles, without clashing or noise, up hill or down; practically noiseless; entire transmission on roller bearings; mechanical lubrication; 30-35 horse-power. Proportion of power to weight, one horse-power to every sixty pounds. \$2250.

Send for our 1906 book B—It's FREE

**The DAYTON MOTOR CAR CO., Dayton, O.**



"As good as it looks"

## \$250 for an Automobile

The "Success" is just what you have been waiting for. It is an Automobile Buggy—light, strong, powerful, speedy, safe and easy to operate. The "Success" is not an experiment. It is thoroughly practical—invented by an engineer with ten years' experience in automobile construction. Over ordinary roads it will run 100 miles on one gallon of gasoline. It's a good hill climber—takes a 30% grade. Speed from 4 to 18 miles per hour. No complicated parts to get out of order.

Orders for Spring delivery should reach us early as orders for March shipments will tax our output facilities. Write for descriptive literature, terms, etc.

**"SUCCESS" AUTOMOBILE MFG. CO. 532 De Baliviere Ave., St. Louis, Mo.**

## "How to Remember" Stop Forgetting

Free to Readers of this Publication

You are no greater intellectually than your memory. My course simple, inexpensive. Increases business capacity, social standing, gives an alert, ready memory for names, faces and business details. Develops will, conversation, speaking, etc. My booklet, "How to Remember," sent free.

**DICKSON SCHOOL OF MEMORY, 700 Kimball Hall, Chicago**

## Our Sectional Filing Cabinet FOR Blue Prints and Electrotypes

is built in sections so sections may be added from time to time as required. We also carry a full line of various styles of Draughting Tables, Blue Print Frames, etc.

Send for Catalogue or ask your jobber.

**Fritz & Goedel Mfg. Co., 97 Alabama St., Grand Rapids, Mich.**

## HENS ARE MONEY MAKERS

With the aid of a Genuine 1906 Pattern **STANDARD CYPHERS INCUBATOR.**

It hatches More Chicks and Healthier Chicks than any other. **90 Days Trial.** Big 228 page Cat'g FREE if you mention this journal and send addresses of two friends interested in poultry. Write nearest office.

**Cyphers Incubator Co., Buffalo, Boston, Chicago, New York, Kansas City or San Francisco.**

## GLOBE INCUBATORS.

Hatch chickens. No experience necessary. Our large new Illustrated Catalogue of Incubators and Brooders and Poultry Information mailed free. Write to-day. Address **C. G. SHOEMAKER Box 651 Freeport, Ills.**

Tube clip, F. A. Bellamy	813,033
Turbine, combined impulse and reaction, C. Penninger	813,169
Turbine driven machinery, Bateau & Sauter	812,878
Turning, shaping, and finishing machine, automatic, A. B. Weisz	813,187
Turpentine, refining, G. O. Gilmer	813,088
Twine, waterproofing, H. Feder	812,837
Typewriting machine, A. J. Briggs	813,345
Valve, check, M. L. Sanborn	812,885
Valve controlling mechanism for explosive engines, Graham & Fox	813,043
Valve for automatic sprinkler systems, dry pipe, E. S. Clayton	813,350
Valve for humidifying and heating systems, electrically controlled regulating, S. W. Cramer	813,083
Valve gear for explosion engines, H. Richter	813,116
Valve mechanism for motors, supply and exhaust, W. H. Johnson	813,305
Valve, reversing, W. A. Field, et al.	812,840
Valve, safety, C. J. Fancher	813,145
Valve, throttle, R. A. Norling	813,110
Vehicle brake, electric, J. N. Mahoney	813,052
Vehicle, motor, P. E. Hanson	813,044
Vehicle, motor propelled, W. S. Johnson	813,213
Vehicle springs, equalizing device for, J. A. Roth	813,388
Vehicles, wind shield for, G. W. Kerr	812,930
Velocipede, ice, H. Schneekloth	813,025
Vender, peanut, J. C. Simering	813,026
Veneer bending machine, H. O. Little	812,854
Vessel, Z. Scott	813,177
Vessel and mechanism connected therewith, submarine, G. Simpson	812,956
Veterinary surgical instrument, W. B. Compton	813,080
Vise, T. W. Vane	813,260
Voting machine, S. D. Layton	812,938
Voting machine, C. E. Kimbrough	813,007
Wagon, dumping, J. E. Briggs	812,918
Wagon gear, E. Einfeldt	813,285
Wardrobe rack, G. R. Thiss	813,258
Washing machine gearing, H. H. Munson	813,015
Washing machines, mechanical movement for, W. Sweet	813,392
Waste materials, apparatus for treating and roasting, F. W. Koontz	813,385
Water and chemicals, rendering materials or articles resistant to, Kochmann & Kaufmann	813,218
Water by electrolysis, decomposing, W. F. M. McCarty	813,105
Water closet flushing apparatus, W. U. Griffiths	812,992
Water wheel, D. Hug	813,299
Weather strip, L. W. Woodburn	813,268
Weighing device, H. E. Dahlman	812,830
Welding machine, electric, W. C. Winfield	812,969
Wells, device for raising liquids from, W. Richards	813,322
Wharf or landing stage, A. Janssens	813,046
Wheel. See Lubricating wheel.	
Wheel, C. P. Melvin	813,225
Wheel rim, vehicle, I. Hodgson	813,382
Wheels, snow shoe for, F. W. Nightingale	813,231
Wheelbarrow, W. Gossett	812,990
Wicket, W. P. Oliver	812,948
Winding machine, thread, G. W. Foster	813,372
Window box for flowers, metal, E. E. Bixler	812,806
Window screen, E. T. Brown	812,813
Window screen, D. W. Keith	812,850
Window screen frame, H. E. Pallady	813,234
Wire lock, A. M. Keeney	812,928
Wire stretcher, K. Cunningham	812,981
Wood boring braces, attachment for, D. B. Yoder	813,070
Work holder, J. W. Spence	812,960
Wrapping machine, M. H. Ballard	812,912
Yoke, neck, W. M. Carriker	812,822


### DESIGNS.

Bag frame, hand, W. Stavenhagen	37,830
Fabric, printed textile, E. B. Vandergaw	37,843, 37,844
Grave cover, W. J. Huber	37,837
Jar, J. E. Lee	37,829
Lace, levers, C. W. Birkin	37,838 to 37,842
Lamp reflector, incandescent electric, O. A. Mygatt	37,835
Rug, A. Petzold	37,845 to 37,847
Tile, W. B. Goddard	37,836
Toy shooting apparatus, casing for, H. Kunzel	37,831


### TRADE MARKS.

Alcohol, C. H. Graves & Sons	49,857
Ammonia compressors, Vulcan Iron Works	49,895
Automobiles, Knox Automobile Co.	49,905
Automobiles, Studebaker Automobile Co.	49,915
Axes and hatchets, Supplee Hardware Co.	49,916
Badges, gold-plated, Irons & Russell	49,860
Baking powder, J. C. Grant Chemical Co.	49,861
Baking powder, Hulman & Co.	49,902
Beans, dried, Albert Dickinson Co.	49,917
Beer, bottled lager, Valentin Blatz Brewing Co.	49,804
Blacking and leather dressing, F. E. Fennessy	49,853
Blanks, soles, and taps, leather, Daniel Forbes Co.	49,792
Bolts, shaking, Barnard & Leas Manufacturing Co.	49,848
Boots and shoes and leather therefor, leather, American Oak Leather Co.	49,798
Boots and shoes, leather, Lynchburg Shoe Co.	49,793
Boots and shoes, leather and canvas, Geo. E. Keith Co.	49,811
Bottles, glass, A. G. Smalley	49,875
Bread raising preparation, Rumford Chemical Works	49,914
Candies, chocolate, Hazen Confectionery Co.	49,900
Candy, Postum Cereal Co.	49,913
Canned pears, R. S. Weston	49,898
Cards, playing, United States Playing Card Co.	49,803
Cards, playing, New York Consolidated Card Co.	49,840 to 49,843
Cards, playing, United States Playing Card Co.	49,844 to 49,846
Cards, playing, New York Consolidated Card Co.	49,889
Cement, Portland, Helderberg Cement Co.	49,886
Coats, vests, trousers, and overcoats, Goldsmith, Joseph, Feiss Co.	49,885
Cocoa, Walter Baker & Co.	49,926
Coffee substitutes, M. T. Lefebvre	49,906
Collars and cuffs, William Barker Co.	49,805
Corn starch, J. C. Hubinger Bros. Co.	49,904
Corsets, Kabo Corset Co.	49,827
Cotton fabrics, certain named, Meyer & Goetze	49,831
Cotton flannel, Pemberton Co.	49,832
Cotton piece goods, Massachusetts Cotton Mills	49,829
Cotton sheetings and drills, Augusta Factory	49,880
Crash, linen, Stevens Linen Works	49,833
Detergent preparation, Holzappel's Compositions Co.	49,859
Drums, Duplex Manufacturing Co.	49,851
Dyspepsia tablets and capsules, Vig-Ni Medicine Co.	49,894
Electric fixtures, socket bushings for, Frank H. Stewart Electric Co.	49,855
Electric light supports, Frank H. Stewart Electric Co.	49,854
Entremets, deviled, William Underwood Co.	49,927
Fertilizers, artificial, Spartanburg Fertilizer Co.	49,877
Flour, potato starch, and dextrin, potato, Norddeutsche Kartoffelmehl-Fabrik mit Beschränkter Haftung	49,911
Flour, self-raising prepared buckwheat, F. C. Williams	49,928
Flour, wheat, Pittsburgh Milling Co.	49,912
Flour, wheat, Threefoot Bros. & Co.	49,923
Forging and forming machines, metal, Ajax Manufacturing Co.	49,879
Galvanized fastening devices, Keystone Nail Co.	49,864
Gold, silver, or copper, bars, ingots, sheets, or molds of, H. W. Treat	49,893
Grease cups, Lunkenheimer Co.	49,883
Hames, Todd Manufacturing Co.	49,882


## This Lamp is an Ornament to Any Automobile



THE attention of manufacturers and dealers is especially requested for these lamps and horns. The price is far below what you have been accustomed to pay and I guarantee that they are as well constructed, as durable and just as showy as the expensive equipments which come only with the imported automobiles. A car looks very much better if it has imposing lamps and a fine horn. I can supply these at prices which may seem to you impossible. Write to-day.



**A. H. FUNKE, 83 Chambers Street, New York**



## HASBROUCK

SAFE SIMPLE SILENT SAVING


A combination of excellence unsurpassed in the motor world. Send for illustrated catalogue sent free.

**HASBROUCK MOTOR WORKS, Inc., - - - New London, Conn.**

CLINTON, MICH., Dec. 21, 1905.  
BRENNAN MOTOR CO., Syracuse, N. Y.

GENTLEMEN:—The 20 H. P. Motor I bought of you three years ago, to run my ice har-

vester, is a dandy. It is simple, easy to control and cheap as to fuel. I did my threshing with it, running a large separator, with blower for stacking, and it seemed to run with as much power, if not more, than the large steam engine. Crowds of people came to see the little thing run such a large machine and do the work so easily. It took about three hours to thresh over 400 bushels of grain and we did not stop once. Any one wanting a motor will make no mistake if they get a J. B. HASCSE.



Yours very truly,  
**BRENNAN STANDARD MOTOR**  
Mounted with Individual Clutch Gear, also Furnish Sliding Gear Transmission.  
Motors from 6 to 80 Horse Power.

## Clean House With Air



Over 55 Companies operating Thurman Patents in America, and as many more in Canada, England, and Europe.

FREE CATALOGUE

**General Compressed Air House Cleaning Co. ST. LOUIS, U. S. A.**

Manufacturers of the Celebrated Thurman direct-connected Gasoline Driven Air Compressors for Mines, Pneumatic Tools, Etc.

## BACKUS

GAS & GASOLINE ENGINE

Simple, Economical, Durable  
Suitable for all kinds of work

**BACKUS WATER MOTOR, cheapest power known**

Write for circular and prices


**BACKUS WATER MOTOR CO., Newark, N. J., U.S.A.**

## MILLS FOR ALL MATERIALS.

OUR BUSINESS IS TO MAKE MACHINERY FOR GRINDING GRAIN, CRUSHING ROCKS AND PULVERIZING ALL HARD SUBSTANCES. WE HANDLE ALL KINDS OF MATERIALS FROM COTTON-SEED TO ROOTS AND HERBS. BY AN UNEXCELLED WANTED ANY KIND OF A MILL OR GRINDING MACHINE, COME TO US AND YOU WILL GET THE BEST AND STILL SAVE MONEY.

DEAL WITH US ONCE AND YOU WON'T CHANGE.  
ESTIMATES FREELY FURNISHED.  
**SPROUT, WALDRON & CO. MUNCY, PA.**

## WHITWASH YOUR BUILDINGS



At Lowest Cost  
with a Progress Universal Spraying Machine. One man can apply whitewash, calcimine, or cold water paint to 10,000 square feet of surface in ten hours, and do better work than with a whitewash brush. It is also adapted for spreading disinfectants, destroying insect pests and diseases on trees, vegetables, and other plants, extinguishing fires, washing windows, wagons, etc., and other purposes. This machine is really a portable water works system, as it develops a pressure of over eighty pounds, and lifts the liquid more than eighty feet higher than itself. The Progress costs only \$21.00 and lasts a lifetime. It pays for itself the first year. Write for detailed description.

**DAYTON SUPPLY CO., Dayton, Ohio.**

## Big Boats Answer the Watres Power Whistle

Its blast can be heard a distance of two miles.

There is nothing to do but pull a cord. The Watres is a power whistle, uses spent gas only, weighs complete but 80 pounds, and can be attached by anybody to any gasoline engine.

The Watres Boat Whistle is made in two sizes and both are sold under our absolute guarantee to pass Government inspection and to refund purchase price if a month's use does not convince you of their efficiency.

Two-inch chime, \$35.00; 1½-inch chime, \$25.00. Write for free booklet, "At Last a Gas Whistle."

**Gas Engine Whistle Co. 1137 Broadway, New York City**

## Don't Waste Time



**AUTOMATIC CARD INDEX CO. Dept. A. 527-531 Bleecker Street, Utica, N. Y.**

## Screw Machine Products

in HIGH BRASS, LOW BRASS and STERLING SILVER

Quotations Made From Model or Working Drawings

**GEORGE W. DOVER CO. Factory B Providence, R. I.**

## Army Auction Bargains

Revolvers . \$0.50 up  
"Holsters" . 10 "  
Haversacks . 10 "  
Knapsacks . 50 "  
Carbines . 50 "  
Muskets . 1.65 "  
Saddles . 1.90 "  
Saddle Bags (pr.) . 75 "  
Bridles . 65 "  
Navy Hats . 10 "  
Army Campaign Hats . 25 "  
Leggins (pair) . 15 "  
Army Uniforms consisting of New Helmet, Coat, Trousers all for 1.65  
176-page Large Illustrated Catalog mailed (stamp) . 12  
FRANCIS BANNERMAN, 501 Broadway, N. Y.  
Largest Stock in the world Government Auction Goods  
15 acres storage—2½ acres Broadway salesroom

## Waterproof Stops Leaks

in tin, iron, shingle or prepared felt roofings and will add many years to their life. It also makes a perfect protection from rust on smoke stacks, engines, machinery, tank cars, steel bridges or in fact anything made of iron, steel or tin. EVERTITE is made in three colors. We want to send you sample for examination; also our booklet.

**ASBESTOS MFG. & ROOFING COMPANY 215 Carr Street, St. Louis, Mo.**



**MANUFACTURERS!**  
You can make and market the  
**GEM CITY WIND MILL**  
at prices so low as to guarantee large returns. Steel and iron construction throughout; triangular shaped, open, steel tower; ball-bearing, sensitive turn table; wheel always to wind; few working parts; easily lubricated; best—simplest—cheapest—strongest. Patents for sale—Write today.  
**Dayton Supply Co., Dayton, Ohio.**

**HANG IT**  
upside down if you like, and it won't spill a drop. Of course it's the "GEECEE" Dry Storage Battery, which during the recent New York Show was used in all the demonstration cars of the following firms: Olds Motor Works, Berkshire Automobile, York Automobile, etc.  
An ideal battery for all kinds of ignition work, small incandescent lights, dental engines, canisters, wireless telegraph, small motors, etc. Write for '06 Catalog and trade prices.  
**Royal Battery Co., 143 Chambers St., N. Y.**

**Acetylene Gas Users**  
Should get **ALCO BURNERS** for House Lighting or Auto Lamps. Longest life. Highest candle-power. \$2.10 dozen.  
**AMERICAN LAVA COMPANY**  
Chattanooga, Tenn.

**THE BERKEFELD FILTER**  
The Standard of the World  
The only filter removing typhoid and cholera bacilli from the water. Tested and recommended by Bacteriologists all over the world. The greatest invention in the filter world during the last ten years. The filter gives water in small and large quantities according to the sizes. Easily cleaned, filter cylinders sterilized by boiling in water. Send for circulars to  
**BERKEFELD FILTER CO.**  
4 Cedar Street, New York

**Colleges and Schools**  
find our Castings and Parts for Motors, Dynamos, Dynamotors, A. C. Rectifiers, etc. (1-15th to 3/4 H. P.) exactly what they need for demonstrating the construction and operation of such machines. We sell outfits complete or a single piece at a time. Complete outfits from \$3.50 up, with full instructions and blue prints. Just right for Amateurs, Electricians and Experimenters. Bulletin W mailed free.  
**PARSELL AND WEED, 129-131 W. 31st St., N.Y. City**

Used by forty of the leading Automobile and motor boat manufacturers. Suitable for any gas or gasoline engine using make and break or jump spark ignition.  
**EVERY BATTERY GUARANTEED** to give satisfaction or purchase money refunded.  
**WITHERBEE IGNITER CO.**  
27-31 Thames St. - NEW YORK

**ELECTRONS AND THE ELECTRONIC**  
Theory are discussed by SIR OLIVER LODGE in SCIENTIFIC AMERICAN SUPPLEMENTS 1428, 1429, 1430, 1431, 1432, 1433, 1434. Price 10 cents each, by mail. Munn & Company, 361 Broadway, New York City, and all newsdealers.

**CUBA**  
Beyond the Line Where Snow Flies  
Atropical climate gives you "that luxurious feeling" which only comes with complete rest.  
**THE HAVANA LIMITED**  
A train de luxe, leaves Chicago FRIDAY AFTERNOONS at 3, St. Louis 9.40 p.m., arrives Mobile DOCK after dinner Saturdays, when you are transferred direct to the New Palatial Steamship "Prince George," arriving Havana in time for breakfast Monday.

The equipment of the train and the accommodations on the boat are the best offered winter tourists.  
**ROUTE** Chicago & Alton Ry. Mobile & Ohio R.R. Munson Steamship Line  
May we have an opportunity of elaborating on the advantages of a Cuban trip this winter?  
Address **GEO. J. CHARLTON**  
Gen'l Pass'r Ag't., Chicago & Alton Ry. CHICAGO, ILL.

**60 YEARS' EXPERIENCE**  
**PATENTS**  
TRADE MARKS DESIGNS COPYRIGHTS & C.  
Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. HANDBOOK on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the  
**Scientific American.**  
A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all newsdealers.  
**MUNN & Co., 361 Broadway, New York**  
Branch Office, 625 F St., Washington, D. C.

Hats and caps, men's and women's, R. J. Hunter	49,824
Hose supporters, C. J. Higley	49,822, 49,823, 49,858
Insulating compound, Standard Underground Cable Co.	49,876
Knit hosiery and underwear, M. & C. Mayer	49,908, 49,909
Knitted hosiery, undershirts, and drawers, J. W. Mettler	49,830
Kummel, Charles Jacquini et Cie	49,791
Lard, L. G. Cromwell	49,899
Laxative fruit preparation, effervescent, H. J. Mayers	49,865
Lead, white, National Lead Company of Massachusetts	49,866
Leather for boots and shoes, upper, Thayer Foss & Co.	49,797
Loom pickers, Norfolk Loom Picker Co.	49,868
Lubricants and lubricant stock, cylinder, Conewango Refining Co.	49,882
Magazines, Criterion Publishing Co.	49,821
Medical ointment, R. M. Connable	49,806
Medicinal preparations, W. R. Warner & Co.	49,896
Metal polishes, J. P. Wulzen & Co.	49,922
Milling cutters, Standard Tool Co.	49,918
Molasses, Eastern Refining Co.	49,910
Oil, olive, Thomas McMillen & Co.	49,863
Oil, painting, staining, and graining, James B. Sipe & Co.	49,925
Olives, S. J. Valk & Bro.	49,874
Overalls, E. G. Sanders	49,808
Packing, machinery, C. A. Daniel	49,856
Paints, enamels, and bronzing liquids, certain named, Gerstendorfer Bros.	49,891
Pajamas and night robes, T. J. Maxwell & Co.	49,790
Paper stock, ground wood and wood pulp for, Aspegren & Co.	49,828
Periodical or magazine, trade journal, Lord & Nagle Co.	49,872
Phosphatic solutions, Rumford Chemical Works	49,892
Piano players, combination pianos, and parts thereof, Wilcox & White Co.	49,890
Pianos, Sterling Co.	49,819
Pills, purgative, W. H. Comstock Co.	49,816
Powders, headache, R. S. Starks	49,870
Precious stones for jewelry, imitations of, Kegnelt, Bigney & Co.	49,849
Pulleys, blocks, and parts thereof, Boston & Lockport Block Co.	49,888
Remedies, eye, Murine Eye Remedy Co.	49,809
Remedy for children's colic and cholera infantum, J. C. Franklin's Sons & Co.	49,850
Remedy for rheumatism, C. Carow	49,815
Remedy, liquid, G. M. Sloat	49,867
Sausage stuffers, and meat presses, National Specialty Manufacturing Co.	49,834
Seeds, certain named, Albert Dickinson Co.	49,884
Shellac, first coat or substitute for, Glidden Varnish Co.	49,839
Shirts, dress and negligee, Manifest Shirt Co.	49,930
Shoes, boots, and slippers, leather, J. G. Brandt Shoe Co.	49,879
Shovels, spades, scoops, and spading forks, Supplee Hardware Co.	49,795
Silk, embroidery and knitting, J. Pearsall & Co.	49,871
Silk piece goods having a rough surface, Rogers & Thompson	49,826
Silver plated hollow ware, International Silver Co.	49,903
Starch for laundry purposes, lump, J. C. Hubinger Bros. Co.	49,862
Starch, laundry, J. C. Hubinger Bros. Co.	49,869
Steel, Park Steel Co.	49,799
Steel ware, stamped, Jacob J. Vollrath Manufacturing Co.	49,852
Stove polish, Eye Shine Polish Co.	49,907
Stoves and ranges, Liberty Stove Co.	49,897
Stoves, heating stoves, and ranges, cook, A. Baldwin & Co.	49,847
Telephone sets, Baird Manufacturing Co.	49,807
Tonic, J. Corato	49,814
Tonic and restorative, uterine, Rio Chemical Co.	49,881
Tonic, phosphate, Bios Laboratory Co.	49,817
Tonics, nervine, and sedatives, Dr. Miles Medical Co.	49,921
Twist drills, Standard Tool Co.	49,883
Varnishes, David B. Crockett Co.	49,919, 49,920
Watch movements, Hampden Watch Co.	49,794
Whiskies, all kinds of, S. C. Herbst	49,796
Whisky, Miloslawsky & Kraus	49,800
Whisky, T. W. Samuels Disty	49,810
Whisky, Ginter Grocery Co.	49,812
Whisky, J. A. Freiberg	49,813
Whisky, J. J. Hagerty & Co.	49,818
Whisky, J. A. Bokel Company of Baltimore City	49,873
Whisky, Hoffheimer Bros. Co.	49,920
Wines, S. S. Pierce Co.	
Yeast, crumb, Yost Yeast Co.	

**LABELS.**

"Bonafid," for toilet paper, Scott Paper Co.	12,680
"Bonnette," for coffee, Fort Smith Commission Co.	12,671
"Callier's Cut Loaf Cream Candy," for candy, J. B. Callier	12,675
"Columbia Phonograph Co., Columbia Record," for sound records, Columbia Phonograph Co.	12,683
"Edstrom's Lung Gas," for medicine, O. E. Edstrom	12,677
"Havana Bit," for cigars, P. Wohl & Co.	12,668
"Hazel Patch," for cigars, O. A. Leistikow	12,670
"Little Nemo's Barefoot Sandal," for sandals, H. Jacobs & Sons	12,681
"McCarthy's Winner," for dry plates, McCarthy Dry Plate Co.	12,682
"Mrs. Winslow's Borated Violet Talcum," for toilet powder, M. Chubb	12,676
"Penn's Plasters," for adhesive plasters, Penn Chemical Co.	12,678
"Prince's Lintment The Great Panacea," for liniment, A. E. Lynch	12,679
"61," for cigars, Bethany Cigar Co.	12,669
"Soda Mint Water," for carbonated water, Soda Mint Water Co.	12,672
"Sponge-Ate The Greatest Bait," for confectionery, Hook & Crownfield	12,674
"Syrret," for syrup, C. H. Keyes	12,673

**PRINTS.**

"Adler's Spring and Summer Clothes," for men's spring apparel, David Adler & Sons Clothing Co.	1,580
"An Easy Shave," for shaving soap, O. F. Woodward	1,576
"Fit-Easy," for shoes, A. S. Bacon	1,578
"Hammer the Hammer," for revolvers, Iver Johnson's Arms and Cycle Works	1,581
"Men's Apparel," for men's apparel, W. C. Both	1,579
"Sauer's Famous Flavoring Extracts," for flavoring extracts, C. F. Sauer Co.	1,573
"The Delicious," for candy, Rochester Candy Works	1,575
"The First Hands," for flour, Washburn Crosby Co.	1,574
"The Knox-All Hat," for hats, F. A. Lux	1,577

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.  
Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

# FRANKLIN

**Why are Franklins the most economical of all motor cars?**  
Because they give not only the best kind of service; but they give it long-est; at the lowest operating and maintenance cost; and they give it every day in the year.

The kind of service Franklin cars give begins with an exceptionally efficient engine in which Franklin air-cooling creates the best-working temperature possible to obtain in a gas-motor cylinder;—a temperature that the Franklin auxiliary exhaust constantly maintains by freely discharging the hot gases of the explosion; before the main valve opens; thus positively preventing back-pressure and overheating; and saving the power commonly lost through burnt and leaky valves.  
Franklin flexible wood sills and four full-elliptic springs absorb road shocks; thus saving the power ordinarily lost through vibration; and making this power more fully available by permitting necessary speed over rough roads with perfect comfort to the occupants of the car.

These qualities of Franklin cars give them genuine usable road ability far beyond that of any other cars of their weight, rating or price.  
The great length of service rendered by Franklin cars comes from the highest grade materials; and the most suitable construction of every part; as indicated by the high grade nickel-steel used; the sheet aluminum bodies and Hess-Bright ball-bearings.  
The extremely low running expense of Franklin cars is due, first, to the high engine efficiency which produces full power on remarkably small fuel consumption; next, to the strong, simple, flexible construction which reduces repair cost to the lowest terms; and thirdly, to the absence of water-cooling apparatus; getting rid of its superfluous weight and thus tremendously cutting down tire bills.


The final important item in the economy of Franklin cars is the fact that having no water about them they never can freeze. Their cost may be divided by 365 working days in every year—and one day more in leap year.

Write for the Franklin catalogue—at once the most sumptuous and most sensible motor book ever printed.

Four-cylinder Runabout	\$1400	Four-cylinder Touring-car	\$2800
Four-cylinder Light Touring-car	\$1800	Six-cylinder Touring-car	\$4000

Prices f. o. b. Syracuse

**H. H. FRANKLIN MFG. CO.,** Syracuse, N. Y., **M. A. L. A. M.**  
Type D. Four-cylinder Touring-car. 5 passengers. Air-cooled motor. 3-speed sliding gear transmission. 20 "Franklin horse-power." Disc clutch. Force-feed oiler on dash. 100-inch wheel base. 1800 pounds. 45 miles per hour. Full head and tail-light equipment, \$2800.



**KING FOLDING CANVAS BOATS**  
Are lighter and more durable than wood. Puncture-proof; non-sinkable; cannot tip over. A revelation in boat construction. Can be carried anywhere by hand or on bicycle or in buggy, or checked as baggage. When not in use, Fold Up Into a Package. Handsome catalog 6c. in stamps.  
**KING FOLDING BOAT CO., 688 North Street, KALAMAZOO, MICH.**

**STATIONARY ENGINEERS**  
desiring to fit themselves for better paying positions should send for 300-page handbook (FREE) describing our Stationary Engineering course, and over 60 other courses, including Electrical, Mechanical and Civil Engineering, Architecture, Mechanical Drawing, Structural Drafting, Telephony, Textiles, etc.  
**American School of Correspondence, Chicago, Ill.**

**Signs, Boxes, Souvenirs & Novelties**  
of Aluminum in any number, style or design. Lithographed metal signs, boxes, jars, etc. Enameled Iron Signs of all colors. Designs, estimates and catalogue. N. J. Aluminum Co., 150 Nassau St., N. Y. H. M. Willis, Mgr.

**LET US BE YOUR FACTORY**  
WRITE FOR ESTIMATE ON ANY ARTICLE YOU WANT MANUFACTURED  
**STAMPINGS, MODELS, EXPR. WORK**  
WRITE FOR FREE BOOKLET  
**THE GLOBE MACHINE & STAMPING CO.**  
970 Hamilton St., Cleveland, O.

**MACHINERY AND SPECIAL PARTS**  
new devices developed; successful experimental work done speedily; skilled labor; good facilities; good value for your money.  
**J. R. ENGELMAN MFG. CO.**  
74 Hudson St. near Penn. Depot, Jersey City

**ICE MACHINES** Corliss Engines, Brewers and Bottlers Machinery. THE VILTER MFG. CO., 899 Clinton St., Milwaukee, Wis.

**MODELS & EXPERIMENTAL WORK.**  
Inventions developed. Special Machinery.  
**E. V. BAILLARD, 24 Frankfort Street, New York.**

**RUBBER** Expert Manufacturers Fine Jobbing Work  
**PARKER, STEARNS & CO., 228-229 South Street, New York**

**MODELS & CHICAGO MODEL WORKS**  
ESTABLISHED 1867 179 E. MADISON ST. CHICAGO, ILL. WRITE FOR CATALOGUE OF MODEL SUPPLIES.

**Foot and Power Lathes**  
Send for catalogue and prices  
**Carroll-Jamison Machine Tool Co., Batavia, Ohio**

**MODELS & INVENTIONS PERFECTED**  
UNION MODEL WORKS  
193 So. CLARK ST. CHICAGO.

**NOVELTIES** and Patents required for English market. Send samples and write W. TUCKER & COY, 16 and 17 Devonshire Square, London, E. C., England.

**Dies, Tools, Models and Special Machinery.**  
HOEFFT & MOORE, Chicago, U. S. A.  
OFFICE: 858 FIFTH AVENUE WORKS: INDIANA & FRANKLIN STREETS

**STEEL TYPEWRITER TYPE**  
We make, or will furnish complete outfit for making, all styles. **NEW YORK STENCIL WORKS,** 100 Nassau Street, New York.

**WANTED MASTER MECHANIC,** competent to take charge of large general manufacturing plant, in New Jersey. First-class references required. Address **MECHANIC, 794 Broad St., Newark, N. J.**

**MOTOR BOAT SUPPLIES** Batteries, Coils, Plugs, Whistles, Tools and all Accessories. Catalog on request. **BECKLEY-RALSTON CO., 86 Michigan Av., Chicago.**

**MODEL AND EXPERIMENTAL WORK.**  
Electrical and Mechanical Instruments. Small Mach'y  
**EDWARD KLEINSCHMIDT, 82 W. Broadway, New York**

**TELESCOPES**  
SEND FOR CATALOGUE  
**W. & D. MOGEY,** BAYONNE CITY, N. J.

**SETS OF CASTINGS OF MODEL ENGINES**  
SEND 10¢ FOR 126 PAGE ILL. CATALOGUE. ALSO TOOLS, GEAR WHEELS & PARTS OF MODELS  
**GOODNOW & WIGHTMAN**  
Removed to 132 Milk Street.

**WANTED**  
TEN MILLION, FIRST QUALITY, 3-16 IN. STEEL BALLS  
Address **Richardson Ball Bearing Skate Co.** 501 Wells St., Chicago, Ill.

**Watch Tacoma Grow!**  
POPULATION 1900, 37,714. 1906, 85,000.  
Leading manufacturing city of Pacific Northwest. Best steamship and railway terminals on Pacific Coast. Six additional transcontinental railroads entering Tacoma. Send ten cents in postage for illustrated literature to SECRETARY, CHAMBER OF COMMERCE AND BOARD OF TRADE, Tacoma, Wash.

**DON'T BUY GASOLINE ENGINES**  
all one-cylinder engines revolutionizing gas power. Costs Less to Buy and Less to Run. Quickly, easily started. No vibration. Can be mounted on any wagon at small cost—portable, stationary or traction. Mention this paper. SEND FOR CATALOGUE. **THE TEMPLE PUMP CO., Mrs. Meagher & 15th Sts., Chicago.**

**UNTIL YOU INVESTIGATE "THE MASTER WORKMAN,"**  
a two-cylinder gasoline engine superior to all styles. NEW YORK STENCIL WORKS. THIS IS OUR FIFTY-SECOND YEAR.

# New York Belting and Packing Co.

LIMITED


Manufacturers of High Grade

## Rubber Belting

Diaphragms, Dredging Sleeves, Emery Wheels; Air Brake, Steam, Suction and Garden Hose, etc., Mats, Matting, Interlocking Rubber Tiling. Also manufacturers of moulded and special rubber goods of every description.

Write for catalogue.

91-93 Chambers St., New York



## CHARTER

Stationaries, Portables, Hoisters, Pumps, Sawing and Boat Outfits, Combined with Dynamos.

Gasoline, Gas, Kerosene.

Send for Catalogue.

State Power Needs.

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

**Scales** All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Scales, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free CHICAGO SCALE CO., Chicago, Ill.

## What Is Daus' Tip-Top?



TO PROVE that Daus' "Tip-Top" is the best and simplest device for making 100 copies from pen-written and 50 copies from typewritten original, we will ship complete duplicator, cap size, without deposit, on ten (10) days' trial. Price \$7.50 less trade discount of 33% per cent, or \$5 Net

The Felix A. B. Daus Duplicator Co., Daus Bldg., 111 John St., New York

## TOOL KNOWLEDGE CHEAP



In fact you can have it free! This cut represents our new Tool Catalogue No. 22. It is cloth-bound and contains 950 pages all about Tools. Full descriptions and thousands of illustrations. Sent post-paid on receipt of \$1.00 which is refunded on your first purchase from us of \$10.00 or over.


MONTGOMERY & CO.  
105 Fulton St., N. Y. City

## Bausch & Lomb Microscopes

This is an invitation to send for our illustrated catalog of Microscopes if you are interested in best instruments for the least money, those that are used in the leading laboratories everywhere and by individual workers who know the best.

Bausch & Lomb Optical Co.  
MANUFACTURERS  
ROCHESTER, N. Y.NEW YORK CHICAGO BOSTON  
SAN FRANCISCO FRANKFORT A-M GERMANY

## IT PAYS BIG To amuse the Public With Motion Pictures



NO EXPERIENCE NECESSARY as our instruction Book and "Business Guide" tells all. We furnish Complete Outfits with Big Advertising Posters, etc. Humorous dramas brimful of fun, travel, history, religion, temperance work and songs illustrated. One man can do it. Astonishing Opportunity in any locality for a man with a little money to show in churches, school houses, lodge halls, theatres, etc. Big profits each entertainment. Others do it, why not you? It's easy; write to us and we'll tell you how. Catalogue free.

AMUSEMENT SUPPLY CO., 467 Chemical Bank Bldg., CHICAGO.

## MOTSINGER AUTO-SPARKER



starts and runs

Gas Engines without Batteries.

No other machine can do it successfully for lack of original patents owned by us. No twist motion in our drive. No belt or switch necessary. No batteries whatever, for make and break or jump-spark. Water and dust-proof. Fully guaranteed.

MOTSINGER DEVICE MFG. CO.  
14 Main Street, Pendleton, Ind., U. S. A.

**HELMETOIL LUBRICATES ANYTHING.**  
IF YOU HAVE A HOT BOILER TRY IT. CHESLEY & CO.  
CHICAGO, ILL. U.S.A.  
15 to 21 South Clinton Street.

## TOPPAN Power Dories and Whale Boat Launches

SAFE	PRICES
DORIES	
18 feet,	\$195.00
20 "	240.00
22 "	275.00
26 "	385.00
30 "	525.00



SPEEDY	PRICES
LAUNCHES	
18 feet,	\$240.00
20 "	290.00
22 "	325.00
25 "	450.00
30 "	575.00

EXTRA FOR TRUNK CABIN ON 26 FT., \$55; ON 30 FT., \$70. ALSO SPEED BOATS.

ENGINES: Toppa-Simplicity; Also Termaat & Monahan in Stock  
Special 15-Ft Fishing Dory, \$125; 1 1/4 H. P. Engine.  
TOPPAN BOAT MANUFACTURING CO., 10 Haverhill St., BOSTON, MASS., U. S. A.  
Send 2 stamps for New 1906 Catalogue

## WHICH FLOOR DO YOU PREFER?

If the one to the right let us tell you how easily it is done in thousands of homes by the use of

**Grippin's Floor Crack Filler and Finishes,**

Our improved method of finishing all floors. Sanitary, simple and inexpensive. Skilled labor is not necessary.

BEFORE TREATMENT

Write NOW for descriptive matter to

**GRIPPIN MFG. CO., Dept. 6**  
NEWARK, NEW YORK STATE  
AFTER TREATMENT

## Civil Engineering and Surveyors' Instruments

DRAWING INSTRUMENTS, MATERIALS AND SUPPLIES

We are the largest house in the world. Try us on BLUE PRINT PAPER, TRACING CLOTH, DRAWING INKS, or SURVEYING and ENGINEERING INSTRUMENTS

A. S. ALOE CO., 507 Olive Street, - - - St. Louis, Mo.

Write for Catalog.

"Sent Free."

Correspondence Solicited.

## STEAM USERS

### Rainbow Packing

The original and only genuine red sheet packing.

The only effective and most economical flange packing in existence.

Can't blow Rainbow out.

For steam, air, hot or cold water, acid and ammonia joints.

Beware of imitations.

Look for the trade mark—the word Rainbow in a diamond in black, three rows of which extend the full length of each roll.


Manufactured exclusively by  
**PEERLESS RUBBER MFG. CO.**  
16 Warren St., New York

## Slate Gives Place to Taylor Old Style Tin After Eighty Years' Trial

The roof of the old Franklin Institute, one of Philadelphia's most cherished landmarks, had given trouble for nearly eighty years. Although an institution having for its purpose the promotion of the mechanic arts, its own roof history has been a continuous round of inspecting, repairing and replacing. Recently a committee, delegated to select the best roofing material obtainable, decided in favor of "Taylor Old Style" tin, and this historical structure now has a roof that will undoubtedly out-live the building. Taylor Old Style tin was probably never selected for a more important purpose, or by a more competent committee.

Our booklet, "A Guide to Good Roofs," will interest all who are interested in good roofs.

**N. & G. TAYLOR COMPANY**  
ESTABLISHED 1810  
Philadelphia



COMPLETE  
20 LIGHT  
OUTFIT  
\$450.

We have complete

Outfits for . . .

## YOUR OWN ELECTRIC LIGHTS

Any size place, summer homes, launches, yachts, etc. Every detail included; very best material; practical. So simple no electrician required. **Light All the Time**, as storage battery included. Gas, Gasoline or Steam engines used give plenty of power for pumping water, sawing wood, refrigeration, etc. For our new 56-page Catalogue describing over 100 different outfits, address

ELECTRIC DEPARTMENT

RICHARDSON ENGINEERING CO., Hartford, Conn.

## "HE'S VERY QUICK AT FIGURES" "ALRIGHT, GIVE HIM THE JOB"

CAN THIS BE SAID OF YOU?

This Book, "RAPID CALCULATION," will give you in a very short space and with little effort, the new system of lightning calculation for business use, that has been discovered after life study by an expert calculator. Your salary is bound to grow if you can do your figuring more quickly and correctly than the usual run of business men.

Don't waste time thinking it over. Send at once, now, when you read this

"Putting Off is the Thief of Opportunity"

**SPECIAL OFFER.**—To any reader who sends in the page number on which this adv. is printed, a copy of "Rapid Calculation" will be sent FREE. This is your chance to increase your salary at the cost of a 2c. stamp.

Commercial Correspondence Schools, 390 c Commercial Bldg., Rochester, N. Y.


"The Queen"  
15 foot row boat, as illustrated. Complete with one pair oars \$29.00

**Mullins Pressed Steel Boats Can't Sink**  
Easier to Row—Absolutely Safe

Made of pressed steel, with air chambers in each end like a life boat. Can't leak—crack—dry out or sink—last a lifetime. Every boat guaranteed. The ideal boat for families—summer resorts—parks—boat livery, etc. Strong—Safe—speedy. Write today for our large catalog of row boats, motor boats, hunting and fishing boats.

The W. H. Mullins Co., 118 Franklin St., Salem, O.

## COLD GALVANIZING. AMERICAN PROCESS. NO ROYALTIES. SAMPLES AND INFORMATION ON APPLICATION.



### NICKEL

Electro-Plating

Apparatus and Material.

THE

Hanson &amp; Van Winkle

Co.,

Newark, N. J.

92 William St., N. Y.

30 &amp; 32 S. Canal St. Chicago.

**MOTOR BOAT PERFECTION**

At popular prices, free from complications and care is a 20th Century Possibility. LET US SHOW YOU.  
122 W. 34th St., New York, N. Y. 1321 Michigan Ave., Chicago, Ill.  
182 Jefferson Ave., Detroit, Mich. 38 Delaware Ave., Camden, N. J.  
509 Tremont St., Boston, Mass. 391 First Ave., S. Seattle, Wash.  
And All Other Principal Cities. If interested in Steam or Sail Yachts, Motor Boats, Row Boats, Hunting Boats, Dingies, Canoes, Engines and Boilers, write us. SATISFACTION GUARANTEED.

Racine Boat Mfg. Co., Box 35, Muskegon, Mich

**Canoes \$31.50 Up**

Best Cedar, canvas covered—highest possible quality—prompt deliveries. Write for 1906 Catalogue No. 5

**FRASER HOLLOW SPAR & BOAT CO.**  
Greenport, Suffolk Co., L. I., N. Y.

## Boats Knocked Down

We do the work—you nail together. You save one-half the boat factory's price and get a better boat. You can finish it to suit your own requirements. Every part is perfectly fitted. Instruction sheets to guide you through entire work. Our price for the fitted parts is about equal to what the rough lumber would cost you. Cost for freight is low. Materials for a 35-foot boat can be shipped to New York for \$10.50. Every boat is especially designed to suit purchaser. Materials are furnished for boats of any length, any width, any depth, any model. Write for catalog to-day.

**FRED MEDART, St. Louis, Mo.**  
Originator of the knocked-down boat system

## Motion Picture

MACHINES and FILMS  
STEREOPTICONS and SLIDES

For Public Entertainments, in Theatres, Halls, Show Tents, etc. Catalogue No. 9 Free

KLEINE OPTICAL CO., 52 State St., Chicago, Ill.

## A Chain Drill

that is built right—not only in spots, but all the way through. It has a three-jawed chuck for holding round shank drills 0 to 1/2 inch. The square shank style can't come within a mile of it for accuracy. \$5.00 each. This **Automatic Drill** is made in the shops of

GOODELL-PRATT COMPANY, Greenfield, Mass.

Send for catalogue—free.

## MAGIC LANTERNS

Stereopticons and Moving Picture Machines—all sizes, all prices. Views illustrating timely subjects. Fine thing for Church and Home Entertainments. Men with small capital makemoney giving public exhibitions. Illustrated catalogue free.

McALLISTER, 49 Nassau St., New York.

## The MEASURE OF ALL TYPEWRITERS



### Commercial Brains

measure every typewriter—quality for quality—attribute for attribute—by the

## Underwood

How approach it in responsiveness—in mechanical perfection. How resemble it in appearance, design and finish. Its increasing fame makes permanent the Standard—


THE ORIGINAL OF ITS KIND  
Imitations are Never so Good

**UNDERWOOD TYPEWRITER CO.,**  
241 Broadway, New York.



# Important Announcement

AT LAST AMERICA HAS A NATIONAL REFERENCE WORK, IN WHICH NORTH, SOUTH, EAST, WEST, CANADA AND SOUTH AMERICA HAVE FULL AND TRUE REPRESENTATION.



READERS OF THE SCIENTIFIC AMERICAN will be gratified to learn that the great work of reference upon which we have been so long engaged is at last completed. After years of patient labor and research and with the co-operation of America's foremost scholars and experts,

## The New AMERICANA

stands as an achievement which has already met with the enthusiastic approval of the American people. It is now no longer necessary to consult foreign works of reference for information concerning American Biography, American History, American Industries, and our American Institutions.

The AMERICANA is the work which the condition of affairs in the Encyclopedic world made necessary. Before ever a line was written for this great work the *Ideal* was set: *A National Work—Universal in its information—American in its Production.*

The AMERICANA is distinctly a National Work. It is made by Americans. Every section of America has been called upon to contribute, and for the first time in a reference publication North, South, East and West, Canada and South America have full and true representation.

The AMERICANA is NEW FROM COVER TO COVER—new and beautiful type, new maps, new engravings and colored plates, new text illustrations, and, best of all, NEW AND ORIGINAL TREATMENT THROUGHOUT by the foremost

### American Expert Authorities.

The AMERICANA is the work of a thoroughly organized body of skilled experts each selected for his special fitness and intimate knowledge of the subject assigned to him. These trained and progressive workers have struck out into *new paths*; they have proceeded upon an *entirely new plan* and that plan embodies the idea which has advanced our country to the front rank among the nations—the idea of *reaching the core of things by the shortest method*. This is the *American Plan*. You'll catch the spirit of it as you turn the pages of the work and note its conciseness yet comprehensiveness, while the names of the eminent writers of the signed articles are an ample assurance of accuracy and authoritativeness. The AMERICANA has commanded the services of so many distinguished educators, scholars and experts as to justify in the truest sense the title bestowed upon it—

## "America's National System of Reference."

"I am truly delighted with the tone and arrangement of this strictly American publication."—B. J. CIGRAND,  
Director Chicago Public Library.

"The treatment throughout is thoroughly American and conspicuously so in its wonderful compression. It goes straight to the core of each subject."  
—EDGAR M. BARBER, C. P. A.,  
U. S. Treasury Dept.

"The work breathes the spirit of to-day even in the description of things ancient. It explores the dark corners of the past by the aid of the arc light and radium."  
—ST. PAUL PIONEER PRESS.

"I consider it in every respect, the best encyclopedia published."  
—P. N. JOHNSTON,  
Reference Librarian, New York Public Library.

### FREE ON REQUEST

No mere advertisement can convey an adequate idea of the vast interest and immense utility of the AMERICANA, or of its exceptional value and sumptuous appearance. Let us send you therefore a handsome 120-page book containing specimen pages, maps, full-page plates, duo tones, color plates, and text illustrations, with portraits of celebrities, full-page photographic plates of the most interesting and up-to-date subjects—*The Americana* being the best illustrated of all reference works. With the object of making the Americana quickly and widely known, before placing the work in the hands of dealers for general distribution, we will accept orders direct at a large reduction from the established price. Those interested are requested to make application immediately. The work is sold exclusively in connection with the SCIENTIFIC AMERICAN, and cannot be otherwise obtained.

**SEND IN  
AT ONCE**

REQUEST BLANK

SCIENTIFIC AMERICAN COMPILING DEPT.  
258 Fifth Ave., New York City

Without obligating myself to purchase I would like to receive FREE, your 120 page Book of Specimen Pages, Maps, Duo tones, Color Plates, Portraits, etc., of the NEW AMERICANA, with particulars of your special low price advertising proposition.

Name .....

Occupation .....

Street .....


Town and State .....

CUT OUT AND MAIL TO-DAY



# SPEEDWAY

## Gasolene Marine Engine



Best in Design. Best in Material.  
Best in Workmanship. Best in Method.  
Best that Money Can Buy.

We build also Steam and Sail Yachts, Gasolene and Naphtha Launches, Steel and Wood Vessels. Marine Steam Engines and Boilers. Twenty years experience in this line.

**GAS ENGINE & POWER CO.**  
and **CHAS. L. SEABURY & CO.**

CONSOLIDATED

Morris Heights, New York City

Send 10 cents stamp for illustrated catalogue.

Member of the National Association of Engine and Boat Manufacturers.

# Waterman's Ideal Fountain Pen

The pen with the Clip-Cap

### In Coat



Holds pen firmly in coat pocket, inside or outside.

### In Vest




Holds the pen rigidly and securely—never drops out.

### On Blouse or Shirt



Can be clipped on the front of shirt, blouse or waist.

### In Belt



Can be held right side up even on the belt, as shown.

**No Danger** of loss with the Ideal Clip-Cap attached to your fountain pen.

Riding or Driving, Steaming or Sailing, Hunting or Fishing, Working or Playing, Indoors or Out this little thing means that your pen is always at hand.

You can carry it safely in any pocket—even if you haven't got a pocket you can hang it on your shirt or belt.



## Waterman's Ideal Fountain Pen

is made in many different sizes with all grades of pen points, at varying prices from \$2.50 upward. It is the "Standard of the World" because it feeds easily and constantly and never sputters, spills or balks.

All reputable dealers carry them—others carry imitations.

Our booklet will educate you on many different grades your dealer can procure.

Ask for "Points for Penmen, Edition A."

**L. E. Waterman Company,**

173 Broadway, New York

209 State Street, Chicago

8 School Street, Boston

136 St. James Street, Montreal


18 Geary Street, San Francisco

SEND FOR CATALOGUES OF

# LOZIER HIGH GRADE MOTOR BOATS MARINE MOTORS

BOOK EIGHTEEN


Our line of Stock Boats for 1906 includes our Special 20-foot \$325 Open Boat (with 3 H. P. Lozier Motor)—of which so many were sold last season—and our Regular 21-foot 3 H. P. and 26-foot 5 H. P. Open Boats, at respectively \$600 and \$800. This is a fine line of high-grade boats whose increasing popularity from year to year warrants our building them for 1906 in larger quantities than ever before.



21-FOOT OPEN BOAT, 3 H. P.



FOUR-CYCLE MOTOR, 25 H. P.



BOOK TWENTY-ONE

The Marine Motor Line is a most complete one, including both Two-cycle and Four-cycle Types, in Single-cylinder, Double-cylinder and Four-cylinder construction. The Two-cycle line includes 3, 5 and 7 1/2 H. P. sizes in Single-cylinder, and 10 and 15 H. P. Double-cylinder. The Regular Four-cycle line includes 20 H. P. Double-cylinder and 40 and 55 H. P. Four-cylinder. Our Special lightweight 25 H. P. Four-cycle Motor weighs with clutch and bed-plate only 775 lbs.

**THE LOZIER MOTOR CO.**

1733 BROADWAY, NEW YORK CITY

Western Agent, DAN B. SOUTHARD, 149 Michigan Ave., Chicago, Ill.  
NICHOLLS BROS., Limited, Toronto, Ontario, Agents for the Province of Ontario, Canada



Every Owner and Chauffeur should enter our

**\$1000**

**Tire Economy**

**Competition**

which, even for those participants who win no cash prizes, will be the means of tremendous saving in the tire expense item for the year.

Particulars on request.

**We Stand for Tire Economy**

and our tires are built for that principle

The cost of upkeep of the car equipped with Pennsylvania Clinchers—if our instructions on usage are followed—will at least be very reasonable.

**PENNSYLVANIA RUBBER CO. JEANNETTE, PA.**

NEW YORK, 1665 Broadway

PHILADELPHIA, 615 N. Broad Street

LONDON, 4 Snow Hill

BOSTON, 167 Oliver Street

CHICAGO, 166 Lake Street